

MAY YES



United States Department of Commerce National Bureau of Standards Building Materials and Structures Report 136

BUILDING MATERIALS AND STRUCTURES REPORTS

On request, the Superintendent of Documents, U. S. Government Printing Office, Washington 25, D. C., will place your name on a special mailing list to receive notices of new reports in this series as soon as they are issued. There will be no charge for receiving such notices.

If 100 copies or more of any report are ordered at one time, a discount of 25 percent is allowed. Send all orders and remittances to the Superintendent of Documents, U. S. Government Printing Office, Washington 25, D. C.

The following publications in this series are available by purchase from the Superintendent of Documents at the prices indicated:

BMS1	Research on Building Materials and Structures for Use in Low-Cost Housing	*
BMS2	Methods of Determining the Structural Properties of Low-Cost House Constructions	10¢
BMS3	Suitability of Fiber Insulating Lath as a Plaster Base	15¢
BMS4	Accelerated Aging of Fiber Building Boards	10¢
BMS5	Structural Properties of Six Masonry Wall Constructions	20¢
BMS6	Survey of Roofing Materials in the Southeastern States	*
BMS7	Water Permeability of Masonry Walls Methods of Investigation of Surface Treatment for Corrosion Protection of Steel	*
BMS8	Methods of Investigation of Surface Treatment for Corrosion Protection of Steel	15¢
BMS9	Structural Properties of the Insulated Steel Construction Co.'s "Frameless-Steel" Con- structions for Walls, Partitions, Floors, and Roofs	10¢
BMS10	Structural Properties of One of the "Keystone Beam Steel Floor" Constructions Spon- sored by the H. H. Robertson Co	10¢
BMS11	Structural Properties of the Curren Fabrihome Corporation's "Fabrihome" Construc- tions for Walls and Partitions	10¢
BMS12	tions for Walls and Partitions. Structural Properties of "Steelox" Constructions for Walls, Partitions, Floors, and Boofs, Sponsored by Steel Building, Inc.	156
BMS13	Roofs, Sponsored by Steel Building, Inc Properties of Some Fiber Building Boards of Current Manufacture	*
BMS14	Indentation and Recovery of Low-Cost Floor Coverings	10¢
BMS15	Indentation and Recovery of Low-Cost Floor Coverings. Structural Properties of "Wheeling Long-Span Steel Floor" Construction Sponsored by the Wheeling Corrugating Co	106
BMS16	by the Wheeling Corrugating Co Structural Properties of a "Tilecrete" Floor Construction Sponsored by Tilecrete Floors, Inc	
BMS17	Sound Insulation of Wall and Floor Constructions	206
Supplemen	t to BMS17, Sound Insulation of Wall and Floor Constructions	56
Supplemen	t No. 2 to BMS17, Sound Insulation of Wall and Floor Constructions	154
BMS18	Structural Properties of "Pre-fab" Constructions for Walls, Partitions, and Floors	100
	Sponsored by the Harnischfeger Corporation	10¢
BMS19	Preparation and Revision of Building Codes	Ť
BMS20	Structural Properties of "Twachtman" Constructions for Walls and Floors Sponsored	10¢
BMS21	Structural Properties of a Concrete-Block Cavity-Wall Construction Sponsored by the	
BMS22	National Concrete Masonry Association	*
BMS23	Structural Properties of a Brick Cavity-Wall Construction Sponsored by the Brick	104
BMS24	Structural Properties of a Reinforced-Brick Wall Construction and a Brick-Tile Cavity-	
	Wall Construction Sponsored by the Structural Clay Products Institute	15¢
BMS25	Wall Construction Sponsored by the Structural Clay Products Institute Structural Properties of Conventional Wood-Frame Constructions for Walls, Partitions, Floors, and Roofs	206
BMS26	Floors, and Roofs	104
BMS27	Sponsored by the Nelson Cement Stone Co., Inc Structural Properties of "Bender Steel Home" Wall Construction Sponsored by the Bender Body Co	104
BMS28	Backflow Prevention in Over-Rim Water Supplies	15
BMS29	Survey of Boofing Materials in the Northeastern States	204
BMS30	Survey of Roofing Materials in the Northeastern States_ Structural Properties of a Wood-Frame Wall Construction Sponsored by the Douglas	154
BMS31	Fir Plywood Association Structural Properties of "Insulite" Wall and "Insulite" Partition Constructions Sponsored by the Insulite Co	*
BMS32	Sponsored by the Insulite Co	154
BMS34	Wall Construction Sponsored by the National Concrete Masonry Assoc Performance Test of Floor Coverings for Use in Low-Cost Housing: Part 1	154
BMS36	Structural Properties of Wood-Frame Wall, Partition, Floor, and Roof Constructions	10¢
11000	With "Red Stripe" Lath Sponsored by the Weston Paper and Monufacturing Co	104
BMS38	With "Red Stripe" Lath Sponsored by the Weston Paper and Manufacturing Co Structural Properties of Two "Dunstone" Wall Constructions Sponsored by the W. E. Dunn Manufacturing Co	10¢
*Out of print.		- op
ouvor print.		

†Superseded by BMS116.

[List continued on cover page III]

Properties of Cavity Walls

Daniel S. Goalwin



Building Materials and Structures Report 136

Issued May 20, 1953

For sale by the Superintendent of Documents, U. S. Government Printing Office, Washington 25, D. C. Price 15 cents

Contents

		rase
1.	Introduction	. 1
2.	Cavity-wall design	. 1
3.	Materials	. 2
4.		
	4.1. Workmanship	4
	4.2. Construction details	
5.	Structural properties	
~.	5.1. Compressive load	
	5.2. Transverse load	
	5.3. Concentrated load	
	5.4. Impact load	
	5.5. Racking load	
6	Water permeability	
0.	6.1. Method of testing	
	6.2. Test results	
7.	Heat transfer	
	7.1. Test equipment and procedure	. 10
	7.2. Test results	
8.	Fire resistance	12
	8.1. Test specimens	. 12
	8.2. Test results	13
9.	Discussion and summary	14
10.	References	15

Properties of Cavity Walls

Daniel S. Goalwin

A compilation is given of data on the performance characteristics of cavity walls, including previously published and some hitherto unplublished material. Structural tests were conducted on cavity walls of brick, concrete block, and structural clay tile. Other tests were made on the properties of wall ties, rain penetrability, thermal transmittance, and fire resistance.

Under certain conditions of loading, compressive strength, resistance to concentrated load, racking load, and impact strength were found to be roughly equivalent to those of conventional walls using the same quantity and quality of material. With respect to resistence to transverse load, the cavity walls were somewhat inferior. When properly flashed and with suitable weep holes, the cavity walls had satisfactory resistance to rain penetration. Their thermal transmittance was about 25 percent lower than for similar solid walls. Their resistance to the effect of fire was satisfactory provided certain limiting loading conditions were met.

1. Introduction

A cavity wall is a form of masonry wall construction consisting of two parallel wythes ¹ of masonry separated by a continuous air space, or cavity, usually about 2 in. wide. It is a type of construction that has been widely used in Great Britain for many years, and which in recent years has come into greater use in this country. Cavity walls may be constructed of various combinations and thicknesses of brick, stone, structural clay tile, concrete masonry, concrete, etc.

One of the advantages claimed for the cavitywall construction is that the air space acts to prevent rain or moisture that has seeped through the outer wythe from penetrating the inner wythe. In addition, the cavity interrupts the continuity of the masonry and provides the additional insulating effect of an air space. These advantages may be lost by improper design of cavity walls, particularly with respect to such items as flashings, openings, ties, and wall intersections, or lack of care in construction.

Common practice at present is to distinguish between hollow and cavity walls. Hollow walls are walls that contain masonry bonds or bridges; these may permit the passage of water between the faces of the walls. In properly built cavity walls, there is no masonry bridge permitted between the outer and interior wythes, the two tiers being bonded by means of metallic or other nonmasonry ties to maintain a substantially constant cavity width. These ties are usually rods or wires bent into Z or rectangular shapes, affording anchorage by embedment of the ends in mortar joints.

Water that penetrates the outer leaf of a cavity wall seeps down its inner face and is diverted outward by means of flashings, generally placed near the bottom of the cavity and above windows and other openings, allowing the water to pass through weep holes in the outer face. These holes, while necessary to dispose of water, should be kept small so as to exclude rodents and to prevent any substantial circulation of air in the cavity, with consequent increase in thermal transmittance.

Tests of structural properties, fire resistance, heat transfer, and water resistance of cavity walls have been made at the National Bureau of Standards; most of these tests have been described in reports of the Building Materials and Structures series. It is the purpose of this report to collect both previously published and hitherto unpublished data so as to summarize in one report information on cavity walls required for building design, construction, and code proparation.

2. Cavity-Wall Design

Design criteria for cavity walls may be found in various reference works, including those of Fitzmaurice, "Principles of Modern Building" [1],2 Plummer, "Brick and Tile Engineering" [2], and "Tile Engineering" [3]. Design of the walls tested followed closely the general requirements for cavity walls of the "American Standard Building Code Requirements for Masonry" [4], which is now in the process of revision. Sound engineering practice requires that the compressive stresses in cavity walls shall not exceed those given in table 1. These compressive stresses are based upon the gross cross-sectional area of the wall, minus the area of the cavity between the wythes, with the assumption that the floor loads bear on but one of the two wythes. When such walls are loaded uniformly at the center of the wall, the allowable

¹ The terms "wythe" and "leaf" are used interchangeably.

 $^{^{2}}$ Figures in brackets indicate the literature references at the end of this paper.

stresses may be increased by 25 percent. When anticipated wind pressures exceed 20 lb/ft², type B mortar should not be used on cavity walls of 12-in, thickness or less.

TABLE 1. Maximum loading for masonry cavity walls

Material	stress (on g	eompressive ross less eav- id bearing on ythe).
	Type A-1 mortar ¹	Type B mortar ¹
Solid masonry units: Strength greater than 2,500 lb/in. ² Strength 1,500 to 2,500 lb/in. ² Hollow masonry units	${lb/in.^2\over 140} \ {100\over 70}$	${{lb/in.^2}\over{110}} _{80} _{55}$

¹ The mortar designations used in this paper are similar to those in the tentative ASTM Specifications for Mortar for Unit Masoury [7]. Mortar A-1 is defined as consisting of 1 part of portland eement by volume, ¹/₄ part of hydrated lime or lime putty, and aggregate in amount not less than 24 nor more than 3 times the sum of the volumes of the eement and lime used. Mortar B consists of 1 part of portland eement by volume, not less than 1/₄ parts of hydrated lime or lime putty, and aggregate in amount not less than 2/₄ normore than 1/₄ parts of hydrated lime or lime putty, and aggregate in amount not less than 2/₄ normore than 2/₄ normore than 3 times the sum of the volumes of the eement and lime used.

ASTM C270-51T requires that the average wet compressive strength of 2-ASTM C270-51T requires that the average wet compressive strength of 2in, eubes of the mortar at 28 days be not less than 2,500 lb/in.² for type A-1 and 750 lb/in.² for type B.

Cavity walls should not exceed 35 ft in height, except that 10-in. cavity walls should not exceed 25 ft in height above their support. As cavity-wall floor loads are usually carried by the inner wythe, the outer wythe is customarily 4 in. in nominal thickness, and the thickness of the inner tier is increased if needed for high walls or to support heavy loads. A nominal 10-in. cavity wall consists of two nominal 4-in. leaves and a 2-in. cavity; a nominal 14-in. cavity wall consists of a 4-in. outer leaf, a 2-in. cavity, and an 8-in. inner leaf.

The facing and backing of cavity walls should be bonded with $\frac{3}{16}$ -in.-diameter steel rods or metal ties of equivalent thickness embedded in the horizontal joints. The ties shall be spaced uniformly to provide at least one per $4\frac{1}{2}$ sq ft of wall surface; the distance between adjacent ties should not exceed 26 in. Rods bent to rectangular shape should be used with hollow masonry units laid with cells vertical; in other walls the ends of the ties should be bent to 90-degree angles to provide hooks not less than 2 in. long. Additional bonding ties should be provided at all openings, spaced not more than 3 ft apart around the perimeter and within 12 in. of the opening. Ties should be of corrosion-resistant metal or coated with a corrosion-resistant metal or other approved protective coating.

British specifications [5] require that steel wall ties be coated with zinc. They also require a crimp or dip in the ties so as to prevent water traveling across the tie to the inner wythe. If no crimp is used, the tie should be inclined downward to the outer wythe.

Because one of the purposes of the cavity is to provide a barrier against the penetration of moisture, it is essential to provide flashing wherever the cavity has been bridged for any purpose, such as heads and jambs of openings, joist bearing points, etc.

Proper drainage should be provided at the base of the cavity to dispose of any water that might penetrate into the cavity. This may be accomplished by providing weep holes in the vertical joints of the course of masonry of the outer tier immediately above a flashing. The cavity must be kept clear of mortar droppings so that the weep holes are not obstructed and so that moisture cannot be transmitted across the cavity on a bridging of mortar.

3. Materials

Tests were conducted at the National Bureau of Standards BMS101 [6] on the strength of wall ties under axial, tensile, and compressive load, and on the corrosion resistance of steel ties coated with various materials.

Table 2 lists the basic dimensions of some of the ties, partial results of compressive tests on tie assemblies, and which tie types were used in wall specimens for other tests described later in this report. Some of the ties are shown in figure 1. Outdoor-weathering specimens are shown in. figure 2.

The tensile specimens failed by pulling out of the tie, by tension failure in the tie, or by crushing of the mortar under the tie, with subsequent splitting of the brick-mortar assembly. Partial bond failure of the tie occurred in many specimens that failed in tension or by crushing of the mortar, the ends of the ties often having slipped in the bed as much as $\frac{1}{8}$ in. The compressive-strength specimens failed either by buckling of the ties or

TABLE 2. Properties of typical wall ties

Kind of material	Ove	er-all dimer	nsions	Chara		n compres- load ¹	Used in walls
Kind of material	Length	Width	Thiekness	Shape	Mortar A-1	Mort: r B	Used in wans
Copperweld Steel ² Do, ² Do, ² Do, Do	in. 6 6 6 6 6 6 6	in. $\begin{array}{c} 6\\ 6\\ 4\\ 6\\ 4\\ 4\end{array}$	in. 0.027 .188 .131 .158 .188 .250	Z-shape do Reetangular Z-shape Rectangular	<i>lb</i> . 3, 880 2, 025 600 2, 310	<i>lb</i> . 2, 180 1, 810 520 2, 060	2E. 1C, 2A, 2B, 2C, 2D, 2E, 3A, 3B, 3C, 3D. 1A, 1B, 1D, 1E.

¹ Average values were obtained from tests on groups of 5 like specimens. Compressive strengths of mortars: A-1, 4,450 lb/in.²; B, 1,330 lb/in.² . ² Average yield strength of steel wires 86,000 lb/in.², the average tensile strength 90,000 lb/in.².




FIGURE 1. Typical cavity wall ties.




FIGURE 2. Specimens for outdoor weathering of ties.

by erushing of the mortar against the ends of the ties.

Uncoated steel ties and those coated with neat cement or mortar were lightly rusted in 10 days or less of indoor (accelerated) weathering, and most were severely rusted in 30 days. Cementitious coatings did not retard rust formation and even appeared to have had an accelerating effect. Coatings of coal-tar paint afforded some protection, but within 120 days the ties were severely rusted adjacent to the masonry. It is possible that the coatings at these points were nicked with the trowel when the mortar protruding from the joints was cut away. The copper coatings on the copperweld ties were darkened by the exposure, but no evidence of rusting of the steel beneath the copper was noted.

Uncoated steel ties corroded in less time when exposed to outdoor than to indoor (accelerated) weathering. The cementitious coatings seemed to offer better protection to the ties when exposed outdoors than indoors. Ties coated with paint were moderately rusted at points adjacent to the inner faces of the masonry after 180 days of exposure.

Physical properties of the concrete blocks, brick, and tile used in tests described later in this report are listed in table 3. Details of the con-






FIGURE 3. Details of concrete-block and structural clay tile. The above include all test specimens except those used in fire-endurance tests.

		Concret	e blocks						
Used in walls	Dimensions	Dry weight	Aggre	egate	Density of	Water a hour co	absorption (24- ld immersion)	Compressive strength	
		weight			concrete	By weight	By volume of concrete	(gross area)	
1A, 1B, 1C, 1D, parts 1E-1, 1E-2 Part 1E-1. Part 1E-2.	<i>in.</i> 4.0 by 23.8 by 7.9 4.0 by 23.8 by 7.9 4.0 by 23.8 by 7.9	<i>lb/block</i> 22 31 33	Cinders Expanded slag Sand and gravel		ag 108		<i>lb/ft</i> ³ 12.7 11.1 8.4	<i>lb/in.</i> ² 900 895 860	
	Brick								
				Water a	bsorption		Modulus	Compressive	
Used in walls	Dimensions	Dry weight	5-hour bo	il Satura coefficie		nitial rate absorption		strength	
2A, 2B, 2C, 2D 3A, 3B, 3C, 3D 2E	<i>in.</i> 8.1 by 3.6 by 2.3 8.0 by 3.8 by 2.3 8.0 by 3.6 by 2.2	<i>lb/brick</i> 4.1 4.8	Percent 18.7 14.7 20.0	. 69	0. 74 . 69 . 79		$egin{array}{c c} lb/in.^2 \ 540 \ 830 \ 450 \end{array}$	<i>lb/in.</i> ² 3, 240 5, 160 3, 580	
		Ti	le						
Used in walls	Dimensions	Dry weight	Cells per tile	Thickness face shell (minimum	of of thick	o, width cell to cness of ng shell	Water absorption (1-hr boil)	Compressive strength (load applied to side)	
3A, 3B, 3D 4A-1 4A-2	<i>in.</i> 3.8 by 4.9 by 12.0 3.8 by 12.0 by 12.0 3.8 by 5.0 by 12.0	<i>lb/tile</i> 9.5 17.2 8.6	4 3 2	in. 0.4 .5 .5		2 5 5	Percent 5.9 10.2 10.7	<i>lb/in.</i> ² 1, 720 1, 040 860	

TABLE 3. Physical properties of the masonry units used in the cavity walls

1 24-hr cold ÷ 5-hr boil.
2 Gain in weight of dry brick (30 in.²) in contact with 1/8 in. of water for 1 minute.

crete block and structural clay tile (except the tile used for fire-endurance tests) are shown in The blocks were laid with the cells figure 3. vertical.

Only cement-lime mortars were used in the constructions described in this report. Definitions of the classes of mortar are taken from the ASTM Tentative Specifications for Mortar for Unit Masonry, C270-51T [7], and are given in table 1. Mortar B is the familiar 1:1:6 by volume. The amount of water added to the mortar was in each case adjusted to the satisfaction of the mason.

4. Construction of Walls

4.1. Workmanship

The walls tested fall into two general classes with respect to workmanship. Workmanship A was superior to the commercial workmanship designated as workmanship B. In workmanship A, the head or cross joints were filled solidly. In workmanship B, the mortar was applied only to the outer edges of the head or cross joints. In both workmanships, a wood strip was placed on the ties to prevent mortar droppings from fouling the ties or the weep holes.

The effect of workmanship on compressive strength of brick walls other than cavity walls is discussed in "Compressive Strength of Clay Brick Walls" [8] and on transverse strength and water permeability in "Watertightness and Transverse Strength of Masonry Walls" [9].

4.2. Construction Details

Four wall types have been tested at the National Bureau of Standards, concrete-block walls, all-brick walls, walls with brick facing and clay-tile backing, and walls with structural clay tile for both facing and backing.

Details of construction, including size, mortar, and workmanship, are given in table 4. A bricktile wall under construction is shown in figure 4.




FIGURE 4. A brick-tile cavity wall under construction for use in structural tests.

Wall No.	Type of wall	Type of tests		Reference	Nom	inal sizes	of walls	Mortar 1	Workman-
Wall IVO.			Report	Wall designation	Width	Height	Thickness	Mortar	ship 2
1A 1B 1C	Cinder-concrete block. do do	Compressive, transverse, impact. Racking Water permeability Heat transfer	BM S21 BM S21 BM S82	AX-C, AX-T, AX-1 AX-R. B123 HT-47	ft. 4 8 3 5	ft. 8 4 8	in. 10 10 10 10 ³ /	A-1 A-1 A-1	B. B. B. B.
1E-1 1E-2	Concrete block 4 do 5	Fire resistancedo	BMS117 BMS120	12	$\begin{array}{c} 16\\ 16\end{array}$	11 11	1074 10 10	B	B. B.
2A	Brick	Compressive, transverse, impact.		BD-C, BD-T, BD-L	4	8		B	
2B 2C 2D-8 2D 2E	dodo do Brick (solid) Brick do	Racking Water permeability Heat transfer do Fire resistance	BM S23 BM S82 (³) (³) (³)	B D-R. B169. H T-23. H T-24. 74, 75, 76.			93/8 8 93/8	B B B B	A. A. A. A.
3A	Brick-tile 6	Compressive, transverse, impact.	BMS24	AU-C, AU-T, AU-I	4	8		B	A (brick), B (tile).
3B	do 6	Racking	BMS24	AU-R	8	8	1	B	A (brick), B (tile).
3C 3D	do •	Water permeability Heat transfer	BMS82	B124, B271, B272 None	3 5	4 8		B	A (brick), B (tile). A (brick), B (tile).
4A	Hollow tile	Fire resistance	RP37	110, 111	8	10	10	(7)	В.

TABLE 4. Construction details of the test walls

Definitions of mortars given in table 1. Mortar B was 1:1:6 by volume. Mortar A-1 strength at 28 days exceeded 2500 lb/in.4. Mortar B strength at 28 days exceeded 750 lb/in.³.
 ² Workmanship A was superior, bead joints filled. Workmanship B was commercial, head joints buttered at the edges only.
 ³ From unpublished data.

⁴ This wall was divided into two 8- by 11-ft sections; one section of cinder units, one section of sand and gravel units.
⁵ This wall was divided into two 8- by 11-ft sections; one section of cinder units, one section of foamed-slag units.
⁶ Brick facing, tile backing.

⁷ 1:1:4 by volume. Strength at 60 days, 1,065 lb/in.².

The concrete-block walls tested for fire endurance consisted of two 8- by 11-ft sections each, separated by a ³/₄-in. air space, with blocks having different aggregates in each section. The units of one section of wall 1E-1 contained cinder aggregates, the other sand and gravel aggregates; one section of wall 1E-2 also contained cinder aggregates, the other foamed-slag aggregates.


For the walls used in the heat-transfer tests, the edges of the cavity were closed by strips of lumber and plastered over with mortar.

No finish was applied to the faces of any of the walls used in the structural or rain-penetrability tests. The concrete-block wall 1D tested for thermal transmittance had two coats of portland cement-base paint on the outside face and three coats of plaster applied directly over the inside face of the concrete blocks. The two structural clay-tile walls, 4A and 4B, tested for fire resistance, had ³/₄ in. of gypsum plaster on the exposed face and 1:3 portland-cement plaster plus 15 percent of lime on the unexposed face.

Ties were placed approximately 24 in. apart on horizontal centers in alternate bed joints for the concreté-block walls used in the structural, rain penetration, and fire-endurance tests, and in every third joint for the cinder-concrete block wall, 1D, used in the heat-transfer tests. They were placed in every sixth brick course for the brick and brick-tile walls.

5. Structural Properties

The kinds of loads encountered on exterior walls and a detailed analysis of engineering



Concrete-block cavity wall under compressive load. FIGURE 5. Load was applied through a round steel bar above beam (not visible).

principles for the design of small houses are discussed in BMS109 [10].

Three types of cavity walls were subjected to compressive, transverse, concentrated, impact, and racking loads at the National Bureau of Standards in accordance with the procedures and methods outlined in ASTM Standard E72-47T and given in BMS2 [11]; these tests are described in detail in BMS21 [12], BMS23 [13], and BMS24 [14]. At least three wall specimens were included in each test group. In general, test procedure was to apply the load in increments, recording the deflection, then release the load and record the set.

5.1. Compressive Load

With one exception, compressive loads were applied to a steel plate covering the upper end of the specimen. The load was applied uniformly along a line parallel to the inside face and onethird the thickness of the specimen from the inside face. For one set of tests on a brick cavity wall, 2A, the load was applied to one wythe only.

A wall under compressive load is shown in figure 5; data obtained from the compressive-load tests are listed in table 5 and presented graphically in figures 6 and 7.

Failure of the concrete-block cavity walls occurred by crushing of the blocks in the back wythe in one or more courses near the top of each of the specimens. Two of the brick cavity walls failed by crushing of the brick and mortar-bed joints in two or three courses of the back wythe at about. two-thirds the height, followed by rupture of both backing and face tiers at this height; one specimen failed by crushing of a few bricks and a mortar bed


TABLE 5. Results of structural tests

Figures are averages for three specimens.

			Compressive tests				Impact (maxi-	Racking		
Wall types	Mertar	Workmanship 1	Distance load applied from inside face	Maxi- mum load	Maxi- mum stress ²	Transverse tests (equivalent maxi- mum load)	mum height of drop of 60-lb sandbag)	(maxi- mum thrust ³)	Racking modulus	
Cinder-concrete block walls 1A and 1B.	1-A	B	in. 3.33	<i>lb/lin ft</i> 37, 800	lb/in. ² 394	1b/ft 2 49.8	<i>ft</i> 3.0	<i>lb/lin f l</i> 6, 010	$\frac{lb/ft.^2}{18.2 imes 10^6}$	
Brick walls 2A and 2B Brick walls 2A	B	A	3.12 ⁽⁴⁾	62, 100 50, 600	650 528	25.3	2.8	5, 660	12.7	
Brick-tile walls 3A and 3B.	B	A-brick; B-tile	3. 25	27, 800	290	21.5 (inside face)	3.7 (inside face)	5, 160	19.3	
	В	A-brick; B-tile				29.1 (outside face).	3.0 (outside face).			


¹ Workmanship A, superior. Workmanship B, commercial. ² On net area, that is, total area less area of cavity.

³ Thrust applied near upper corner. ⁴ Load applied and centered on back wythe only.



DEFLECTION, IN.

FIGURE 6. Wall shortening under compressive loads. Opening circles represent shortcnings, closed circles sets after removal of the corresponding load. Wall 1A, concrete-block cavity wall; wall 2A, brick cavity wall; wall 3A, brick-tile cavity wall.



LATERAL DEFLECTION, IN.

FIGURE 7. Lateral wall deflections under compressive loads.

Open eircles represent lateral deflections, elosed eircles lateral sets after the removal of the eorresponding load. Wall 1A, eoncrete-block cavity wall; wall 2A, brick cavity wall; wall 3A, brick-tile.

joint in the back wythe at about two-thirds the height. The load at failure of the brick cavity walls loaded on one wythe only averaged 80 percent of the load at failure of the walls loaded on both wythes. Each of the brick-tile cavity-wall specimens failed by breaking of the tile in the upper two or three courses; no failure of the brick facing was observed.

5.2. Transverse Load

Transverse load tests were made with the wall in a vertical position. Two equal loads were applied, each along horizontal lines at one-quarter of the span from the supports toward the middle of the span. The wall rested against a roller near the top and another near the bottom, separated by a span of 7 ft 6 in.; the loading rollers were thus 3 ft 9 in. apart on the loaded wythe.

A wall under transverse load is shown in figure 8. The results of the transverse load tests are presented in table 5 and the lateral deflections in figure 9.

Each of the concrete-block cavity walls failed by rupture of the bond between the blocks and the mortar in both the face and the back wythes at bed joints, usually between the loading rollers. In the brick cavity walls, the bond failure occurred near a loading roller in both the loaded and opposite faces.

Three of the brick-tile cavity walls failed by rupture of the brick-mortar bond at midheight in the facing and by rupture of the bond between the




FIGURE 8. Brick-tile cavity wall under transverse load. Loading rollers at quarter span are shown to the right of the wall.

242501 - 53 - 2




FIGURE 9. Wall deflection under transverse load.
Open circles represent deflections, closed circles sets after removal of the corresponding load. Wall 1A, concreteblock cavity wall; wall 2A, brick cavity wall, wall 3A, brick-tile cavity wall.

tile and the mortar at one or two bed joints at or between the loading rollers in the backing. For three other specimens, the bond between the tile and the mortar ruptured at a bed joint near midheight in the backing, the bond rupture on the brick face occurring at a bed joint between the loading rollers in the facing.

5.3. Concentrated Load

A concentrated load was applied through a 1-in. diameter steel disc placed against the face of the test specimen at what was thought to be the weakest place. A wall under concentrated load is shown in figure 10.

Only one specimen failed below the 1,000-lb load obtainable with the apparatus used. This was one of the brick cavity walls on which the load had been applied at a head joint. Failure of this specimen occurred by rupture of the bond between the brick and mortar at a bed joint below when a 646-lb load was applied.

5.4. Impact Load

The impact loads were applied by allowing a 60-lb sand bag to swing as a pendulum. The bag struck the wall about the midpoint between four wall ties near the center of one face of the specimen. A wall preparatory to impact is shown in figure 11. The test results are given in table 5.

For the three concrete-block cavity walls, bed joints near midheight in both the face and back




FIGURE 10. Brick cavity wall under concentrated thrust. "A" indicates the point of application of load through 1-in. disk.



FIGURE 11. Brick-tile cavity wall preparatory to impact test. Sandbag weighs 60 pounds.

wythes cracked at drops of 1.5, 2, and 2.5 ft, respectively. The tests were continued to failure, which finally occurred by displacement of the bond between the blocks and the mortar at those bed joints that had previously cracked.

For one of the brick cavity walls, a bed joint cracked near midheight at a drop of 1.5 ft, and another bed joint in the far wythe cracked at a 2.5-ft drop. A second specimen also showed a cracked bed joint at 1.5 ft. The tests were continued to failure, which finally occurred by rupture of the bond between the brick and the mortar at one or more joints on all three specimens.

For the three brick-tile cavity-wall specimens, the bond between the tile and the mortar in the back wythe ruptured transversely at or above midheight at drops of 1.5, 2, and 2 ft, respectively. The bond between the brick and the mortar in the facing ruptured transversely at or above the midspan at slightly higher drops. Both the backing and the facing finally failed by opening of these cracks or by the formation of new ones in the tile backing. For two of the specimens, both the back wythe and the face wythe failed at the same drop. For one of the specimens, the tile backing failed first, followed by failure of the brick facing at the next drop.

5.5. Racking Load

The test specimens were 8 by 8 ft, twice as large as any of the other walls for structural tests, and were braced on the lower corner to prevent horizontal sliding when thrust was applied. The loaded end was constrained from vertical movement by tie plates, but was allowed to move horizontally by a series of plates and rollers under the tie plates. The thrust was applied horizontally at the upper corner of the specimen and the



FIGURE 12. Concrete-block cavity wall under racking load. Ties at top restrict vertical motion. Compressometers measure horizontal deformation.

horizontal displacement relative to the fixed base measured at the other end of the wall (fig. 12). Test results are given in table 5.

The racking modulus given in table 5 is "the force causing a racking deformation of one foot for a wall one foot square, computed from the initial rate of deformation," reference [10]. Typical values of the racking modulus may be found in table 15 of reference [10].

One of the concrete-block walls failed by crushing of blocks in both the facing and the backing at the loaded corner. The other two failed by rupture of the blocks of both the face and back wythes approximately along a diagonal between the point of application of the load and the stop.

Two of the brick walls failed by rupture of both facing and backing along a diagonal between the point of application of load and the stop. The course of the cracks followed the joints in some places and passed directly through the brick in others. The third specimen failed by rupture of the back wythe only.

The tile wythe of each of the brick-tile walls failed by rupture between the masonry units and the mortar in the bed and head joints along a diagonal from the load to the stop. On only one of these walls did the brick facing fail.

6. Water Permeability

Because exterior masonry walls of houses on other buildings may be penetrated by wind-driven rains, with subsequent damage to the interior finish of such structures, the water permeability




FIGURE 13. Water-permeability test chamber.

of one brick, three brick-tile, and one concreteblock cavity wall was examined and is reported in BMS82 [15].

6.1. Method of Testing

The test apparatus is shown in figure 13. The wall specimens were clamped into position against sponge-rubber gaskets so that the exposed face formed one side of a pressure chamber. Water from a perforated pipe was applied to the upper portion of the exposed face (inside the chamber), the 40-gal/hr rate being sufficient to cover the wall face with a thin sheet of flowing water. The applied air pressure maintained in the chamber was equal to that produced by a 2-in. head of water (approximately 10 lb/ft ²), about the maximum pressure difference on two faces of a wall that might be caused by a 60-mph wind.

The air temperature in the testing room varied between 50° and 75° F. The walls were tested for not less than 1 day. As the backs of the walls had been painted with whitewash, the discoloration produced by moisture (dampness) on the back could be easily detected. The permeability test was more severe and of greater duration than the natural wind and rain storms to which most building walls are ordinarily subjected.

6.2. Test Results

With the exception of wall 1C, table 4, the backs of the walls remained dry during 1-day tests. Wall 1C became wet on the back above the flashing in 12 min.

The cavities in one of the brick-tile walls, 3C, was filled with 0.7 lb/ft² of shredded redwood bark; this wall was tested both before and after the cavity was filled. With the cavity open, some moisture appeared in the region around its reversed flashings in 10 hr, but in the retest, with

the cavity filled, a large damp area appeared on the back in 0.2 hr. After the tests, when the backing wythes were removed, the shredded redwood bark remained standing; water was visible at only a few points on the back of the filling, but the inside of the brick wythe was dripping wet. The filling contained about 14 percent of moisture by weight before it was placed in the wall. After the tests, it contained 50 percent of moisture at the bottom and about 20 percent at the top of the wall.

According to the Armour Research Foundation and the Structural Clay Products Institute [16], a cavity wall filled with a specially designed pouring type of fiberglas, but having no wall ties, was tested and reported to have resisted moisture penetration through the back wythe for a period of several days. Apparently there was no differential air pressure across the cavity in these tests.

7. Heat Transfer

In order to determine the thermal insulating value of a cavity wall as compared to that of a solid wall, and to ascertain to what degree the ventilation of a cavity wall with outdoor air affects its insulating value, heat-transfer tests were made by H. E. Robinson of the Bureau's staff on brick, brick-tile, and concrete-block cavity walls. A solid brick wall was tested for comparison purposes.

7.1. Test Equipment and Procedure

In the guarded hot-box heat-transfer apparatus (fig. 14), heat flowed through the specimen from the electrically heated metering and guard boxes to the cold box, which was cooled by a refrigerating machine. The guard box was used so that the space surrounding the metering box could be maintained at substantially the same temperature as the interior of the metering box. This minimized heat exchange to or from the metering box except through the specimen. To keep heat exchange through the edges of the specimen to a minimum, the top and sides were encased by an insulated wooden enclosure (not shown in fig. 14).

For testing, the specimen was placed in the apparatus, the temperature in the cold box adjusted to approximately 0° F and that in the metering and guard boxes to 70° F. Air was circulated at approximately 35° F through the enclosure along the edges of the specimen. After a state of steady heat flow was attained, the heat transmittance of the specimen, indicated by the rate at which electric energy was supplied to the metering box, was observed.

In order to determine the effect of ventilation of the cavity on the heat-transfer properties of the brick and brick-tile cavity walls, six bricks were left out of the outside wythe, three at the third and three at the thirty-second courses, leaving openings into the cavity near both the bottom and the top of the wall. In one series of tests on the brick




FIGURE 14. Test apparatus for heat-transfer measurements. To minimize heat exchange through the edges, the top and sides of the spec-imen were encased in an insulated wooden enclosure not shown in this drawing.

wall 2D, the openings in the outside face were closed with brick chinked with sponge rubber. thereby completely sealing the cavity. In another series of tests (see table 6), the openings in the outside face were partly closed with brick and sponge rubber. Openings of 4.2-in.² area, or 1.0 in.² per linear foot of wall, were left at both top and bottom. In a further series of tests, the openings amounted to 7.2 in.² in area, or 1.7 in.² per linear foot of wall, and 89.0 in.², or 21.0 in.² per linear foot, respectively.

Three series of tests were run on brick-tile cavity wall 3D, with the cavity completely sealed, with the openings between the bricks of 0.9 in.² per linear horizontal foot at both the top and bottom, and with openings totaling 2.5 in.² per linear foot at both top and bottom.

The cavity of the concrete-block wall, 1D, was not ventilated.

7.2. Test Results

The results of the tests on both ventilated and unventilated walls are given in table 6. In this table, the heat-transfer coefficients of the specimens are expressed in three ways. The observed thermal transmittance, u, is the number of Btu per hour transmitted through each square foot of the warm face of the specimen for each degree F difference in temperature of the air on the two sides of the wall, with air moving at a velocity of about 2 mph parallel to the faces on both sides of the wall. The coefficient u includes the effect of the warm-surface film coefficient f_i and the coldsurface film coefficient f_0 , the values of which for the test conditions are presented in table 6. The film coefficients are expressed in Btu per hour per square foot of surface for each degree F difference in temperature between the surface and the air.

The thermal conductance, C, of each of the specimens is also presented, representing the number of Btu per hour transmitted through each square foot of the warm face of the specimen for each degree F difference in temperature of the two faces of the wall.

It is customary to express the heat-transfer coefficient of a building wall in terms of a selected thermal transmittance, U, corresponding to conditions of still air on the warm side and air moving at a velocity of 15 mpl on the cold side of the wall. For these conditions, a value of 1.65 Btu/ $(hr)(ft^2)(^{\circ}F)$ is taken for the warm-surface film coefficient, f_i , and 6.00 for the cold-surface film coefficient, f_0 . Values of U, calculated from the test results, are presented in the table for each of the unventilated walls.

When walls 2D and 3D were tested with their cavities ventilated, the symbols u, U, C, and f_o were not applicable to the results as they are in ordinary cases because part of the heat was carried away by the ventilating air passing through the cavity. The quantity u as recorded in table 6 was in each of these cases, therefore, the observed heat flow through the area of the specimen covered by the metering box, in Btu per hour for each

TABLE 6. Heat-transfer data

	Concrete- block wall			Brick w	all 2D	Brick-tile wall 3D			
	1D (cavity un- ventilated)	brick wall 2D–S	Cavity un- ventilated	Cav	vity ventil	lated	Cavity un- ventilated	Cavity	entilated
Openings for eavity ventilation at top and bottom of wall (in.?/lin. ft of wall)	0.25 .27 .35 1.97 1.51	0. 44 . 53 . 89 1. 85 1. 64	0 .31 .35 .48 1.95 1.64 	$ \begin{array}{r} 1.0 \\ 7.2 \\ .33 \\ \overline{}, 51 \\ 1.96 \\ \overline{} \\ 13 \\ .4 \\ \end{array} $	$ \begin{array}{r} 1.7\\ 7.2\\ .34\\ \overline{},53\\ 1.89\\ 19\\ .6\\ \end{array} $	$ \begin{array}{r} 21. 0 \\ 7. 2 \\ . 45 \\ \hline . 69 \\ 1. 94 \\ \hline . 63 \\ 3. 1 \end{array} $	0 .28 .31 .41 2.04 1.46	$ \begin{array}{c} 0.90 \\ 6.8 \\ .28 \\ \hline .42 \\ 2.07 \\ \hline 7 \\ .2 \end{array} $	2, 5 6, 8 . 30

Between the air on the two sides of the wall, observed under test conditions. Between the air on the two sides of the wall, corrected for a 15-mph wind outside, and still air inside. Between the outer surface of the outer wythe and the inner surface of the inner wythe.

square foot and for each degree-F difference in temperature of the air on the two sides of the wall.

Solid counterparts of the brick-tile and the plastered concrete-block cavity walls were not tested, but it is estimated that their u values would have been about 0.38 and 0.34 Btu/(hr) $(ft^2)(^{\circ}F)$, respectively, and their U values about 0.44 and 0.38 $Btu/(hr)(ft^2)(^{\circ}F)$, respectively.

As would be expected, the measured u values of the unventilated cavity walls were considerably lower than those for their solid counterparts. The differences obtained in the *u* values of the solid and sealed-cavity counterparts were due to the insulating effect of the cavity air space, the average thermal conductance of which was approximately 1.0 Btu/(hr)(ft²)(°F).

The *u* values of the ventilated cavity walls increased as the size of the ventilating openings was made larger. Estimated rates of ventilating air flow through the cavity and estimates of the percentage of the heat entering the cavity that was carried out by the ventilating air are presented in table 6. The u values of the brick and the brick-tile cavity walls were increased very little by the ventilation resulting from openings at top and bottom of approximately 1.0 in.² per linear foot of wall.

8. Fire Resistance

Seven cavity walls were subjected to standard fire exposure according to American Standards Association Specification No. A2–1934 and the American Society for Testing Materials Specification E119-47, which require that a fire exposure with standard time-temperature relation³ shall be applied to the wall. The specifications require that the wall must carry a continuously applied load sufficient to cause the maximum allowable working stress. The first of the following criteria to occur defines failure: (1) An average temperature rise of 250 deg F or a maximum rise of 325

³ The standard furnace temperatures are: 1,000° F at 5 min; 1,300° F at 10 inn 1,550° F at 30 min; 1,700° F at 1 hr; 1,850° F at 2 hr; 2,000° F at 4 hr; min; 1,550° F at 2,300° F at 8 hr.

deg F measured with thermocouples under asbestos pads on the unexposed side of the wall, (2) the passage of heat, gases, or flame through the specimen intense enough to ignite cotton waste, or (3)structural failure.

The walls were contained within frames that were moved into place to form one side of the furnace chamber. They were restrained within the panel frame with a constant compressive load applied vertically. One wall was tested fully restrained. None of the cavities was ventilated.

8.1. Test Specimens

Two of the seven walls tested were of concrete block, three of brick, and two of structural clay tile. Construction details are given in table 4, curing and loading details in table 7. A concrete block cavity wall in position for test is shown in figure 15.

In general, a plate covering both wythes served to distribute the loads, which were applied uniformly along a line parallel to the faces of the walls. Walls 1E-1 and 1E-2 of hollow masonry units were loaded centrally, 1E-1 to 80 lb/in.2 of gross area, corresponding to 100 lb/in.² of gross less cavity area, and 1E-2 to 80 lb/in.² of gross less cavity area. The mortar of wall 1E-1 as tested in cubes averaged 1,403 lb/in.², that of wall 1E-2, 2,560 lb/in.² (both 1:1:6 by volume). These walls were described in BMS117 [17] and BMS120 [18]. The brick walls were laid in winter, and the brick were dampened only slightly. As disclosed by examination after the tests, the mortar bond was considered good.

Wall 2E-1 was loaded centrally to 236,250 lb, or 125 lb/in.², of gross area, corresponding to 156 lb/in.² of gross area less cavity area. The load on wall 2E-2 was 72,000 lb, applied 1% in. off center toward the side exposed to the fire, corresponding to an average load of 80 lb/in.² on the exposed wythe and 28 lb/in.² on the unexposed wythe. This load is representative of the actual load that

TABLE 7.	Summary	of fire-test	data
----------	---------	--------------	------

			-		Loading			Failure		
Wall	Material	Mortar (by volume)	Curing	Exposed wythe	Unex- posed wythe	Eccen- tricity	Fire intensity	Туре	Time	Maximum deflection
1E-1 1E-2	Concrete block ¹	1:1:6 (B) 1:1:6 (B)	Days 32 30	<i>lb/in.</i> ² 100 80	<i>lb/in.</i> ² 100 80	<i>in</i> . 0 0	Percent 101.2 100	Load Avg temp rise	$\begin{array}{cccc} hr & m \\ 1 & 1 \\ {}^{2} 3 & 4 \\ {}^{2} 4 & 4 \end{array}$	3 3.4 5 1.1
2E-1 2E-2 2E-3	do	1:1:6 (B) 1:1:6 (B) 1:1:6 (B)		156 80 (³)	$156 \\ 28 \\ (^3)$	$0\\158\\(^3)$	$101 \\ 100 \\ 100$	Load Avg temp rise do	$ \begin{array}{ccc} 1 & 1 \\ 5 & 1 \\ 4 & 5 \end{array} $	5 3.4
4A-1 4A-2	Hollow tile ⁴	1:1:4 1:1:4	$\begin{array}{c} 34\\ 34\end{array}$	$125 \\ 125$	$\frac{25}{25}$	$\frac{2}{2}$	96 98	do do	4 4	7 1.1 5 1.2

¹ The concrete-block walls were each divided into two separate 8- by 11-ft sections. Wall 1E-1 had one section of cinder aggregate and one section of sandand-gravel aggregate. ² First line refers to section of wall with cinder aggregate; second line to section of wall with foamed-slag aggregate.

³ Restrained from expansion in the plane of the frame.
 ⁴ Fire clay and gypsum plaster on exposed side; 1:3 cement plus 15 percent of lime on unexposed side. 4A-1 end construction; 4A-2 side construction.



FIGURE 15. Concrete-masonry cavity wall in position for fire test.

One 8- by 11-ft section consisted of cinder-concrete units, the other of sand and gravel-concrete units

would be applied to an <u>U</u>exterior wall under the limitations of some building codes.

Wall 2E-3 was tested restrained within panel frames made of 20-in. 120-lb girder beams under conditions representative of installation within the framework of fire-resistive buildings.

Gypsum plaster was applied to the exposed sides of the structural clay-tile walls, 4A-1 and 4A-2, 1:3 cement plus 15 percent of lime on the unexposed side. The load on these walls was applied 2 in. from the center toward the exposed face and resulted in an average load of 125 lb/in.² on the exposed wythes and 25 lb/in.² on the unexposed wythes. These walls are described in "Fire Resistance of Hollow Load-Bearing Walls" [19].

8.2 Test Results

The time and type of failure of the walls and maximum deflection at failure are listed in table 7. Figure 16 gives time-temperature curves for one of the brick walls, 2E-2. Two of the walls collapsed under load after approximately 1¼ hr of fire exposure; all the others withstood the fire and failed by the temperature-rise criterion at times of 3¾ hr or more. The temperatures on the exposed faces of all the walls were similar at corresponding phases of the tests. The walls which failed structurally, 1E-1 and 2E-1, showed much larger deflections than the others; for in-




FIGURE 16. Time-temperature curves for a brick cavity wall F, Furnace temperatures; I, temperatures in the cavity; P, unexposed-surface temperatures.

stance, the maximum deflection of wall 1E-1 at 1 hr 10 min was 3.4 in. compared to a maximum deflection of wall 1E-2 at 4 hr 40 min of only 2.4 min.

Wall 1E-1 was loaded centrally to 100 lb/in.² of gross area less cavity area; the maximum allowable compressive load for this type of construction loaded centrally is given in reference [4], subsequently developed, as 63 lb/in.², and in the tentative revision (table 1, footnote) as 69 lb/in.². Wall 1E-1 also used a weaker mortar than wall 1E-2.

Wall 2E-1 was loaded centrally to 156 lb/in.² of gross area less cavity area; the maximum allowable compressive load for this type of construction loaded centrally is given in reference [4] as 125 lb/in.² and in the tentative revision (table 1, footnote) as 100 lb/in.².

The distance from the center point of the wall at midheight and the line of application of load becomes smaller as bowing takes place during fire exposure only when the load is applied eccentrically toward the exposed (back) wythe; this type of loading thus tends to be more stable than central, or uniformly distributed, loading. For example, for a centrally loaded wall and a 3-in. bow, the line of loading would be about 2 in. from the outside face of the outer wythe at the midheight of the wall. Because the most severe exposure is on the inside of a structure, and as cavity walls are used predominantly as exterior walls, eccentric loading toward the exposed face is not only favorable to a longer fire endurance but also represents the usual application.

In none of the tests did the temperature in the cavity become high enough to cause failure of the metal ties. Although these cavity walls were tested unventilated, experience with fire-endurance tests of walls with large cracks indicates that the fire endurance would not be materially affected by weep holes.

As supplemental information, the fire resistance for some unventilated cavity walls with and without plaster and with and without combustible members framed into the wall are presented in table 8.

Table 8 is adapted from National Bureau of Standards Building Materials and Structures Report BMS92 [20]. The fire-resistance ratings apply where the mortar mixes are not leaner than, 1:1:6 for brick and concrete blocks, and not leaner than 1:1:4 for structural clay tile. Loads are assumed to be applied eccentrically. Ratings were generally rounded off to a period just shorter than the test results; some of the ratings were obtained by S. H. Ingberg by interpolating or extrapolating actual test data. The effects of plaster were derived from test results and accepted formulas. The thicknesses for which endurance ratings are given are those most likely to be found in building construction. Ratings for plastered brick and concrete-block walls are for ½-in. plaster thickness and for structural clay tile are for %-in. thickness inside and ³/₄-in. portland-cement stucco outside.

9. Discussion and Summary

No failure of the ties was observed in the structural tests listed in table 4. However, tests on wall-tie assemblies, described in BMS101 [6], indicated the importance of the mortar in determining the type of the failure and under what conditions it would occur. Thus, for 1,000-lb/in.² mortar, a typical assembly tested in compression failed by buckling of the ties; for 270-lb/in.² mortar, specimens failed by crushing of the mortar against the ends of the ties.

Assuming a tie spacing of one per $4\frac{1}{2}$ ft² of wall area, any of the 6-, 8-, or 10-gage steel or copperweld Z-shaped or rectangular ties provided adequate bonding between the two wythes to maintain the relative positions of the wythes against the usual lateral loads to which such walls may be subjected. Ties in cavity walls are intended to connect the two tiers and to serve as

TABLE 8. Estimated fire resistance of cavity walls

Interpolated results taken from BMS92. All the walls have 2-in, wide cavities; all are loading-bearing. Where plaster is indicated, it is assumed to be not less than ½-in, of 1:3 sanded gypsum plaster. For the tile, ¾ in, of plaster or stucco outside and ‰ in, of plaster inside were applied

			Fire-resistance period						
Nominal wall thickness	Description	Propor- tion of cored spaces in units		tible memb l or no frame	Combustible members framed into wall				
			No plaster	Plaster on one side ²	Plaster on two sides	No plaster	Plaster on exposed side		
in. 9 10 10 10 10	Clay or shale brick Structural clay or shale tile (334-in, tile) Cored concrete-masonry units (expanded slag or pumice aggregates) Cored concrete-masonry units (expanded burned clay	Percent 0 60 38	hr 5 	hr 6 5	hr 7 4 6	hr 2 132	hr 2½ 2		
10	or shale, crushed limestone, air-cooled slag, or cin- ders) Cored concrete-masonry units ¹ (calcareous sand and gravel)	38 38	31/2	4	5 5	134 134	2 134		

¹ Coarse aggregate, 60 percent or more calcite and dolomite. ² No

struts or tension members between them. Wall ties of the types tested did not have sufficient flexural rigidity to transmit shearing forces across the cavity. Consequently, when one wythe was subjected to a vertical load, only a small part of the load was transmitted to the other, and the two tiers did not exert common action under such loading.

Exact comparison between the structural tests on cavity walls and similar tests on solid walls or walls with continuous masonry bridges [8, 21] was not possible because of the difficulty of adequately reproducing mortar and workmanship and, for some of the tests, conditions of curing. For most of the compressive-strength tests, too, the distribution of the load over both wythes was not completely typical of conditions to be met in service. Rough generalizations that could be made by comparing these test results, however, lead to the conclusion that for compressive loads with both wythes loaded, for concentrated loads, for racking loads, and for impact loads, the performance of the cavity walls was approximately equivalent to that of walls without cavities, using the same type and quantity of material; for transverse loads the performance was inferior to that of conventional walls for similar materials and workmanship. The tests indicated that cavity walls built according to accepted specifications [4] and having adequate workmanship will withstand reasonable impact and the usual floor and roof loadings of a two-story dwelling.

Results of tests indicate that while the outer wythe may be highly permeable to wind-driven rain, the proper inclusion of flashing and weep holes gives adequate protection against leakage through the inner wythe. When highly permeable concrete-masonry units were used in the facing wythe, it was necessary to apply a protective coating, consisting of portland-cement paint, to the exterior surface.

The thermal-insulating properties of a cavity wall depended upon the construction, air permeability, ventilation allowed, etc. In general, an improvement of over 25 percent in insulating properties was found for unventilated cavity walls compared with solid walls of the same material. A small amount of ventilation, not exceeding 1 in.² of opening at the top and bottom per linear foot of wall, did not materially increase the thermal transmittance of the walls.


The fire resistance of unventilated cavity walls was not much different from that of walls having the same quantity of solid materials except for the load-bearing ability. In the fire tests of those walls on which the loads applied were within the limits given in "Tile Engineering" [3] and table 1 of this report, structural failure was not observed before failure by rise of temperature on the unexposed face. The condition of loading favorable to structural stability during fire occurred when the load was applied eccentrically toward the exposed (inner) wythe, a condition that would occur in most applications.

Acknowledgment is made my associates on the staff of the Building Technology Division for their helpful advice in the preparation of this paper and especially H. E. Robinson and S. H. Ingberg for the use of hitherto unpublished data.

10. References

- R. Fitzmaurice, Principles of modern building, I chap. III, p. 159-172 (1939). His Majesty's Sta-tionery Office, London.
- [2] H. C. Plummer, Brick and tile engineering (1950), Structural Clay Products Institute, Washington, D. C
- [3] H. C. Plummer, Tile engineering (1946), Structural Clay Products Institute, Washington, D. C.
 [4] American Standard Building Code Requirements for
- Masonry (A41.1–1944). (Tentative revision, 1952.) [5] Metal wall ties, British Standard 1243:1945, British Standards Institution, London, England.
- [6] C. C. Fishburn, Strength and resistance to corrosion of ties for cavity walls, NBS Building Materials and Structures Report BMS101 (1943).
- [7] Tentative specifications for mortar for unit masonry, ASTM Designation C270-51T, American Society for Testing Materials, Philadelphia, Pa.
 [8] A. H. Stang, D. E. Parsons, and J. W. McBurney, Compressive strength of clay brick walls, BS J. Research 3, 507 (1929) RP108.
 [9] D. F. Parsons Wattrightness and transverse strength
- [9] D. E. Parsons, Watertightness and transverse strength of masonry walls (1939), Structural Clay Products Institute, Washington, D. C.
- [10] H. L. Whittemore, J. B. Cotter, A. H. Stang, and V. B. Phelan, Strength of houses, NBS Building Materials and Structures Report BMS109 (1948).
 [11] H. L. Whittemore and A. H. Stang, Methods of de-
- termining the structural properties of low-cost house constructions, NBS Building Materials and Structures Report BMS2 (1938).
- [12] H. L. Whittemore, A. H. Stang, and D. E. Parsons, Structural properties of a concrete-block cavity wall, NBS Building Materials and Structures Report BMS21 (1939). [13] H. L. Whittemore, A. H. Stang, and D. E. Parsons,
- Structural properties of a brick cavity-wall con-struction, NBS Building Materials and Structures Report BMS23 (1939).
- [14] H. L. Whittemore, A. H. Stang, and C. C. Fishburn, Structural properties of a reinforced-brick wall construction and a brick-tile cavity-wall construction, NBS Building Materials and Structures Report
- [15] C. C. Fishburn, Water permeability of walls built of masonry units, NBS Building Materials and Structures Report BMS82 (1942).
 [16] Insulated cavity wall, Technical notes of the Structures (1961).
- tural Clay Products Institute 2 (May 1951).
- [17] H. D. Foster, E. R. Pinkston, and S. H. Ingberg, Fire resistance of walls of lightweight-aggregate concrete masonry units, NBS Building Materials and Structures Report BMS117 (1950).
- [18] H. D. Foster, E. R. Pinkston, and S. H. Ingberg, Fire resistance of walls of gravel-aggregate concrete masonry units, NBS Building Materials and Structures Report BMS120 (1951).
- [19] S. H. Ingberg and H. D. Foster, Fire resistance of hollow load-bearing walls, BS J. Research 2 (1929) RP37.
- [20] Fire-resistance elassifications of building constructions, NBS Building Materials and Structures Report BMS92 (1942).
- [21] H. L. Whittemore, A. H. Stang, and D. E. Parsons, Structural properties of six masonry wall construc-tions, NBS Building Materials and Structures Report BMS5 (1938).
 - Washington, December 4, 1952.





BUILDING MATERIALS AND STRUCTURES REPORTS

[Continued from cover page 11]

BMS39	Structural Properties of a Wall Construction of "Pfeifer Units" Sponsored by the Wisconsin Units Co	104
BMS43	Performance Test of Floor Coverings for Use in Low-Cost Housing: Part 2	10,
BMS44	Surface Treatment of Steel Prior to Pointing	· ,
	Surface Treatment of Steel Prior to Painting Structural Properties of Prefabricated Wood-Frame Constructions for Walls, Parti-	
BMS47	Structural Properties of Prelabricated wood-Frame Constructions for Walls, Parti-	
	tions, and Floors Sponsored by American Houses, Inc. Structural Properties of "Precision-Built" Frame Wall and Partition Constructions	-20g
BMS48	Structural Properties of "Precision-Built" Frame Wall and Partition Constructions,	
	Sponsored by the Homasote Co	150
BMS50	Stability of Fiber Building Boards as Determined by Accelerated Aging	
BMS51	Stability of Properties of "Tilestates Time A" Floor Construction Structure	
DWDD1	Structural ribberties of Theerete Type A Floor Construction sponsored by the	
	THEORETE LO	10¢
BMS52	Effect of Ceiling Insulation Upon Summer Comfort	15¢
BMS53	Structural Properties of a Masonry Wall Construction of "Munlock Dry Wall Brick"	
	Shonsored by the Wunlock Humpering L'o	1114
BMS54	Effect of Soot on the Bating of an Oil Fired Heating Poiler	10
	Effect of Soot on the Rating of an Oil-Fired Heating Boiler Effects of Wetting and Drying on the Permeability of Masonry Walls	100
BMS55	Linects of wetting and Drying on the Permeability of Masonry Walls	1
BMS58	Strength of Soft-Soldered Joints in Copper Tubing Strength, Absorption, and Resistance to Laboratory Freezing and Thawing of Building	10¢
BMS60	Strength, Absorption, and Resistance to Laboratory Freezing and Thawing of Building	
	Bricks Produced in the United States Structural Properties of a Precast Joist Concrete Floor Construction Sponsored by the	300
BMS62	Structural Properties of a Present Joint Congrate Floor Construction Sponsored by the	00,
10111002	Destion of a receiver of a receiver of the contraction sponsored by the	1
DAGOO	Portland Cement Association	100
BMS63	Moisture Condensation in Building Walls	15q
BMS65	Methods of Estimating Loads in Plumbing Systems	1.50
BMS66	Plumbing Manual	350
BMS67	Plumbing Manual Structural Properties of "Mu-Steel" Prefabricated Sheet-Steel Constructions for Walls,	
	Partitions, Floors, and Roof, Sponsored by Herman A. Mugler	154
DMSCO	Parformance Toot for Electronic for Use Territory Devices	100
BMS68	Performance Test for Floor Coverings for Use in Low-Cost Housing: Part 3	200
BMS69	Stability of Fiber Sheathing Boards as Determined by Accelerated Aging	10¢
BMS70	Asphalt-Prepared Roll Roofings and Shingles	206
BMS71	Fire Tests of Wood- and Metal-Framed Partitions	×
BMS72	Fire Tests of Wood- and Metal-Framed Partitions Structural Properties of "Precision-Built, Jr." Prefabricated Wood-Frame Wall Con-	
DHIDIZ	struction processed by the Bongasta Co	104
10.3 5 0 100	struction Sponsored by the Homasote Co	
BMS73	Indentation Characteristics of Floor Coverings Structural and Heat-Transfer Properties of "U. S. S. Panelbilt" Prefabricated Sheet-	10¢
BMS74	Structural and Heat-Transfer Properties of "U. S. S. Panelbilt" Prefabricated Sheet-	
	Stool Constructions for Walls Partitions and Poofs Sponsored by the Connesso	
	Coal Iron & Bailroad Co	20¢
DMS76	Coal, Iron & Railroad Co Effect of Outdoor Exposure on the Water Permeability of Masonry Walls	200
BMS76	Effect of Outdoor Exposure on the water Permeability of Masonry wans	3
BMS77	Properties and Performance of Fiber Tile Boards	1
BMS78	Structural, Heat-Transfer, and Water-Permeability Properties of Five Earth-Wall	
	Constructions	25¢
BMS79	Water-Distributing Systems for Buildings	20%
BMS80	Performance Test of Floor Coverings for Use in Low-Cost Housing: Part 4	150
	Find Transform Check List for Dubling Constructions (aloth sources)	201
BMS81	Field Inspectors' Check List for Building Constructions (cloth cover, 5 x 71/2 inches)	300
BMS82	Water Permeability of Walls Built of Masonry Units	25¢
BMS83	Water Permeability of Walls Built of Masonry Units	15¢
BMS84	Survey of Roofing Materials in the South Central States	150
BMS85	Dimensional Changes of Floor Coverings With Changes in Belative Humidity and	
DIALOUG	Temperature fundation of the overlings with changes in teleastic fundation and	*
DAGOO	Temperature	
BMS86	Structural, Heat-Transfer, and Water-Permeability Properties of "Speedbrik" Wall	
	Construction Sponsored by the General Shale Products Corporation	15¢
BMS87	A Method for Developing Specifications for Building Construction—Report of Sub-	
	committee on Specifications of the Central Housing Committee on Research,	
	Design and Constructions of the Central Housing Committee of Research,	20¢
DMGOO	Design, and Construction Recommended Building Code Requirements for New Dwelling Construction With	200
BMS88	Recommended Building Code Requirements for New Dweining Construction with	
	Special Reference to War Housing	*
BMS89	Structural Properties of "Precision-Built, Jr." (Second Construction) Prefabricated	
	Wood-Frame Wall Construction Sponsored by the Homasote Co	150
BMS90	Structural Properties of "PHC" Prefabricated Wood-Frame Constructions for Walls,	
D11030	bildefinal froberies of file frequencies would fame constitutions for wans,	154
DIAGON	Floors, and Roofs Sponsored by the PHC Housing Corporation	15¢
BMS91	A Glossary of Housing Terms	-
BMS92	Fire-Resistance Classifications of Building Constructions	- 3 0¢
BMS93	Fire-Resistance Classifications of Building Constructions Accumulation of Moisture in Walls of Frame Construction During Winter Exposure	*
BMS94	Water Permeability and Weathering Resistance of Stucco-Faced, Gunite-Faced, and	
	"There Concerned Their? We have	154
DMOOF	"Knap Concrete-Unit" Walls Tests of Cement-Water Paints and Other Waterproofings for Unit-Masonry Walls	100
BMS95	lests of Cement-Water Paints and Other Waterproofings for Unit-Masonry Walls	25¢
BMS96	Properties of a Porous Concrete of Cement and Uniform-Sized Gravel	10¢
BMS97	Experimental Dry-Wall Construction With Fiber Insulating Board	*
BMS98	Physical Properties of Terregay of Aggregates	*
BMS99	Physical Properties of Terrazzo Aggregates	
DW1933	of uctural and near-transfer fropercies of "Multiple Box-Girder riywood fanels" for	1 ~ /
DAGA	walls, Floors, and Roots	19¢
BMS100	Walls, Floors, and Roofs Relative Slipperiness of Floor and Deck Surfaces	10¢

•Out of print.

[List continued on cover page IV]

BUILDING MATERIALS AND STRUCTURES REPORTS

[Continued from cover page III]

BMS101	Strength and Resistance to Corrosion of Ties for Cavity Walls	
BMS102	Painting Steel10 Measurements of Heat Losses From Slab Floors15	đ
BMS103	Measurements of Heat Losses From Slab Floors15	đ
BMS104	Structural Properties of Prefabricated Plywood Lightweight Constructions for Walls.	ľ
	Partitions, Floors, and Roofs Sponsored by the Douglas Fir Plywood Association	*
BMS105	Paint Manual with particular reference to Federal Specifications\$1.2	5
BMS106	Laboratory Observations of Condensation in Wall Specimens10	d
BMS107	Building Čode Requirements for New Dwelling Construction	*
BMS108	Temperature Distribution in a Test Bungalow With Various Heating Devices	đ
BMS109	Strength of Houses: Application of Engineering Principles to Structural Design \$1.5	
BMS110	Paints for Exterior Masonry Walls15	d
BMS111	Paints for Exterior Masonry Walls15 Performance of a Coal-Fired Boiler Converted to Oil15	d
BMS112	Properties of Some Lightweight-Aggregate Concretes With and Without an Air-	r
	entraining Admixture10	d
BMS113	Fire Resistance of Structural Clay Tile Partitions	đ
BMS114	Temperature in a Test Bungalow With Some Radiant and Jacketed Space Heaters 25	é
BMS115	A Study of a Baseboard Convector Heating System in a Test Bungalow 20	d
BMS116	Preparation and Revision of Building Codes 15	1
BMS117	Fire Resistance of Walls of Lightweight Aggregate Concrete Masonry Units 20	d
BMS118	Stack Venting of Plumbing Fixtures 15	4
BMS119	Wet Venting of Plumbing Fixtures 20	d
BMS120	Fire Resistance of Walls of Gravel-Aggregate Concrete Masonry Units 15	ć
BMS121	Investigation of Failures of White-Coat Plasters25	é
BMS122	Investigation of Failures of White-Coat Plasters25 Physical Properties of Some Samples of Asbestos-Cement Siding15	é
BMS123	Fire-Tests of Wood-Framed Walls and Partitions With Asbestos-Cement Facings 15	é
BMS124	Fire Tests of Steel Columns Protected With Siliceous Aggregate Concrete 15	é
BMS125	Stone Exposure Test Wall 30	é
BMS126	The Self-Siphonage of Fixture Traps 20	é
BMS127	Effect of Aging on the Soundness of Regularly Hydrated Dolomitic Lime Putties 15	¢
BMS128	Atmospheric Exposure Tests of Nailed Sheet Metal Building Materials 20	é
BMS129	Fire Endurance of Shutters for Moving-Stairway Openings 10	é
BMS130	Methods and Equipment for Testing Printed-Enamel Feit-Base Floor Covering 15	é
BMS131	Fire Tests of Gunite Slabs and Partitions15	ć
BMS132	Capacities of Plumbing Stacks in Buildings 20	ć
BMS133	Live Loads on Floors in Buildings 20	¢
BMS134	Fire Resistance of Concrete Floors 15	ć
BMS135	Fire Tests of Steel Columns Encased With Gypsum Lath and Plaster	¢
BMS136	Properties of Cavity Walls15	¢

*Out of print.