

NBSIR 80-2167

Weatherization Investment Costs for Low-Income Housing

Stephen F. Weber Michael J. Boehm Barbara C. Lippiatt

Center for Building Technology National Engineering laboratory National Bureau of Standards U.S. Department of Commerce Washington, DC 20234

November 1980

Prepared for: Community Services Administration Washington, DC 20506

QC 100 .U56 80-2167 1980 c. 2 -

WEATHERIZATION INVESTMENT COSTS FOR LOW-INCOME HOUSING

National Bureau of Standards Library, E-01 Admin, Bldg.

FEB 27 1981

Not oci - Gre OCIOO . UEB NO. 80-21=7 1980 1.2

Stephen F. Weber Michael J. Boehm Barbara C. Lippiatt

Center for Building Technology National Engineering Laboratory National Bureau of Standards U.S. Department of Commerce Washington, DC 20234

November 1980

Prepared for: Community Services Administration Washington, DC 20506



U.S. DEPARTMENT OF COMMERCE, Philip M. Klutznick, Secretary Jordan J. Baruch, Assistant Secretary for Productivity, Technology, and Innovation NATIONAL BUREAU OF STANDARDS, Ernest Ambler, Director



PREFACE

This project was conducted under the sponsorship of the Community Services Administration (CSA) by the Applied Economics Group in the Center for Building Technology (CBT) of the National Bureau of Standards (NBS).

In response to the burden that high and rapidly rising energy costs are imposing on low-income households, CSA and NBS are conducting a demonstration program to weatherize the dwellings of such households to conserve energy. This program involves the installation and analysis of a broad range of weatherization options for over 200 single-family houses in 14 demonstration sites throughout the United States. One important element of this program is to collect and analyze the costs of these weatherization investments so that CSA, the Department of Energy, and other interested parties can have accurate estimates of weatherization costs available and can better decide whether the installed package of weatherization options is expected to pay for itself. Consequently, this report presents an analysis of the field data collected on the costs of installing in low-income houses architectural weatherization features designed to reduce the building space heating load.

Special appreciation is extended to the local project coordinators of the demonstration sites for taking the time to fill out the many cost data forms required and for providing information needed to resolve ambiguities. Special appreciation is also extended to Kimberly A. Barnes for developing the first versions of the computer programs used for this report and for providing advice on computer matters. Lawrence J. Kaetzel, Judith T. Calabrese, and Charles B. Andrews also deserve thanks for providing technical assistance with the operation of the CBT computer system. For assistance in tabulating data and editing the manuscript the authors are grateful to Anne Hillstrom. Special appreciation is also extended to Brenda L. Kefauver and Mary L. Ramsburg for typing the manuscript. For helpful comments throughout the project, the authors would like to thank Robert E. Chapman, Richard W. Crenshaw, and Stephen R. Petersen. In addition, the authors are grateful to the reviewers for providing comments to improve the report: Kimberly A. Barnes, Robert W. Beaucoliel, Richard W. Crenshaw, and Harold E. Marshall.

ABSTRACT

This report presents the results of a project involving the collection and tabulation of field data on the costs of retrofitting low-income houses for energy conservation. This project is part of the Community Services Administration Weatherization Demonstration Program being carried out through the National Bureau of Standards. The program involves the installation and evaluation of a broad range of energy conservation techniques for over 200 single-family houses in 14 demonstration sites throughout the United States. The energy conservation techniques discussed in this report consist of a variety of architectural modifications to building envelopes for the purpose of reducing heat losses due either to air infiltration or conduction. The methods used to collect and synthesize the field data on the major cost components of installing these techniques are described. An analysis of these costs is presented in the form of summary statistics including the weighted mean and standard deviation of the unit cost of installing each architectural option in each demonstration site. The significant intercity variation found in the mean unit cost of most techniques suggests that unique cost estimating procedures may be needed for each city. Possible sources of variation in the mean unit costs are discussed. Recommendations for further research include investigating the effect on cost that can be attributed to selected sources of variation.

Key Words: Building economics; cost components; data analysis; data collection; demonstration; economic analysis; energy conservation; insulation; low-income housing; statistics; unit costs; weatherization.

TABLE OF CONTENTS

			Page
LIST	OF TA	ABLES	vi
LIST	OF F	IGURES	vii
CONVI	ERSIO	N FACTORS FROM CUSTOMARY TO METRIC (SI) UNITS	viii
1.0	INTRO	DDUCTION	1
	1.1 1.2 1.3	Purpose Scope Usefulness of Cost Data	1 2 2
2.0	DATA	COLLECTION METHOD	6
	2.1 2.2	Data Collection Form Monitoring the Data Collection	6 8
3.0	DATA	REDUCTION AND SYNTHESIS	10
	3.1 3.2 3.3	Non-Attic Options Attic Insulation Weatherization-Related Repair Work	10 15 17
4.0	DATA	PRESENTATION	19
	4.1 4.2	Infiltration Options Conduction Options	19 39
		<pre>4.2.1 Non-Attic Conduction Options</pre>	39 57
	4.3 4.4	Weatherization-Related Repair Work	65 65
5.0	RECON	MENDATIONS FOR FURTHER RESEARCH	70
REFEF	RENCES	· · · · · · · · · · · · · · · · · · ·	73

. .

LIST OF TABLES

Page

Table 1.1	Metropolitan Area, State, and Abbreviation for the Demonstration Sites in this Report	3
Table 1.2	Number of Houses Reported by Architectural Option and City	4
Table 4.1	Expenditures (\$) for Weatherization-Related Repair Work, by City and Type of Repair Work	66
Table 4.2	Weighted Mean Total Cost of Installed Architectural Options, by City, in Dollars per Lineal Foot (\$/lf) or Dollars per Square Foot (\$/sf)	67
Table 4.3	Weighted Mean Total Cost of Installed Attic Insulation Based on Actual R-value Added, by City, in Dollars per "R" added per Square Fott (\$/R•sf) and Dollars per Square Foot (\$/sf)	69

LIST OF FIGURES

Page

Figure 2.1	Dwelling Unit Cost Data Form	7
Figure 2.2	Cost Data Tracking Chart	9
Figure 3.1	Composite Data Form	11

NUITS (
(SI)
METRIC
TO
CUSTOMARY
FROM
FACTORS
ONVERSION

QUANTITY	TO CONVERT FROM	TO	MULTIPLY BY
Length	lineal foot (lf)	meter	3.048 x 10 ⁻¹
Area	square foot (sf)	square meter	9.290×10^{-2}
Volume	cubic foot (cf)	cubic meter	2.832×10^{-2}
Mass	pound (1b)	kilogram	4.536 x 10 ⁻¹
Density	pound per cubic foot (lb/cf)	kilogram per cubic meter	1.603×10^{1}
Temperature	degree Fahrenheit (°F)	degree Celsius	$t_{\rm C} = (t_{\rm F} - 32)/1.8$
Temperature difference	degree Fahrenheit (°F)	degree Celsius	5.556 x 10 ⁻¹
Energy	British thermal unit (Btu)	joule	1.055×10^3
Thermal Resistance	square foot hour degreee Fahrenheit per Btu	square meter degree Celsius per watt	1.761×10^{-1}

viii



1.0 INTRODUCTION

1.1 PURPOSE

The purpose of this report is to present the results of a project involving the collection and tabulation of field data on the costs of retrofitting low-income houses for energy conservation. This project is part of the Community Services Administration (CSA) Weatherization Demonstration Program being carried out through the National Bureau of Standards (NBS).¹ The program involves the installation and evaluation of a broad range of energy conservation techniques for over 200 single-family houses in 14 demonstration sites throughout the United States. The results presented in this report are in the form of summary statistics giving the mean, median, range, and standard deviation of the unit cost of installing each architectural option in each demonstration site. Statistics are also presented on such major cost components as labor cost, materials cost, and overhead.

¹ For an overview of the many research activities comprising this Weatherization Demonstration, see R. Crenshaw <u>et al.</u>, <u>CSA Weatherization Demonstration Project Plan</u>, National Bureau of Standards Interagency Report 79-1706, Washington, D.C., March 1979.

1.2 SCOPE

The energy conservation techniques discussed in this report consist of a variety of architectural modifications to building envelopes, usually referred to as architectural options. These architectural options are divided into two major groups: those that reduce heat losses due to direct conduction through the envelope components, that is, walls, windows, attic and floor (conduction options), and those that reduce heat losses due to air leakage through cracks in or between the components (infiltration options). The selection of the particular options to be installed at each demonstration site was based on an economic analysis of predicted energy savings and estimated costs for each option.¹

All of the demonstration sites for which cost data on architectural options were reported are listed in table 1.1, along with the three-letter codes often used in this report to reference the sites. Table 1.2 lists the architectural options and indicates the number of dwellings for which cost data were received for each architectural option in each demonstration site. For any particular option-site combination, the cost data are summarized in this report only if both labor and materials costs were reported separately for at least four dwellings. The items of cost data which satisfy this criterion and are thus presented in this report account for 87 percent of all reported architectural option installations.

1.3 USEFULNESS OF COST DATA

The cost data collected over the course of this project are based on the actual weatherization work conducted at the demonstration sites. Thus, future estimates of the cost of installing various architectural options based on these data can be expected to have greater accuracy than would be possible in the absence of such direct and specific experience. These architectural cost data can also be used to assess the cost effectiveness of the weatherization options that were installed.

A very useful characteristic of the architectural cost data is that the data reported for each option installed on a house include both the size of the job (e.g., square feet of wall area insulated) as well as a separate accounting of labor and materials. With these detailed data, studies can be made of the major sources of variation in the cost of an architectural option from house to house and from site to site. Among the sources of variation that can be studied using these data are possible economies of scale in terms either of the number of square or lineal feet installed or of the thermal resistance of the insulation added. Another source of variation is whether the work was carried out under contract or on an in-house basis. Yet another

¹ For a detailed discussion of how the economically optimal weatherization options were selected for each site and fuel type, see R. Chapman <u>et al.</u>, <u>Optimizing Weatherization Investments in Low-Income Housing: Economic Guidelines and Forecasts</u>, National Bureau of Standards Interagency Report 79-1948, Washington, D.C., February 1980.

Table 1.1

Metropolitan Area, State, and Abbreviation for the Demonstration Sites in this Report

Metropolitan Area	State	Abbreviation
Albuquerque	New Mexico	ALB
Atlanta	Georgia	ATL
Charleston	South Carolina	CHA
Colorado Springs	Colorado	CSP
Easton/Allentown/Bethlehem	Pennsylvania	EAS
Fargo	North Dakota	FAR
Minneapolis/St. Paul	Minnesota	MSP
Oakland	California	OAK
Portland	Maine	POR
St. Louis	Missouri	STL
Tacoma	Washington	TAC
Washington, D.C.	Maryland ^a	WAS

^a The dwellings at this site are located near Hughesville, Maryland.

Option Description	ALB	ATL	CHA	CSP	EAS	FAR	MSP	OAK	POR	STL	TAC	WAS
Infiltration Options												
Replace Broken Glass	4	2 ^a	12	15	15		6 ^b	8	4		3 ^a	
Reset Glazing	la	la	9	7	11		6 ^b	la	4			
Replace Thresholds		2ª	17	16				5	la		la	la
Seal Structural Cracks	за	за	18	13	2ª				la			
Caulk Windows	la	2a										
Caulk Doors		2a										
Caulk Windows and Doors		3a	18	18	8				8			10
Weatherstrip Windows		3a		7		11	7b					
Weatherstrip Doors	7	4		18		12	6 ^b	5	12		9	10
Weatherstrip Windows and Doors		3 ^a	15		12							
Weatherstrip Attic Hatch		4		9					6			
Conduction Options												
Install Storm Windows	6		la	16						15	9	10
Install Storm Doors	la			2 ^a								2ª
Install Triple Glazing		5		7	7	13						
Insulate Basement Walls w/Cellulose									10			
Insulate Basement Walls w/Fiberglass Batts				5								
Insulate Basement Walls w/High R Sheathing and Fiberglass Batts										9b		
Insulate Basement Walls w/Urea-Formaldehyde						7					10	за
Install Foundation Vents			5									
Install Foundation Vapor Barrier			la								3a	
Insulate Crawl Space w/Styrofoam		2a	11			la					8	
Insulate Crawl Space w/Urea-Formaldehyde		за				за						
Insulate Floor Joists w/Fiberglass Batts		2ª	5	4								5
Insulate Rim Joists w/Fiberglass Batts						за	1/					
Insulate Walls w/Cellulose		2a		6					15		4	4
Insulate Walls w/Fiberglass					7							
Insulate Walls w/Urea-Formaldehyde				10		12	17					5
Insulate Attic w/Cellulose			17	18	9	12	12	8	15	13		10
Insulate Attic w/Fiberglass	5							за				
Insulate Attic w/Rock Wool		9								8 b	11	
Install Attic Vents			за			2a			2a			

Table 1.2

Number of Houses Reported by Architectural Option and City

City

^a Because fewer than four dwellings were reported, cost data are not summarized in this report.

b Because labor and materials costs were not reported, cost data are not summarized in this report.

use for these data would be in constructing a separate price index to apply to each cost component in order to account for cost differences over time and across regions and thus permit accurate periodic revisions of cost estimates based on these data.



2.0 DATA COLLECTION METHOD

2.1 DATA COLLECTION FORM

The first step in the process of collecting data on the costs of the architectural options was the development of a standard form for reporting the data. The form that was developed and used for this purpose is shown as figure 2.1. This Dwelling Unit Cost Data Form was used by personnel at the demonstration sites to record information relevant to the cost reporting of every architectural option installed in each house of the demonstration program. The circled numbers on figure 2.1 provide a key to the following types of information recorded on the form:

- 1. Code number of the dwelling being weatherized.
- 2. Building element being modified.
- 3. Energy conservation retrofit option being installed.
- 4. Job size or dimensions of the option being installed, measured in square feet, lineal feet, or number of units treated.
- 5. Total cost of the option being installed including overhead cost.

Figure 2.1 DWELLING UNIT COST DATA FORM RETROFIT OPTION SG FT, LIN FT, #UNITS	USE MATERIALS & EQUIPMENT USE	RATE TOTAL MATERIALS/EQUIPMENT UNIT SIZE TIME OR UNIT COST																		
ATA FORM 3	MATER	IALSZEQUIPMENT																		
Figure 2.1 WELLING UNIT COST DA RETROFIT OPTION SQ FT, LIN FT, A		TOTAL MATER							-											
	DECT I AROR IICF	HOURS RATE																		
MENT 2	DIR	LABOR SKILL							And the second s											
ADDRESS		TYPE OF WORK	PREPARATION	())	TOTAL	INSTALLATION		_	6)					TOTAL	OTHER OF	OTHER	(8)

- Cost of preparation work normally required before the installation process itself.
- Costs directly associated with the actual installation of the option.
- 8. Two types of costs were recorded under Other Costs:
 - (a) The cost of doing any repairs to a building before the option could be installed; and
 - (b) Some overhead cost items such as travel and supervision for jobs done on an in-house basis.
- 9. Labor cost for each of items 6 through 8. The number of labor hours of each labor skill, the rate paid per hour for that skill and the total labor charges for that skill were recorded separately.
- 10. Materials costs for items 6 through 8. Specific information was given on the type of material used, the size of each unit of the material, the number of units used, the cost per unit, and the total cost for the material. For example, if 15 bags of cellulose insulation were used, each bag costing \$5.95, this information and the resulting total material cost of \$89.25 was recorded.

2.2 MONITORING THE DATA COLLECTION

The local project coordinator of each demonstration site was asked to fill out and submit a trial Dwelling Unit Cost Data Form as soon as the first architectural option was installed. The completed trial form revealed possible uncertainties in reporting procedures and thus served as a basis for establishing a workable and consistent set of guidelines for recording and reporting the remaining cost data for each site. As data collection forms were submitted, telephone conversations between NBS staff and the local project coordinators were held to resolve ambiguities and supply missing data. This type of direct communication between NBS staff and the local project coordinators was found to be effective in improving the quality of the data.

The progress of the cost data collection was monitored through the use of Cost Data Tracking Charts. An individual chart was developed for each site according to the particular options selected to be installed. As figure 2.2 illustrates with a hypothetical example, a typical Cost Data Tracking Chart lists these architectural options vertically and the appropriate house code numbers horizontally. Each cell at the intersection of a particular option and house could contain any one of the three symbols defined at the top of the chart. These charts provided at a glance the current status of the architectural cost data reporting on a site-by-site basis.

Figure 2.2. Cost Data Tracking Chart

Note: 1. "X" indicates cost data already received.

- Place "NA" in cells that represent options that will not be installed on a particular house.
- 3. Place "0" in cells that represent completed work, but data not yet submitted.

SITE

Coldspot, USA

					H	IOUSE	NUM	IRFER				
OPTION	1	3	7	11	16	17	18	23	25	30	31	39
Replace Broken Glass	NA	NA	X	NA	0	NA	NA	NA	X	NA	Х	<u>X</u>
Reset Glazing		NA	NA	NA	NA	NA	NA		NA		NA	NA
Replace Thresholds		NA	NA	NA	NA	NA	NA		NA	NA	NA	
Seal Structural Cracks	NA	NA	NA				NA		NA	NA		
Caulk Windows and Doors	0	0	0	0	0	NA	0	0	0	0	0	0
Weatherstrip Windows and Doors	0	0	0	0	0	NA	0	0	0	0	0	0
Weatherstrip Attic Hatch												
Install Storm Windows												
Insulate Basement Walls	0	х	0	Х	Х	Х	Х	NA	х	X	0	0
Insulate Walls	х	х	х	х	х	х	NA	х	х	X	х	X
Insulate Attic	X	Х	X	Х	Х	Х	X	Х	0	Х	NA	x
	OPTION Replace Broken Glass Reset Glazing Replace Thresholds Seal Structural Cracks Caulk Windows and Doors Weatherstrip Windows and Doors Weatherstrip Attic Hatch Install Storm Windows Insulate Basement Walls Insulate Malls	OPTION1Replace Broken GlassNAReset GlazingNAReplace ThresholdsNASeal Structural CracksNACaulk Windows and Doors0Weatherstrip Windows and Doors0Weatherstrip Attic Hatch0Install Storm Windows0Insulate Basement Walls0Insulate MallsXInsulate AtticX	OPTION13Replace Broken GlassNANAReset GlazingNAReplace ThresholdsNASeal Structural CracksNACaulk Windows and Doors0Weatherstrip Windows and Doors0Weatherstrip Attic Hatch	OPTION137Replace Broken GlassNANAXReset GlazingNANANAReplace ThresholdsNANASeal Structural CracksNANACaulk Windows and Doors00Weatherstrip Windows and Doors00Weatherstrip Attic Hatch	OPTION13711Replace Broken GlassNANAXNAReset GlazingNANANANAReplace ThresholdsNANANANASeal Structural CracksNANANACaulk Windows and Doors000Weatherstrip Windows and Doors000Weatherstrip Attic Hatch	OPTION1371116Replace Broken GlassNANAXNA0Reset GlazingNANANANANAReplace ThresholdsNANANANANASeal Structural CracksNANANANACaulk Windows and Doors0000Weatherstrip Windows and Doors0000Weatherstrip Attic Hatch	OPTION137111617Replace Broken GlassNANAXNA0NAReset GlazingNANANANANANAReplace ThresholdsNANANANANANASeal Structural CracksNANANANANACaulk Windows and Doors0000NAWeatherstrip Windows and Doors0000NAWeatherstrip Attic Hatch	OPTION13711161718Replace Broken GlassNANAXNA0NANAReset GlazingNANANANANANANANAReplace ThresholdsNANANANANANANANASeal Structural CracksNANANANANANANACaulk Windows and Doors0000NA0Weatherstrip Windows and Doors0000NA0Weatherstrip Attic Hatch	OPTION1371116171823Replace Broken GlassNANAXNA0NANANANAReset GlazingNANANANANANANANANANAReplace ThresholdsNANANANANANANANANANASeal Structural CracksNANANANANANANAOOCaulk Windows and Doors00000NAOOWeatherstrip Windows and Doors0000NA0OWeatherstrip Attic HatchInstall Storm Windows0X0XXXXNAInsulate Basement Walls0X0XXXXXXXXInsulate AtticXXXXXXXXXXX	OPTION137111617182325Replace Broken GlassNANAXNA0NANAXReset GlazingNANANANANANANANANANAReplace ThresholdsNANANANANANANANANANASeal Structural CracksNANANANANANANANACaulk Windows and Doors0000NA000Weatherstrip Windows and Doors0000NANANANAInstall Storm Windows0XXXXXXXXInsulate Basement Walls0XXXXXXXXXInsulate AtticXXXXXXXXXXX	OPTION 1 3 7 11 16 17 18 23 25 30 Replace Broken Glass NA NA X NA 0 NA NA	OPTION 1 3 7 11 16 17 18 23 25 30 31 Replace Broken Glass NA NA X NA 0 NA NA X NA X NA NA NA NA X NA X NA NA NA NA X NA X NA X NA X NA X NA NA NA NA NA NA X NA <



3.0 DATA REDUCTION AND SYNTHESIS

In this section we discuss how the raw architectural cost data received from the demonstration sites were used to develop the summary statistics presented in section 4 for each option and site. The procedures for extracting, consolidating, and analyzing the data were slightly different for each of three categories of architectural work: (1) non-attic options; (2) attic options; and (3) weatherization-related repair work. The procedures followed for each category are discussed in turn.

3.1 NON-ATTIC OPTIONS

The first step in the data reduction process for non-attic options was to extract the relevant information from each Dwelling Unit Cost Data Form and to consolidate this information for all houses that had a particular option installed in a given city. To accomplish this task the Composite Data Form was developed. As illustrated in figure 3.1 using a hypothetical example, this form specifies the demonstration site, the option, and whether the work was performed under contract or in-house. Each row of this form presents five items of information extracted from a single Dwelling Unit Cost Data

Figure 3.1 Composite Data Form

Site Coldspot, USA

Option Insulate Walls with UF Foam

Contracted or In-House Contracted

House Number	Job Size (sf)	Labor Cost (\$)	Materials Cost (\$)	Total Cost (\$)
3	848	208.00	121.75	523.92
7	744	160.00	146.75	405.47
16	917	128.00	121.75	526.22
17	752	112.00	116.75	374.45
25	912	128.00	136.75	435.33
30	1040	160.00	160.50	522.51

Form: (1) code number of the weatherized house; (2) job size or dimensions of the architectural option installed; (3) labor cost of the installation; (4) materials cost of the installation; and (5) total cost of the installed option.

Two distinct accounting definitions of total cost were developed and applied depending on whether the option was installed by contracted labor (contracted) or by employees of the local community action agency (in-house). In the case of contracted jobs, the definition of total cost is given by

 $T \equiv L + M + OP$,

(3.1)

where T = Total cost reported as charged under the contract;

L = Labor cost reported for the option;

M = Materials cost reported for the option; and

OP = Overhead and profit calculated as a residual.

For contracted jobs, T, L, and M are recorded explicitly on the Dwelling Unit Cost Data Form, whereas OP must be calculated as a residual on the basis of equation (3.1). Overhead represents the fixed business expenses of the contractor which arise independently of the volume of contracted business. Examples of overhead expenses are office rent, insurance, management, and clerical and administrative support. Also included in the residual OP is the contractor's profit. In one city (CSP), the contractor's total charge for installing storm windows was less than the sum of labor and materials costs incurred. Here, rather than have the residual OP be negative, the sum of labor and materials costs was recorded as the total cost on the Composite Data Form, under the assumption that contractors are not likely to continue underestimating job costs.

In the case of in-house weatherization jobs, the definition of total cost is given by

 $T \equiv L + M + OT$,

(3.2)

where T = Total cost calculated as the sum of its components; OT = Overhead and travel cost as reported for the option; and

L & M are as defined for equation (3.1), above.

For these jobs performed on an in-house basis, there is no reported contract cost to use as the total cost of the option. Thus total cost has to be calculated as the sum of its three reported components: L, M, and OT. OT is derived from two types of cost items reported on the Dwelling Unit Data Form: overhead and travel. Examples of the overhead items reported include clerical support and certain management functions such as supervision, job estimation, and inspection. No attempt was made to estimate or impute any overhead expenses beyond those explicitly reported by the local community action agencies. The other component of OT, travel cost, was consistently reported and included both labor time spent in transit to and from the job site and vehicle mileage costs. A special cost accounting problem arose whenever two or more architectural options for a house were reported on a single combined Dwelling Unit Cost Data Form. In this situation a single total cost figure was always given for the combined options, although the labor and materials costs could in most cases be assigned to the separate options. Since the data for this report were to be analyzed on an option-by-option basis, it was necessary to determine a separate total cost figure for each of the options reported. This figure was obtained by employing equation (3.3), which computed the overhead and profit or overhead and travel multiplier applicable to the cost of the labor and materials for the combined options and applied that multiplier to the sum of labor and materials costs of each separate option:

$$T_{s} = [T_{c}/(L_{c}+M_{c})] \cdot [L_{s}+M_{s}],$$

(3.3)

where

 $T_s = Total cost of a single option;$ $T_c = Total cost of the combined options;$ $L_c = Total labor cost of the combined options;$ $M_c = Total materials cost of the combined options;$ $L_s = Total labor cost of the single option; and$ $M_s = Total materials cost of the single option.$

Another similar accounting problem occasionally arose when a single Dwelling Unit Cost Data Form contained more than one architectural option. The materials were generally described in enough detail that the particular options for which they were used could be easily discerned. On some forms, however, the labor costs were found grouped together so that one could not tell how many labor hours were spent on each option. To address this problem, the combined labor costs were distributed among the options in proportion to the cost of the materials used for each option. The following equation was used for assuring this apportionment of combined labor costs:

$$L_{s} = (M_{s}/M_{c}) \cdot L_{c},$$

(3.4)

- M_s = Materials cost for the option for which labor cost is to be calculated;
- M_c = Total materials cost of the combined options; and

 L_c = Total labor cost of the combined options.

The final accounting problem occurred only when two or more architectural options were installed by the same contractor. Although a separate contract cost figure may have been given for each option on an individual Dwelling Unit Cost Data Form, occasionally the amounts reported did not reflect a realistic assignment of costs to each option. For example, in one city where attics and walls were insulated by the same contractor, substantial losses were reported on the attic installations (i.e., the contract cost was actually less than the sum of labor and materials costs), while excessive profits were reported in the wall installations (i.e., the contract cost was more than twice as much as the sum of labor and materials costs). The procedure followed to address this situation was to combine the cost data for the two options under one contract and then redistribute the total contract overhead and profit in proportion to the labor and materials costs of each option. Equation (3.3) was used to carry out this cost redistribution, and the revised data for each house and option were then recorded on the appropriate Composite Data Form.

Once correctly recorded on the Composite Data Forms, all the relevant cost data for each option-site combination were entered into a computer file. A computer program was then used to retrieve the data from the file and calculate several summary statistics for each of the following variables of that option-site combination: job size (in square or lineal feet), unit labor cost (labor cost per square or lineal foot), unit material cost, unit overhead cost, and unit total cost. The summary statistics calculated for each of the above variables were the minimum, maximum, arithmetic mean, and median. Two additional statistics for the total cost variable were then calculated: its mean and standard deviation, both weighted by job size. All of these summary statistics for each non-attic option are presented in subsections 4.1 and 4.2.1.

The arithmetic mean and the weighted mean of the unit total cost variable differ from one another in their calculation and interpretation. The methods of calculating these statistics are given by the following equations:

$$\overline{X} = \underbrace{i=1}_{n}^{\Sigma} (T_i/S_i)$$
, and (3.5)

$$\overline{X}_{w} = \frac{\sum_{i=1}^{n} (T_{i}/S_{i}) \cdot S_{i}}{\sum_{i=1}^{n} S_{i}} = \frac{\sum_{i=1}^{n}}{\sum_{i=1}^{n}},$$

where \overline{X} = Unweighted arithmetic mean;

 X_w = Mean weighted by job size;

- n = Number of jobs (dwellings) reported for the option and site being considered;
- T_i = Total cost of installing the option for each individual dwelling; and
- S_i = Size of each individual job (lf or sf).

To illustrate the difference between these two statistics, consider the following example. Suppose for a particular site and option only two dwellings were retrofitted: on one house 1000 sf of wall area were insulated at a cost of \$1.00/sf, while on the other 500 sf of wall area were insulated for \$1.20/sf. The arithmetic, or unweighted, mean cost for this site would be exactly halfway between the two unit cost amounts of the houses, namely \$1.10/sf. In this sense, the unweighted mean gives each individual job (or

(3.6)

dwelling) equal importance, regardless of the size (number of square or lineal feet) of the job. In contrast, for the same two jobs the weighted mean would be $1.07/sf\left(\frac{1.00 (1000) + 1.20 (500)}{1500}\right)$, which reflects the

relatively greater weight given by this statistic to the unit cost (\$1.00/sf) of the larger job than to that (\$1.20/sf) of the smaller job. Thus the weighted mean is a measure of the average cost of installing one square or lineal foot of the option for that demonstration site.

As mentioned earlier, the standard deviation weighted by job size of the total cost variable is also computed. The formula used for calculating the weighted standard deviation (SD_w) is:

$$SD_{w} = \sqrt{\sum_{i=1}^{n} (T_{i}/S_{i}-S_{w})^{2} \cdot (S_{i}/\sum_{i=1}^{n} S_{i})}, \qquad (3.7)$$

where the symbols are defined as for equations (3.5) and (3.6), above. This statistic provides a measure of the variability of the unit cost of the option across all houses within the demonstration site. This unit cost variation within a site may be due to several factors. The location of the house may account for some variation because the travel component is a function of distance from the assembly point of the work crew. The size of the job may also affect unit cost because of possible economies of scale. This factor is particularly important when fixed costs such as for travel or setting up equipment represent a significant proportion of the total cost of installing the option. Another cause of the variance in unit cost could be the differences found in the physical structures of the dwellings themselves. An example of this would be the relatively higher unit cost of insulating a brick veneer wall compared with that of insulating a wood-frame wall.

3.2 ATTIC INSULATION

Procedures similar to those used for the cost data on non-attic options were followed for data on attic insulation. The major accounting problems encountered with attic insulation data were the determination of overhead costs and the revision of total cost estimates for two or more options installed by the same contractor. These problems were dealt with in the manner described in subsection 3.1 above. Once these accounting problems were resolved, the relevant information for all houses was taken from the corrected Dwelling Unit Cost Data Forms and consolidated onto the Composite Data Form for each demonstration site. Besides the house number, job size, labor cost, materials cost, and total cost recorded for the other options, an additional variable had to be recorded for attic insulation: the amount of thermal resistance (R-value) added. This need arose because across each site, the sample dwellings designated to have this option installed had variable amounts of insulation already in their attics. Therefore, different amounts of insulation had to be installed in these attics to achieve the R-value recommended for the particular site in question. In order to make the cost data for attic insulation comparable across houses and sites, all the figures are presented on a per R-value basis. To accomplish this, the R-value of the added insulation was calculated for each case using equation (3.8).

 $R = [W/(D \cdot A)] \cdot 12 V,$

where R = Thermal resistance of added insulation;

- W = Weight of the loose-fill insulation added, as determined by taking the product of the reported number of bags of insulation added and the reported number of pounds per bag;
- D = Density of the loose-fill insulating material once installed. The values used in the calculations were 2.75 lb/cf for cellulose insulation¹ and 2.0 lb/cf for rock wool insulation;²
- A = Area of attic floor covered by the added insulation, net of joists. Since the area figures reported on the Dwelling Unit Cost Data Forms are in gross terms (i.e., including joists), an adjustment factor of 0.906 was used to convert the reported gross areas to their corresponding net area values;³ and
- V = Thermal resistance of the insulating material per inch of added thickness. The values used in the calculations were 3.7 sf•h•°F/Btu for cellulose and 2.9 sf•h•°F/Btu for rock wool.⁴ Multiplication by 12 converts these values to R-values per foot of thickness.

To illustrate the application of equation (3.8), suppose a Dwelling Unit Cost Data Form reported that 15 bags of cellulose, each containing 30 pounds of material, were blown into an attic with 500 gross square feet of area. The R-value of the added insulation in this case would be approximately 16:

$$R = \frac{(15)(30)(12)(3.7)}{(2.75)(500)(0.906)} = 16.04.$$

- ¹ This value is the midpoint of the density range for cellulose published in American Society of Heating, Refrigerating, and Air-Conditioning Engineers, Inc. ASHRAE Handbook of Fundamentals, New York, 1972, p. 361.
- ² This value is based on the density range for rock wool given in Brookhaven National Laboratory, <u>An Assessment of Thermal Insulation Materials and</u> <u>Systems for Building Applications</u>, Report No. BNL-50862, June 1978, pp. 80-81.
- ³ This adjustment factor was determined by assuming a typical joist width of 1.5 in and 16 in on center construction. Thus, out of every 16 in of lineal dimension across the joists, 14.5 in are net of joists. These figures work out to a ratio of net to gross area of 0.906. It should be noted that this value ignores the effect of half the area of the two outermost joists. In addition, this approach assumes that none of the added insulating material lies above the top of the joists.
- ⁴ These values are taken from Brookhaven National Laboratory, <u>An Assessment of Thermal Insulation Materials and Systems for Building Applications</u>, pp. 80-84.

Once all of these values were calculated they were recorded on the Composite Data Forms along with the other information as specified for the non-attic options. With this additional information, the variation in amount of insulation added to the attics of the individual dwellings was taken into account when analyzing the corresponding costs.

The information from the Composite Data Forms, including the calculated R-value of the added attic insulation, was entered into a computer file. These attic cost data were processed somewhat differently from the non-attic data. Specifically, to control for the variation in amount of insulation added to each attic, all cost data items are denominated in terms of cents per square foot per R-value before the minimum, maximum, arithmetic mean, and median values are generated. In addition, these four summary statistics are calculated and printed for the R-value added variable. Furthermore, the two weighted statistics that are calculated for the total cost variable for attic insulation are not only weighted by job size, but by R-value as well. The equations applied to attic cost data to calculate the unweighted arithmetic mean and the mean weighted by job size and R-value, respectively, are:

$$\overline{X} = \frac{\underset{i=1}{\overset{i=1}{n}}}{\underset{n}{\overset{n}{\sum}}}, \text{ and} \qquad (3.9)$$

$$\overline{X}_{w} = \frac{\underset{i=1}{\overset{i=1}{n}}}{\underset{i=1}{\overset{n}{\sum}}}, \qquad (3.10)$$

where $R_i = R$ -value added to the attic and the remaining symbols are defined as for equations (3.5) and (3.6). Similarly, because of the need to account for variable R-values, the equation used to obtain the weighted standard deviation of total costs was modified as follows:

$$SD_{w} = \sqrt{\sum_{i=1}^{n} (T_{i}/S_{i} \cdot R_{i} - X_{w})^{2} \cdot (S_{i} \cdot R_{i}/\sum_{i=1}^{n} S_{i} \cdot R_{i})}, \qquad (3.11)$$

where all the symbols are defined as for equations (3.9) and (3.10).

All of the summary statistics for attic insulation are presented in subsection 4.2.2 by demonstration site.

3.3 WEATHERIZATION-RELATED REPAIR WORK

During the weatherization process, the need sometimes arose for a certain building component to be repaired in conjunction with the installation of an energy conservation option. For example, in several instances it was necessary to repair a roof before attic insulation could be installed These weatherization-related repairs occurred so infrequently and irregularly, however, that the cost data on them do not warrant being analyzed statistically. Instead, total expenditures for weatherization-related repair work are presented in subsection 4.3 by demonstration site and type of repair work.



4.0 DATA PRESENTATION

N

4.1 INFILTRATION OPTIONS

In this subsection the summary statistics described in subsection 3.1 are presented for the infiltration group of architectural options. Recall that the criterion for including cost data in this presentation is that both labor and materials cost data must have been reported for at least four dwellings for a particular option-site combination. There is a separate table for each option-site combination; all the infiltration options for each site are grouped together; and the tables for each site are presented in alphabetical order according to the name of the nearest metropolitan area. The abbreviations used in the tables are defined as follows:

MIN	= Minimum	OVERHEAD = Unit overhead and profit for
MAX	= Maximum	work done under contract and
SF	= Square feet	unit overhead and travel cost
LF	= Lineal feet	for work done in-house.
LABOR	= Unit labor cost	TOTAL = Unit total cost
ATERIAL	= Unit materials cost	STD DEV = Standard deviation

ALBUQUERQUE NM REPLACE BROKEN GLASS WORK DONE IN-HOUSE 4 JOBS REPOPTED

	SUM	MARY STATIST	105	
	MIN	мах	. TEAN	MEDIAN
JOB SIZE(SF)	4.1	34.9	15.0	10.6
LABOR (S/SF)	0.511	5.007	1.898	1.036
MATERIAL(\$/SF)	0.726	10.827	3.657	1.537
OVERHEAD (S/SF)	0.158	1.393	0.526	0.277
TOTAL(S/SF)	1.833	17.227	6.081	2.632

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(S/SF)	Ŧ	3.226	STD DEV(\$/SF)	*	3.824
*************		********			

ALBUQUERQUE NM WEATHERSTRIP DOORS WORK DONE IN-HOUSE 7 JOBS REPORTED

SUMMARY STATISTICS								
MIN	MAX	MEAN	MEDIAN					
31.5	51.0	38.9	34.0					
0.245	1.324	0.580	0.540					
0.264	2.266	0.947	0.720					
0.050	0.162	0.110	0.119					
0.694	3.656	1.636	1.296					
	SUM MIN 31.5 0.245 0.264 0.050 0.694	SUMMARY STATIST MIN MAX 31.5 51.0 0.245 1.324 0.264 2.266 0.050 0.162 0.694 3.656	SUMMARY STATISTICS MIN MAX MEAN 31.5 51.0 38.9 0.245 1.324 0.560 0.264 2.266 0.947 0.050 0.162 0.110 0.694 3.656 1.636					

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MCAN(S/LF)	E	1.579	STO DEV(S/LF)	=	0.924	
						T

ATLANTA GA WEATHERSTRIP DOORS WORK DONE IN-HOUSE 4 JOBS REPORTED

	MIN	MAX	NEAN	MEDIAN
JOJ SIZE(LF)	19.0	30.0	23.6	22.6
LABOR(S/LF)	0.091	0.315	0.225	0.247
MATERIAL(S/LF)	0.149	0.413	0.269	0.257
QVERHEAD(\$/LF)	0.042	0.152	0.109	0.120
TOTAL(S/LF)	0.465	0.607	0.602	0.568

MEAN(\$/LF)	-	0.593	STD DEV(S/LF)	#	0.123	
	•					
*************		*********	******************			

ATLANTA GA WEATHERSTRIP ATTIC HATCH WORK DONE IN-HOUSE 4 JOBS REPORTED

.

SUMMARY STATISTICS							
	MEN	HAX	1FAN	MEDIAN			
JOB SIZE(LF)	8.0	16.0	10.5	9.0			
LABOR(S/LF)	0.147	0.472	0.267	0.225			
MATERIAL(S/LF)	0.070	0.348	0.190	0-171			
OVERHEAD(S/LF)	0+052	0.179	0.089	0.062			
TOTAL(S/LF)	0.272	0.888	0.546	0.512			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(S/LF)	-	0.599	STD DEV(S/LF)	×	0.257
------------	---	-------	---------------	---	-------

CHARLESTON SC REPLACE BROKEN GLASS WORK DONE IN-HOUSE 12 JOBS REPORTED

	SU	MMARY STATIST	ICS				
**************				323323332383			
¢.	MIN	MAX	MEAN	MEDIAN			
JUB SIZE(SF)	2.8	16.9	5.9	4.8			
LABOR(\$/SF)	0.833	4.491	1.830	1.564			
MATERIAL(\$/SF)	0.877	2.500	1.422	1.246			
OVERHEAD(\$/SF)	0.335	4.138	1.452	0.966			
TOTAL(\$/SF)	3.239	7.929	4.704	4.107			
TOTAL COST STATISTICS WEIGHTED BY JOB SIZE							
HEAN(\$/SF)	= 4.391	STD D	EV(\$/SF)	= 1.190			

CHARLESTON S Reset glazin Hork Done In 9 Jobs Repo	C G -HQUSE		- 3 2				
	RTED						
***********	RTED						
	RTED	MARY STATIST					
	RTE D SU	MARY STATIST	1 C S 1 E A N	MEDIAN			
JOB SIZE(LF)	RTED SU MIN 8.0	MARY STATIST MAX 500.0	1 C S 4 E A N 16 3 • 8	MEOIAN 175.0			
JOB SIZE(LF) LABOR(\$/LF)	MIN 8.0 0.129	MARY STATIST MAX 500.0 0.562	1CS 1EAN 163.8 0.246	MEDIAN 175.0 0.218			
JOB SIZE(LF) LABOR(\$/LF) MATERIAL(\$/LF)	MIN 8.0 0.129 0.024	MARY STATIST MAX 500.0 0.562 0.125	1 C S 1 E A N 1 6 3 • 8 0 • 2 4 6 0 • 0 6 0	MEDIAN 175.0 0.218 0.048			
JOB SIZE(LF) LABOR(S/LF) MATERIAL(S/LF) OVERHEAD(S/LF)	RTED SU MIN 8.0 0.129 0.024 0.016	MARY STATIST MAX 500.0 0.562 0.125 0.339	1CS 4EAN 163.8 0.246 0.060 0.111	MEDIAN 175.0 0.218 0.048 0.090			
JOB SIZE(LF) LABOR(S/LF) MATERIAL(S/LF) OVERHEAD(S/LF) TOTAL(S/LF)	RTED SU MIN 8.0 0.129 0.024 0.016 0.181	MARY STATIST MAX 500.0 0.562 0.125 0.339 1.026	1CS 1EAN 163.8 0.246 0.060 0.111 0.417	MEDIAN 175.0 0.218 0.048 0.090 0.375			
JOB SIZE(LF) LABOR(S/LF) MATERIAL(S/LF) OVERHEAD(S/LF) TOTAL(S/LF) TOTAL	RTED SU MIN 8.0 0.129 0.024 0.016 0.181 COST STATI	MARY STATIST MAX 500.0 0.562 0.125 0.339 1.026 STICS WEIGHTE	1 C S 1 E AN 1 6 3 . 8 0 . 2 4 6 0 . 0 6 0 0 . 1 1 1 0 . 4 1 7 D BY JOB SI	MEDIAN 175.0 0.218 0.048 0.090 0.375			

CHARLESTON SC REPLACE THRESHOLDS WORK DONE IN-HOUSE 17 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	HAX	HEAN	MEDIAN			
JOB SIZE(LF)	2.7	12.0	5.7	5.3			
LABOR(\$/LF)	0.743	3.585	1.990	1.887			
MATERIAL(\$/LF)	1.000	1.132	1.085	1.126			
OVERHEAD(\$/LF)	0.298	7.082	1.404	0.900			
TOTAL(\$/LF)	2.775	10.635	4.479	3.806			
TOTAL C	OST STAT	ISTICS WEIGHTE	D BY JOB SI	۲E.			

MEAN(\$/LF) = 4.598 STD DEV(\$/LF) = 1.922

CHARLESTON SC SEAL STRUCTURAL CRACKS WORK DONE IN-HOUSE 13 JOBS REPORTED

SUMMARY STATISTICS								
	FILM	nex.	TEAN	HEULAN				
JOB SIZE(LF)	10.0	128.0	38.0	23.0				
LABOR(S/LF)	0.475	4.913	1.900	1.825				
MATERIAL(S/LF)	0.214	3.217	0.806	0.640				
OVERHEAD(\$/LF)	0.252	2.310	1.073	1.138				
TOTAL(S/LF)	1.129	10.440	3.779	3.274				

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(S/LF)	s 🕿 🕐	2.673	STD	DEV(3/L	F)	Ŧ	2.105	
*************								= = =

CHARLESTON SC CAULK WINDOWS AND DOORS WORK DONE IN-HOUSE 18 JOBS REPORTED

SUMMARY STATISTICS						
	MIN	нах	MEAN	MEDIAN		
JOB SIZE(LF)	160.1	457.0	259.7	250.0		
LABOR(\$/LF)	0.075	0.134	0.107	0.110		
HATERIAL(S/LF)	0.016	0.045	0.028	0.028		
OVERHEAD(S/LF)	0.012	0.305	0.075	0.043		
TOTAL(S/LF)	0.115	0.457	0.209	0.182		

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(S/LF)	*	0.192	STD DEV(S/LF)	-	0.085
*******		*********			*******

CHARLESTON SC WEATHERSTRIP WINDOWS AND DOORS WORK DUNE IN-HOUSE 15 JOBS REPORTED

***************************************	***************************************
SUMMARY	STATISTICS
***************************************	***************************************

•	MIN	MAX	MEAN	MEQIAN
JOB SIZE(LF)	28.8	94.0	48.4	33.0
LABOR(S/LF)	0.036	0.372	0.186	0.185
HATERIAL(\$/LF)	0.116	0.344	0.185	0.182
OVERHEAD(S/LF)	0.034	0.765	0.187	0.097
TOTAL(S/LF)	0.241	1.400	0.558	0.426

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(\$/LF) = 0.506	STO DEV(\$/LF)	E	0.259
---------------------	----------------	---	-------

CULORADO SPRINGS CO Replace broken glass Work done under contract 15 Jobs Reported

****************	S U	MMARY STATIS	TICS	**********
**************	*******	*********		*********
R	MIN	HAX	MEAN	MEDIAN
JOB SIZE(SF)	1.0	29.1	9.8	6.8
LABOR(\$/SF)	0.097	3.000	0.999	0.738
HATERIAL(\$/SF)	1.167	21.000	2.912	1.340
OVERHEAD(\$/SF)	0.177	9.000	2.026	0.839
TOTAL(\$/SF)	1.515	33.000	7 د 9 • 5	3.192

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(B/SF)	-	3.360		STD DEVE	¥/SE)	*	2.8	96
			*******	********	******			

COLORADO SPRINGS CO RESET GLAZING WORK DONE UNDER CONTRACT 7 JOBS REPORTED

SUMMARÝ STATISTICS							
	HIN	MAX	HEAN	MEDIAN			
JOB SIZE(LF)	8.0	150.0	39.9	24.0			
LABOR(\$/LF)	0.036	1.260	0.275	0.122			
MATERIAL(\$/LF)	0'.235	2.750	0.797	0.467			
OVERHEAD(\$/LF)	0.066	0.960	0.275	0.170			
TOTAL (S/LF)	0.495	4.990	1.347	0.698			

,

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(S/LF)	* * °0 • 78 3	STD DEV(\$/LF)	*	0.749
************	****************	*****************		

COLORADO SPRINGS CO REPLACE THRESHOLDS WORK DONE IN-HOUSE 16 JOBS REPORTED

SUMMARY STATISTICS						
*************	MIN	нах	MEAN	MEDIAN		
JOB SIZE(LF)	3.0	8.3	5.4	5.3		
LABOR(S/LF)	0.146	1.502	0.476	0.362		
MATERIAL(S/LF)	0.750	1.000	0.910	0.913		
OVERHEAD(\$/LF)	0272	3.510	0.614	0.452		
TOTAL(S/LF)	0.888	4.523	2.001	1.837		

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(S/LF)	æ	1.889	STD DEV(S/LF)	-	0.736
**************		***********	*******************		

CULORADO SPRINGS CO SEAL STRUCTURAL CRACKS WORK DONE IN-HOUSE 13 JOBS REPORTED

**************	********	**********					
SUMMARY STATISTICS							
***************	*******	************	***********				
X	MIN	MAX	MEAN	MEDIAN			
J08 SIZE(LF)	5.0	45.0	16.2	15.0			
LABOR(S/LF)	0.053	0.630	0.198	0.153			
MATERIAL(S/LF)	0.106	0.475	0.344	0.317			
OVERHEAD(S/LF)	0.015	0.244	0.115	0.116			
TOTAL(S/LF)	0.387	1.228	0.657	0.594			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(S/LF)	*	0.593	STO DEV(S/LF)	x	0.227	
*************	3232	********	*******************			=
COLORADO SPRINGS CO CAULK WINDOWS AND DOORS WORK DONE IN-HOUSE 18 JOBS REPORTED

	NIN	HAX	MEAN	MEDIAN
JOB SIZE(LF)	76.0	233.0	139.7	130.0
LABOR(\$/LF)	0.015	0.126	0.054	0.042
MATERIÁL(S/LF)	0.037	0.187	0.083	0.076
OVERHEAD(\$/LF)	0.005	0.108	0.038	0.026
TOTAL (S/LF)	0.086	0.395	0.176	0.168

REAN(S/LF)	= U.133	SID DEV(S/LF)	= 0.071
***********	************		

COLORADO SPRINGS CO HEATHERSTRIP WINDOWS HORK DONE IN-HOUSE 7 JOBS REPORTED

SUMMARY STATISTICS						
	MIN	HAX	HEAN	MEDIAN		
JO3 SIZE(LF)	7.0	120.0	38.0	30.0		
LABOR(S/LF)	0.080	0.959	0.393	0.256		
MATERIAL(S/LF)	0.037	0.347	0.245	0.286		
OVERHEAD (S/LF)	0.001	0.085	0.047	0.055		
TOTAL(\$/LF)	0.238	1.239	0.684	0.566		

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/LF) = 0.579 STD DEV(\$/LF) = 0.394

CULORADO SPRINGS CO HEATHERSTRIP DOORS HORK DONE IN-HOUSE 13 JOBS REPORTED

SUMMARY STATISTICS						
	MIN	мах	MEAN	MEDIAN		
JOB SIZE(LF)	17.0	50.0	33.9	33.0		
LABOR(S/LF)	0.048	0.590	0.210	0.191		
MATERIAL(\$/LF)	0.000	0.439	0.167	0.140		
OVERHEAD(\$/LF)	0.001	0.305	0.003	0.050		
TOTAL(\$/LF)	0.111	1.334	0.459	0.387		

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(S/LF)	*	0.458	STD DEV(\$/LF)	= 0.264
		*********	***************	

COLORADO SPRINGS CO WEATHERSTRIP ATTIC HATCH WORK DONE IN-HOUSE 9 JOBS REPORTED

SUMMARY STATISTICS

	MEN	MAX	MEAN	MEDIAN
JOB SIZE(LF)	5.3	20.0	10.5	8.0
LABOR(\$/LF)	0.046	0.479	0.238	0.202
MATERIAL(\$/LF)	3.049	0.147	0.114	0.130
OVERHEAD(\$/LF)	0.011	0.253	0.086	0.056
TOTAL(S/LF)	0.156	0.755	0.438	0.372

MEAN(S/LF)	*	0.44?	STD D	EV(S/LF)	=	0.215	
***********					*****		-

EASTON PA REPLACE BROKEN GLASS WORK DONE IN-HOUSE 15 JOBS REPORTED

	SU	JHHARY STATIST	ICS	

	MIN	HAX	MEAN	MEDIAN
JOB SIZE(SF)	0.8	36.3	11.3	8.5
LABOR(\$/SF)	0.184	9.962	2.834	1.802
MATERIAL (\$/SF)	.0.297	3.259	1.900	2.042
OVERHEAD(\$/SF)	0.020	4.600	0.728	0.345
TOTAL(S/SF)	0.501	16.150	5.463	4.537
TUTAL CO	IST STATI	ISTICS WEIGHTED	D BA JOR 21	l Z E
HEAN(\$/SF) =	3.779	STD DE	V(S/SF)	= 2.874

EASTON PA RESET GLAZING WORK DONE IN-HOUSE 11 JOBS REPORTED

*****	*******	**********	**********	
	St	JMMARY STATIS	TICS	
10	MIN	нах	HEAN	MEDIAN
JOB SIZE(LF)	6.0	48.0	23.5	12.0
LABOR(S/LF)	0.036	0.222	0.123	0.103
MATERIAL(\$/LF)	0.033	0.167	0.104	0.132
OVERHEAD(S/LF)	0.005	0.059	0.025	0.010
TOTAL (S/LF)	0.080	0.413	0.252	0.249

TOTAL COST S	ATISTICS WEIGHTED	ΒY	108 S	I Z E
--------------	-------------------	----	-------	-------

MEAN(\$/LF)	-	0.183	STD DEV(%/LF)	=	0.107	
**************		*********		***	*******	

EASTON PA CAULK WINDUNS AND DOORS WORK DONE IN-HLUSE B JOBS REPORTED

SUMMARY STATISTICS						
***************	MIN	MAX	MEAN	MEDIAN		
J08 SIZE(LF)	13.5	189.0	102.9	121.5		
LABOR(\$/LF)	0.041	0.141	0.075	6.063		
MATERIAL(\$/LF)	0.035	0.055	0.048	0.055		
OVERHEAD(\$/LF)	C.007	2.119	0.279	6.017		
TUTAL(S/LF)	0.049	2.245	0.403	0.130		

•

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(\$/LF) =	0.344	STD DEV(S/LF)	= 0.630

EASTON PA WEATHERSTRIP WINDOWS AND DUORS WURK DUNE IN-HOUSE 12 JOBS REPORTED

	**************************************	HARY STATIS		
	MIN	MAX	MEAN	MEUIAN
JUB SIZE(LE)	25.0	56.0	45.8	50.0

LASUR(E/LF)	0.111	3.019	0.621	0.413
MATERIAL (B/LF)	0.118	1.076	0.306	0.230
DY. R HEAD (SILF)	6.627	1.623	0.237	U.095
TUTA: (\$/1E)	0.304	· . 016	1.164	0.745

MEAN(S/LF)	Ŧ	1.161	STO LEV(S/LF)	= 1.264

FARGO ND WEATHERSTRIP WINDOWS WORK DONE UNDER CONTRACT 11 JOBS REPORTED

SUNMARY STATISTICS					
	MIN	НАХ	MEAN	MEDIAN	
JOB SIZE(LF)	75.0	261.0	163.9	187.0	
LABOR(\$/LF)	0.053	0.159	0.121	0.124	
MATERIAL(S/LF)	0.038	0.399	0.128	0.111	
OVERHEAD(\$/LF)	0.101	0.384	0.102	0.163	
TOTAL(\$/LF)	0.200	0.921	0.430	0.403	
TOTAL COST STATISTICS WEIGHTED BY JOB SIZE					

.

MEAN(S/LF)	= 0.429	STD DEV(\$/LF)	= 0.143
	***************	*****************	

FARGO ND WEATHERSTRIP DOORS WORK DONE UNDER CONTRACT 12 JOBS REPORTED

*************	**********	**********	*********				
SUMMARY STATISTICS							
****************	**********	*********	**********				
	, MIN	MAX	MEAN	MEDIAN			
JO3 SIZE(LF)	37.3	37.3	37.3	37.3			
LABOR(S/LF)	0.161	0.643	0.322	0.322			
MATERIAL(\$/LF)	0.264	0.264	0.264	0.264			
OVERHEAD (S/LF)	0.005	0.009	0.008	0.009			
TOTAL(S/LF)	0.432	0.916	0.594	0.595			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(S/LF) = 0.594 STD DEV(S/LF) 0.114

DAKLAND CA REPLACE BROKEN GLASS WORK DONE IN-HOUSE 8 JOBS REPORTED

SUMMARY STATISTICS

	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	6.3	52.4	24.5	17.0
LASOR(\$/SF)	0.630	4.937	1.601	1.147
MATERIAL (\$/SF)	0.550	5.141	1.755	1.090
OVERHEAD(\$/SF)	0.138	2.305	0.910	0.626
TOTAL(\$/SF)	1.547	10.215	4.266	3.902

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/SF)	-	5.119	STD DEV(S/SF) = 2.833

OAKLAND CA REPLACE THRESHOLDS WORK DONE IN-HOUSE 5 JOBS REPORTED

۶,

ch to

SUMMARY STATISTICS

	MIN	HAY	MEAN	MEDIAN
JOB SIZE(LF)	3.0	9.0	5.4	6.0
LABOR(S/LF)	0.497	1.248	0.768	0.673
MATERIAL(\$/LF)	0.817	1.250	1.069	1.167
OVERHEAD(S/LF)	0.187	0.498	0.368	0.453
TUTAL(S/LF)	1.500	2.888	2.205	2.227

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN (S/LF)	*	2.265	STD DEV(S/LF)	=	0.407
**************					********

30.

OAKLAND CA WEATHERSTRIP DOORS WORK DONE IN-HOUSE 5 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	MAX	YEAN	MEDIAN			
JOB SIZE(LF)	17.8	77.3	45.6	38.7			
LABOR(\$/LF)	0.139	0.436	0.266	0.256			
MATERIAL(\$/LF)	0.272	0.459	0.369	0.362			
OVERHEAD (S/LF)	0.071	0.242	0.128	0.110			
TOTAL(S/LF)	0.590	1.138	0.763	0.672			

MEAN(S/LF)	-	0.832	STD DEV($\$/LF$) = 0.224	



PORTLAND HE REPLACE BROKEN GLASS WORK DONE IN-HOUSE 4 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	Max	MEAN	MEDIAN			
JOB SIZE(SF)	4.0	21.9	11.6	10.2			
LABOR(\$/SF)	0.542	2.250	1.162	0.928			
MATERIAL (\$/SF)	0.786	1.659	1.114	1.006			
OVERHEAD(\$/SF) ^a	0.000	1.080	0.270	0.000			
TOTAL(\$/SF)	1.560	4.512	2.546	2.056			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/\$F) = 2.022 STD DEV(\$/\$F) = 0.805 ^a overhead and travel costs were not reported for all these houses

PORTLAND ME RESET GLAZING WORK DONE IN-HOUSE 4 JOBS REPORTED

SUNMARY STATISTICS								
	MIN	МАХ	MEAN	MEDIAN				
JUB SIZE(LF)	3.0	36.0	18.2	16.8				
LABOR(S/LF)	0.750	2.098	1.496	1.568				
MATERIAL(\$/LF)	0.251	3.636	1.747	1.550				
OVERHEAD(S/LF) ^a	0.000	0.000	0.000	0.000				
TUTAL(S/LF)	2.179	5.273	3.243	2.759				
LABOR(S/LF) MATERIAL(S/LF) OVERHEAD(S/LF) ^a TOTAL(S/LF)	0.750 0.251 0.000 2.179	2.098 3.636 0.000 5.273	1.496 1.747 0.000 3.243	1.565 1.550 0.000 2.759				

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/LF)		2.963	STD DEV(\$/LF)	=	1.268
-------------	--	-------	----------------	---	-------

^aOVERHEAD AND TRAVEL COSTS WERE NOT REPORTED FOR ALL THESE HOUSES

PORTLAND ME CAULK WINDOWS AND DOORS WORK DONE IN-HOUSE 8 JOBS REPORTED

SUMMARY STATISTICS								
	MIN	MAX	MEAN	MEDIAN				
JOB SIZE(LF)	32.0	323.0	165.6	152.0				
LABOR(S/LF)	0.067	0.168	0.113	0.119				
HATERIAL(\$/LF)	0.028	0.247	0.103	0.100				
OVERHEAD(\$/LF) ^a	0.000	0.186	0.050	0.021				
TOTAL(S/LF)	0.100	0.509	0.266	0.224				

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(\$/LF)	0.249	STD DEV(S/LF)	=	0.082

^aOVERHEAD AND TRAVEL COSTS WERE NOT REPORTED FOR ALL THESE HOUSES

PORTLAND ME WEATHERSTRIP DOORS WORK DONE IN-HOUSE 12 JOBS REPORTED

	SUMMARY STATISTICS								
		MIN	MAX	1EAN	MEDIAN				
109	SIZE(LF)	16.3	40.0	35.8	36.8				
LABO	R(S/LF)	0.056	0.612	0.192	0.125				
MATE	RIAL(\$/LF)	0.343	0.906	0.426	0.382				
OVER	HEAD(S/LF) ^a	0.000	1.236	0.184	0.095				
TOTA	L(\$/LF)	0.485	2.198	0.802	0.631				

MEAN(\$/LF)	= 0.8	11		STD	GEV(\$/LF)	π	0.	• 488	
 		******		= z = = z		*********				=
aOVERHEAD	AND	TRAVEL	COSTS	WERE	NOT	REPORTED	FOR	ALL	THESE	HOUSES

PORTLAND ME HEATHERSTRIP ATTIC HATCH HORK DONE IN-HOUSE 6 JOBS REPORTED

SUMMARY STATISTICS								
	MIN	MAX	MEAN	MEDIAN				
JOB SIZE(LF)	4.0	17.0	8.8	8.0				
LABOR(S/LF)	0.175	1.125	0.887	1.125				
MATERIAL (\$/LF)	0.113	1.772	0.568	0.275				
OVERHEAD(S/LF)ª	0.000	0.372	0.109	0.017				
TOTAL(\$/LF)	0.450	3.270	1.564	1.492				

MEAN(\$/LF)	= 1.2	36		STC	DEV(\$/LF)	z	0	.786	
	****	******	======				****	= = = = =		=
^a ove rhead	AND	TRAVEL	COSTS	WERE	NOT	REPORTED	FOR	ALL	THESE	HOUSES



4.2 CONDUCTION OPTIONS

4.2.1 Non-Attic Conduction Options

In this subsection the summary statistics described in subsection 3.1 are presented for non-attic architectural options in the conduction group. The same criterion for inclusion applies as for infiltration options: both labor and materials cost data must have been reported for at least four dwellings for a particular option-site combination. These tables are to be read in the same way as those for infiltration options in the previous subsection.

ALBUQUERQUE NM INSTALL STORM WINDOWS WORK DONE IN-HOUSE 6 JOBS REPORTED							
	SUM	MARY STATIST					
	MIN	MAX	MEAN	MEDIAN			
JOB SIZE(SF)	108.0	360.0	190.0	175.0			
LABUR(\$/SF)	0.168	0.347	0.228	0.204			
MATERIAL (\$75F)	0.256	2.810	0.936	0.635			
OVERHEAD(\$/SF)	0.016	0.053	0.039	0.041			
TOTAL (S/SF)	0.461	2.994	1.202	0.943			
TOTAL	COST STATIS	TICS WEIGHTE	12 80L Y5 C	ZE			

MEAN(\$/\$F) = 1.493 STD DEV(\$/\$F) = 1.036

ATLANTA GA INSTALL TRIPLE GLAZING WORK DONE UNDER CONTRACT 5 JOBS REPORTED

*****************				************				
SUMMARY STATISTICS								
	MIN	НАХ	MEAN	MEDIAN				
JOB SIZE(SF)	60.0	135.4	108.0	115.0				
LABOR(\$/SF)	0.287	0.549	0.415	0.388				
MATERIAL(\$/SF)	0.519	3.060	1.624	1.924				
OVERHEAD (\$/SF)	0.087	0.787	0.456	0.444				
TOTAL (\$/SF)	1.250	3.646	2.494	2.637				

MEAN(\$/SF)	æ	2.587	STD DEV(\$/SF)	=	0.906



CHARLESTON SC INSTALL FOUNDATION VENTS WORK DONE IN-HOUSE 5 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	MAX	MEAN	MEDIAN			
JUB SIZE(SF)	3.0	4.5	3.5	3.0			
LABOR(\$/SF)	3.750	6.667	5.306	5.000			
MATERIAL(\$/SF)	4.000	4.000	4.000	4.000			
OVERHEAD (\$/SF)	0.996	2.392	1.850	1.943			
TUTAL(\$/SF)	9.440	12.983	11.156	10.603			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

1EAN(S/SF)	36	10.951	STD	DEV(S/SF)) =	±	1.392	

CHARLESTON SC INSULATE CRAWL SPACE WITH STYRUFOAM WORK DONE IN-HOUSE 11 JOBS REPORTED

SUMMARY STATISTICS

	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	170.0	356.0	202.7	272.0
LABOR(\$/SF)	6.559	2.459	1.135	0.899
MATERIAL (\$75F)	0.759	1.083	0.876	0.825
OVERHEAD (\$75F	0.08.	.401	0.266	0.294
TUTAL(S/SF)	1 .	3 - 464	2.278	2.119

FUTAL CREET MATINFIC & IGHTED BY THE SIZE

4+44(\$/\$E) + 2.205 >TC DEV(\$/\$E) = 0.494

CHARLESTON SC INSULATE FLOOR JOISTS WITH FIBERGLASS BATTS WORK DONE IN-HOUSE 5 JOBS REPORTED

SUMMARY STATISTICS								
	MIN	MAX	MEAN	MEDIAN				
JOB SIZE(SF)	704.0	1184.0	975.2	1020.0				
LABOR(\$/SF)	0.067	0.080	0.072	0.071				
MATERIAL(\$/SF)	0.113	0.161	0.133	0.127				
OVERHEAD(\$/SF)	0.039	0.061	0.050	0.050				
TOTAL(\$/SF)	0.223	0.283	0.255	0.248				

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/SF) = 0.255 STD DEV(\$/SF) = 0.024



CULORADO SPRINGS CO Install Storm Windows Hurk Done Under Contract 16 Jobs Reported

SUMMARY STATISTICS					
	MIN	MAX	HEAN	MEDIAN	
JOB SIZE(SF)	4.0	150.4	58.1	52.0	
LABOR(\$/SF }	0.155	1.125	0.404	0.351	
HATERIAL(\$/SF)	1.150	3.019	2.068	2.050	
OVERHEAD (\$/SF	0.000	0.861	0.129	0.000	
TOTAL (\$7SF)	1.932	3.305	2,.601	2.546	

1EAN(\$/SF) = 2.552 STD DEV(3/SF) = 0.316

^a OVERHEAD AND PROFIT WERE NOT REPORTED FOR ALL THESE HOUSES

COLORADO SPRINGS CO INSTALL TRIPLE GLAZING YORK DONE IN-HOUSE 7 JOBS REPORTED

SUMMARY STATISTICS	

	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	2.4	11.7	6.9	5.8
LABOR(S/SF)	0.497	2.000	1.058	0.820
HATERIAL(\$/SF)	0.680	1.625	1.401	1.495
OVERHEAD (\$7SF)	0.113	0.550	0.282	6.296
TUTAL (\$/SF)	1.613	4.071	2.742	2.353

MEAN(\$/SF)	2.493	STD DEV(1/SF)	z	u.751
***********	 **********			

COLORADO SPRINGS CO INSULATE BASEMENT WALLS WITH FIBERGLASS BATTS WORK DONE UNDER CONTRACT 5 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	MAX	YEAN	MEDIAN			
JOB SIZE(SF)	290.0	500.0	379.0	342.0			
LABOR(\$/SF)	0.257	0.879	0.494	0.441			
MATERIAL (%/SF)	0.271	0.658	0.436	0.421			
OVERHEAD(\$/SF)	0.799	1.660	1.057	0.929			
TOTAL (S/SF)	1.457	2.427	1.987	1.960			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/SF)	*	1.945	STD DEV(\$/SF)	=	0.368	
		****======				-

COLORADO SPRINGS CO INSULATE FLGOR JOISTS WITH FIBERGLASS BATTS WORK DONE UNDER CONTRACT 4 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	MAX	MEAN	MEDIAN			
JO3 SIZE(SF)	460.0	1000.0	770.5	811.0			
LABOR(\$/SF)	0.114	0.413	0.242	0.219			
MATERIAL (\$/SF)	0.182	0.269	0.225	0.224			
OVERHEAD(\$/SF)	0.029	0.242	0.113	0.090			
FOTAL (\$/SF)	0.346	0.925	0.579	0.524			

MEAN(\$/SF)	2	0.517	STE	DEVISISHI	ء	0.207
1919122221122223		********				

COLORADO SPRINGS CO INSULATE WALLS WITH CELLULOSE WORK DONE UNDER CONTRACT 6 JOBS REPORTED

SUMMARY STATISTICS									
	HIN	MAX	MEAN	MEDIAN					
JOB SIZE(SF)	450.0	1120.0	869.2	920.0					
LAS DR(S/SF)	0.046	0.150	0.078	0.065					
MATERIAL(3/SF)	0.070	0.159	0.057	0.073					
OVERHEAD(\$/SF)	0.324	0.518	0.470	0.495					
TOTAL(\$/SF)	0.633	0.641	0.636	0.635					
TOTAL	COST STATI	STICS WEIGHT	ED BY JOB SI	ZE					

MEAN(\$/SF) = 0.635 STD DEV(6/SF) = 0.002

COLORADO SPRINGS CO INSULATE WALLS WITH UF FOAM WJRK DONE UNDER CONTRACT 10 JOBS REPORTED

 	. = =	 	z # 1	 .	= 3	==		* = =	= =		. = =		:=	= = :	= =	z 3	= 4	= =	= =	= =	 	= =	==	= =	=
						รบ	147	MAR	Y	ST4	TI	ST	I	cs											
 		 		 			-														 				-

	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	650.0	1188.0	902.7	871.5
LABOR(\$/SF)	0.036	0.123	0.055	0.045
MATERIAL(\$/SF)	0.103	0.174	0.121	0.109
OVERHEAD(\$/SF)	0.390	0.526	0.437	0.433
TOTAL (S/SF)	0.585	6.736	0.613	0.589

MEAN(\$/SF)	=	0.610	STD	DEVISISES	=	0.044

EASTON PA INSTALL TRIPLE GLAZING WORK DONE IN-HOUSE 7 JOBS REPORTED

*********	SUM	MARY STATIST	I C S	
	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	2.0	15.9	7.7	5.7
LABOR(\$/SF)	0.950	4.189	1.866	1.241
MATERIAL(\$/SF)	0.960	4.645	2.529	2.270
OVERHEAD (\$/SF)	0.128	1.528	0.514	0.450
TOTAL(\$/SF)	2.329	10.412	4.909	3.670

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

=

MEAN(\$/SF)	Ŧ	4.342	STD DEV(\$/SF)	=	2.578

EASTON PA INSULATE WALLS WITH FIBERGLASS WORK DONE UNDER CONTRACT 7 JOBS REPORTED

************		MMARY STATIS	TICS	
	MIN	нах	"EAN	MEDIAN
JUB SIZE(SF)	150.0	2350.0	1612.9	1800.0
LABUR(\$/SF)	0.111	0.272	0.174	0.184
MATERIAL(\$/SF)	0.160	0.160	0.160	0.160
OVERHEAD(\$/SF)	0.141	0.534	0.247	0.232
TOTAL(S/SF)	0.412	0.966	0.581	0.579

	1EAN(S/SF)	-	0.521	STD	DEV(S/SF)	Ŧ	0.089
--	------------	---	-------	-----	-----------	---	-------

FARGO ND INSTALL TRIPLE GLAZING HORK DONE UNDEP CONTRACT 13 JOBS REPORTED

					_
	۶U	MARY STATIS	TICS		-
	MIN	ХАМ	MEAN	MEDIAN	
JUB SIZE(SF)	60.0	190.0	114.3	96.0	
LABOR(\$/SF)	0.301	0.745	0.477	0.471	
MATERIAL(\$/SF)	0.135	0.576	0.510	0.528	
OVERHEAD(\$/SF)	0.423	1.110	0.769	0.738	
TOTAL(\$/SF)	1.015	2.302	1.757	1.720	

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

	HEAN(\$/SF)	*	1.754	STD	DEV(S/SF)	=	0.275	
= =	**********		********					= =

FARGO ND INSULATE BASEMENT WALLS WITH UF FOAM WORK DONE UNDER CONTRACT 7 JOBS REPORTED

SUMMARY STATISTICS								
	HIN	MAX	HEAN	MEDIAN				
JOB SIZE(SF)	407.0	504.0	427.6	460.0				
LABOR(\$/SF)	0.115	0.218	0.180	0.197				
MATERIAL(\$/SF)	0.272	0.336	0.303	0.304				
OVERHEAD (\$/SF)	0.003	0.329	0.134	0.132				
TUTAL(\$/SF)	0.485	6.830	0.617	0.581				

1EAN(\$/SF)	æ	0.615	STD DEV(\$/SF)	=	0.097
-------------	---	-------	----------------	---	-------

FARGO ND INSULATE WALLS WITH UF FOAM WORK DONE UNDER CONTRACT 12 JOBS REPORTED SUMMARY STATISTICS

	MIN	HAX	MEAN	MEDIAN
JOB SIZE(SF)	240.0	1040.0	821.1	856.0
LABOR(\$/SF)	0.132	0.245	0.171	0.152
MATERIAL(\$/SF)	0.133	0.256	0.106	0.152
OVERHEAD(\$/SF)	0.125	0.301	0.197	0.194
TOTAL (S/SF)	0.448	0.618	0.534	0.543

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(S/SF)	=	0.530	STD	DEV(\$/SF)	=	0 • 049	
		********		********	*****	*======	Ŧ



10

MINEAPOLIS/ST PAUL MN INSULATE RIM JOISTS WITH FIBERCLASS BATTS WORK DONE UNDER CONTRACT 17 JOBS REPORTED

SUMMARY STATISTICS								
***********************	*********		***********					
	MIN	MAX	HEAN	MEDIAN				
J09 SIZE(LF)	32.0	257.0	ප්ප් .4	80.0				
LABOR(\$/LF)	0.163	C •800	0.439	0.437				
MATERIAL (\$/LF)	0.412	0.499	0.425	0.420				
OVERHEAD(\$/LF)	0.148	1.271	0.528	0.501				
TOTAL(\$/LF)	0.732	2.251	1.392	1.271				
TOTAL	COST STATI	STICS WEIGHT	ED BY JOB SI	<i>L</i> E				

MEAN (S/LF)	æ	1.265	STD DEV(\$/LF)	=	0.423	
	= = = =		*****************	====		x :

MINEAPOLIS/ST PAUL MN INSULATE WALLS WITH UF FOAM WORK DONE UNCER CONTRACT 17 JOBS REPORTED

SUMMARY STATISTICS								
	*********	***********		***********				
	MIN	MAX	MEAN	MEDIAN				
JO3 SIZE(SF)	967.0	2448.0	1395.4	1072.0				
LABOR(\$/SF)	0.163	0.449	0.320	0.324				
MATERIAL(\$/SF)	0.180	0.556	0.294	6.238				
OVERHEAD(\$/SF)	0.128	0.796	0.330	0.244				
TOTAL (S/SF)	0.585	1.608	0.944	0.830				

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

4EAN(3/SF) = 0.917 STD DEV(3/SF) = 0.230

PORTLAND HE INSULATE BASEMENT WALLS WITH CELLULOSE WORK DONE UNDER CONTRACT 10 JOBS REPORTED

***************	SUMMARY STATISTICS						
	MIN	MAX	MEAN	MEDIAN			
JOB SIZE(SF)	463.0	1156.0	758.9	742.0			
LABOR(\$/SF)	0.149	0.321	0.198	0.179			
MATERIAL(\$/SF)	0.181	0.420	0.343	0.344			
OVERHEAD(\$/SF)	0.025	0.359	0.159	0.149			
TUTAL(\$/SF)	0.700	0.700	0.700	0.700			
OVERHEAD(\$/SF) TUTAL(\$/SF)	0.025	0.359	0.159	0.149			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/SF)	=	0.700	STD DEV(\$/SF)	Ŧ	0.000
**************	****	***********			

PORTLAND ME INSULATE WALLS WITH CELLULOSE WURK DONE UNDER CONTRACT 10 JOBS REPORTED

	*********		*********					
SUMMARY STATISTICS								
************	**********		***********					
	MIN	MAX	1 EAN	MEDIAN				
JOB SIZE(SF)	1570.0	3400.0	2367.0	2200.0				
LABOR(\$/SF)	0.015	0.091	0.044	0.032				
MATERIAL (\$/SF)	0.014	0.088	0.052	0.948				
OVERHEAD(\$/SF)	0.027	0.168	9.116	0.121				
TOTAL (S/SF)	0.119	0.275	0.211	0.722				

HEAN(\$/SF)	æ	0.212	STD	Sev(S/SF)	=	0 - 040
*************		***********			****	*******

PORTLAND ME INSULATE WALLS WITH CELLULOSE WURK DONE IN-HOUSE 5 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	MAX	1EAN	MEDIAN			
JO3 SIZE(SF)	778.0	1560.0	1113.2	909.0			
LABOR(S/SF)	0.051	0.101	0.066	0.058			
MATERIAL(\$/SF)	0.065	0.135	0.093	0.089			
OVERHEAD(\$/SF)	0.011	0.090	0.032	0.020			
TOTAL(\$/SF)	0.137	0.231	0.191	0.219			

MEAN(\$/SF)	0.190	STD	DEV(\$/SF)	=	0.043	
**********	 ********		**======*		*******	-



ST LOUIS MO INSTALL STORM WINDOWS WORK DONE IN-HOUSE 15 JOBS REPORTED

	SUM	MARY STATIST	ICS	
	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	26.8	289.4	120.6	106.0
LABOR(\$/SF)	0.197	0.913	0.504	0.521
MATERIAL(\$/SF)	1.563	2.890	2.014	2.034
OVERHEAD(\$/SF) ^a	0.000	0.000	0.000	0.000
TOTAL(\$/SF)	1.922	3.531	2.518	2.581

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/SF) = 2.432 STD UEV(\$/SF) = 0.400

^aOVERHEAD AND TRAVEL COSTS WERE NOT REPORTED FOR ALL THESE HOUSES



TACOMA WA INSTALL STORM WINDOWS WORK DONE UNDER CONTRACT > JOBS REPORTED

SUMMARY STATISTICS								
	MIN	HAX	MEAN	MEDIAN				
JOB SIZE(SF)	31.0	222.0	132.1	139.4				
LABOR(\$/SF)	0.324	1.076	0.759	0 • 809				
MATERIAL(\$/SF)	1.259	3.861	2.239	1.392				
OVERHEAD(\$/SF)	0.069	1.729	0.830	1.056				
TOTAL(\$/SF)	3.404	4.951	3.828	3.685				

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE MEAN(\$/SF) = 3.711 STD CEV(\$/SF) = 0.236

TACOMA WA INSULATE BASEMENT WALLS WITH UF FOAM WORK DONE IN-HOUSE 10 JOBS REPORTED

۰,

SUMMARY STATISTICS									
	HIN	HAX	MEAN	MEDIAN					
JO3 SIZE(SF)	82.5	266.0	163.1	167.0					
LABOR(\$/SF)	0.057	0.564	0.179	0.091					
MATERIAL(\$/SF)	0.087	0.651	0.253	0.112					
OVERHEAD(\$/SF)	0.004	0.148	0.057	0.035					
TOTAL(S/SF)	0.175	1.244	0.489	0.245					

MEAN(\$/SF)	×	0.413	STD DEV(+/SF)) =	0.377	
			**************			*

TACOMA HA INSULATE CRAWL SPACE HITH STYROFOAM WORK DONE IN-HOUSE B JOBS REPORTED

*************	**********								
SUMMARY STATISTICS									
	***********	*************	**********						
2	MIN	HAX	MEAN	MEDIAN					
JO3 SIZE(SF)	125.0	500.0	305.4	310.0					
LABOR(\$/SF)	0.236	1.289	0.643	0.671					
MATERIAL (\$/SF)	0.398	1.015	0.606	0.592					
OVERHEAD(\$/SF)	0.018	0.294	0.093	0.056					
TOTAL (\$/SF)	0.655	2.070	1.343	1.363					

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

MEAN(\$/SF)	 1.189	STD DEV(\$/SF)	=	0.410
		***************	****	

TACONA WA INSULATE WALLS WITH CELLULOSE WORK DONE UNDER CONTRACT 4 JOBS REPORTED

*********	**********	************	
SU	MMARY STATIS	TICS	
**************************************	**************************************	MEAN	MEDIAN
803.0	1418.0	1028.3	946.0
0.116	0.207	0.153	0.145
0.110	0.164	0.133	0.128
0.041	0.084	0.071	0.080
0.357	0.357	0.357	0.357
	SU MIN 803.0 0.116 0.110 0.041 0.357	SUMMARY STATIS MIN MAX 803.0 1418.0 0.116 0.207 0.110 0.164 0.041 0.084 0.357 0.357	SUMMARY STATISTICS MIN MAX MEAN 803.0 1418.0 1028.3 0.116 0.207 0.153 0.110 0.164 0.133 0.041 0.084 0.071 0.357 0.357 0.357

TOTAL	COST	STATI	STICS	WEIGHTED	BY	HUL	SIZE

MEAN(\$/SF) = 0.357 STD DEV(\$/SF) = 0.0	MEAN(\$/SF)		0.357	STD DEV(1/SF)	-	0.000
--	-------------	--	-------	---------------	---	-------

WASHINGTON DC INSTALL STORM WINDOWS WORK DONE IN-HOUSE 10 JOBS REPORTED

SUNNARY STATISTICS									
		MAX	MEAN	MEDIAN					
JOB SIZE(SF)	28.9	303.1	172.4	164.4					
LABOR(\$/SF)	0.403	0.793	0.562	0.565					
HATERIAL(\$/SF)	1.202	2.374	1.793	1.789					
OVERHEAD(\$/SF)	0.051	1.258	0.364	0.233					
TOTAL (\$/SF)	1.903	3.538	2.719	2.721					

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(\$/SF)	*	2.518	STD DEV(S/SF)	 0.435

WASHINGTON DC INSULATE FLOOR JOISTS WITH FIBERGLASS BATTS WORK DONE IN-HOUSE 5 JOBS REPORTED

140

SUMMARY STATISTICS						
	HIN	MAX	HEAN	MEDIAN		
JOB SIZE(SF)	140.0	1128.0	655.2	680.0		
LABOR (S/SF)	0.064	0.196	0.127	0.136		
MATERIAL(\$/SF)	0.170	0.370	0.271	0.288		
OVERHEAD(3/SF)	0.048	0.263	0.101	0.061		
TOTAL(S/SF)	0.369	0.639	0.500	0.500		

MEAN(S/SF)	-	0.476	STO LEV(S/SF)	=	0.062	

WASHINGTON DC INSULATE WALLS WITH CELLULOSE WORK DONE IN-HOUSE 4 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	MAX	MEAN	MEDIAN			
JOB SIZE(SF)	1120.0	2490.0	1539.5	1274.0			
LASOR(\$/SF)	0.123	0.273	0.217	0.237			
MATERIAL(\$/SF)	0.068	0.113	0.082	0.074			
OVERHEAD(\$/SF)	0.024	0.113	0.062	0.055			
TOTAL(\$/SF)	0.259	0.405	0.361	0.391			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN (\$/SF)	-	0.340	STD DEV(\$/SF)	Ŧ	0.067	
				3233.		= :

WASHINGTON DC INSULATE WALLS WITH UF FOAM WORK DONE UNDER CONTRACT 5 JOBS REPORTED

SUMMARY STATISTICS							
***********	#IN	MAX	######################################	MEDIAN			
JOB SIZE(SF)	960.0	2160.0	1504.8	1620.0			
LABOR(\$/SF)	0.135	0.172	0.151	0.155			
MATERIAL(\$/SF)	0.252	0.637	0.416	0.332			
OVERHEAD(\$/SF)	0.092	0.281	0.142	0.258			
TOTAL (S/SF)	0.700	0.748	0.710	0.700			

TOTAL COST STATISTICS WEIGHTED BY JOB SIZE

HEAN(\$/SF)	=	0.710	STD DEV(\$/SF)	z	0.020	



4.2.2 Attic Insulation

In this subsection the summary statistics described in subsection 3.2 are presented for attic insulation. The same criterion for inclusion applies as for non-attic options: both labor and materials cost data must have been reported for at least four dwellings for a particular option-site combination. As noted above, the attic unit cost data are denominated in terms of cost per square foot per R-value added. The symbol, R, used in these tables refers to the R-value added to the attic. In all other respects these tables are to be read in the same way as those for non-attic options in the previous subsections.



ALBUQUERQUE NM INSULATE ATTIC WITH FIBERGLASS WORK DONE IN-HOUSE 5 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	MAX	MEAN	MEDIAN			
JOB SIZE(SF)	154.5	3680.0	2057.7	2132.0			
R-VALUE ADDED	19.0	19.0	19.0	19.0			
LABOR(\$/R*SF)	0.001	0.006	0.002	0.001			
MATERIAL(\$/R*SF)	0.005	0.017	0.008	0.006			
OVERHEAD (\$/R*SF)	0.000 ^a	0.001	0.000	0.000			
TOTAL(S/R#SF)	0.006	0.024	0.011	0.007			

TOTAL COST STATISTICS WEIGHTED BY R-VALUE \neq JOB SIZE MEAN(\$/R \Rightarrow SF) = 0.007 STD DEV(\$/R \Rightarrow SF) = 0.003

a THE ZERO OVERHEAD COST IS DUE TO ROUNDING

ATLANTA GA INSULATE ATTIC WITH ROCK WOOL WORK DONE UNDER CONTRACT 9 JOBS REPORTED

	SUN	MARY STATIST	ECS	
	MIN	HAX	MEAN	MEDIAN
JOB SIZE(SF)	841.0	1350.0	1125.6	1122.0
R-VALUE ADDED	19.3	23.5	19.8	19.3
LABOR(\$/R*SF)	0.002	0.003	0.002	0.002
MATERIAL(\$/R*SFI	0.006	0.010	0.006	0.006
OVERHEAD (\$/R#SF1	0.002	0.004	0.003	0.003
TOTAL(\$/R*SF)	0.011	0.016	0.012	0.011
TOTAL COST S	TATISTICS	WEIGHTED BY	R-VALUE + JI	DB SIZE
MEAN(\$/R#SE1 =	0.012	STD DEVC	$S/R \neq SE) =$	0.002

CHARLESTON SC INSULATE ATTIC WITH CELLULOSE WORK DONE IN-HOUSE 17 JOBS REPORTED

SUNMARY STATISTICS							
	MIN	нах	MEAN	MEDIAN			
JOB SIZE(SF)	675.0	1890.0	1107.1	1088.0			
R-VALUE ADDED	8.9	26.6	17.4	18.1			
LABOR(\$/R*SF)	0.003	0.006	0.005	0.005			
HATERIAL (\$/R+SF)	0.005	300.0	0.005	0.005			
OVERHEAD(\$/R+SF)	0.001	0.004	0.003	0.002			
TUTAL(S/R#SF)	0.010	0.015	0.013	0.013			

TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*SF) = 0.012 STD DEV(\$/R*SF) = 0.001

a COSTS INCLUDE WEATHERSTRIPPING ATTIC HATCH

COLURADO SPRINGS CO INSULATE ATTIC WITH CELLULOSE HORK DONE UNDER CONTRACT 18 JOBS REPORTED

SUMMARY STATISTICS						
	MIN	MAX	HEAN	MEDIAN		
JOB SIZE(SF)	238.0	1075.0	739.7	800.0		
R-VALUE ADDED	4.6	48.9	16.9	14.5		
LABOR (\$/R+SF)	0.001	0.004	0.002	0.001		
MATERIAL (\$/R*SF)	0.005	0.008	0.007	0.007		
OVERHEAD(\$/R*SF)	0.008	0.035	0.010	0.009		
TOTAL(S/R#SF)	0.015	0.046	0.019	0.017		

TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE HEAN(\$/R+SF) = 0.018 STD DEV(\$/R+SF) = 0.006 -----

EASTON PA INSULATE ATTIC WITH CELLULOSE HORK DONE IN-HOUSE 9 JOBS REPORTED

SUMMARY STATISTICS						
	MIN	MAX	TEAN	MEDIAN		
JOB SLZE(SF)	400.0	1500.0	748.1	650.0		
R-VALUE ADDED	10.4	18.6	14-1	14.8		
LABOR(S/R+SF)	0.003	0.013	0.006	0.004		
MATERIAL (S/R#SF	0.003	0.012	0.006	0.006		
OVERHEAD(\$/R*SF	0.000 ^a	0.019	0.004	0.002		
TOTAL (S/R+SF)	0.007	0.044	0.016	0.014		

MEAN(\$/R+\$F) = 0.014 STU DEV(\$/R+\$F) = 0.010 ****************

THE ZERO OVERHEAD COST IS DUE TO ROUNDING

FARGO NO INSULATE ATTIC WITH CELLULOSE WORK DONE UNDER CONTRACT 12 JOBS REPORTED

SUMMARY STATISTICS							
	MIN	HAX	MEAN	NEDIAN			
JOB SIZE(SF)	305.0	1036.0	700.0	709.5			
R-VALUE ADDED	3.1	21.0	10.4	9.6			
LABOR(\$/R*SF)	0.004	0.018	0.009	0.008			
MATERIAL(\$/R*SF)	0.007	0.008	0.008	0.007			
OVERHEAD(\$/R+SF)	0.004	0.020	0.011	0.011			
TOTAL(S/R*SF)	0.019	0.040	0.028	0.027			

TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*SF) = 0.026 STD DEV(\$/R*SF) = 0.006

MINEAPOLIS/ST PAUL MM INSULATE ATTIC WITH CELLULUSE WJRK DUNE UNDER CUNTRACT 12 JOBS REPORTED

	· Sil	IMMARY STATISTI	CS			

	MIN	MAX	YEAN	MEDIAN		
JOB SIZE(SF)	550.0	1092.0	918.9	915.5		
R-VALUE ADDED	9.7	36.9	20.5	20.4		
LABOR(\$/R#SE)	0.004	C.uzt	0.003	0.006		
MATERIAL (\$/R#SE) 0.003	6.609	1.03	0.008		
JVER HEAD (SZP *SF) 0.003	C . L C 4	·· · · · · · · · · · · · · · · · · · ·	U. JUH		
TOTAL (S/POSE)	0.015	C.U++	9.025	0.022		

TOTAL COST STATISTICS WEIGHTED BY R-VALUE & JUB SIZE MEAN(S/R*SE) = 0.023 STE LEV(!/S*SE) = 0.008 OAKLAND CA INSULATE ATTIC WITH CELLULOSE WORK DONE IN-HOUSE 8 JOBS REPORTED

HIN MAX NEAN NEDIAN JOB SIZE(SF) 420.0 1210.0 831.9 875.0 R-VALUE ADDED 5.4 20.7 13.9 14.3 LABOR(\$/R*SF) 0.002 0.007 0.004 0.003 MATERIAL(\$/R*SF) 0.000 ^a 0.007 0.002 0.001 OVERHEAD(\$/R*SF) 0.000 ^a 0.007 0.002 0.001 TOTAL (\$/R*SF) 0.009 0.023 0.014 0.012	SUMMARY STATISTICS					
JOB SIZE (SF) 420.0 1210.0 831.9 875.0 R-VALUE ADDED 5.4 20.7 13.9 14.3 LABOR (\$/R*SF) 0.002 0.007 0.004 0.003 MATERIAL (\$/R*SF) 0.005 0.010 0.008 0.008 OVER HE AD (\$/R*SF) 0.000 ^a 0.007 0.002 0.001 TOTAL (\$/R*SF) 0.009 0.023 0.014 0.012 TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JJB SIZE MEAN(\$/R*SF) = 0.012 STD DEV(\$/R*SF) = 0.004		MIN	MAX	MEAN	HEDIAN	
R-VALUE ADDED 5.4 20.7 13.9 14.3 LABOR(\$/R*SF) 0.002 0.007 0.004 0.003 MATERIAL(\$/R*SF) 0.005 0.010 0.008 0.008 OVERHEAD(\$/R*SF) 0.000 ^a 0.007 0.002 0.001 TOTAL(\$/R*SF) 0.009 0.023 0.014 0.012 MEAN(\$/R*SF) 0.012 STD DEV(\$/R*SF) = 0.004 0.004	JOB SIZE(SF)	420.0	1210.0	831.9	875.0	
LABOR(\$/R*SF) 0.002 0.007 0.004 0.003 MATERIAL(\$/R*SF) 0.005 0.010 0.008 0.008 OVERHEAD(\$/R*SF) 0.000 ^a 0.007 0.002 0.001 TOTAL(\$/R*SF) 0.009 0.023 0.014 0.012 MEAN(\$/R*SF) 0.012 STD DEV(\$/R*SF) = 0.004 0.004	R-VALUE ADDED	5.4	20.7	13.9	14.3	
MATERIAL(\$/R*\$F) 0.005 0.010 0.008 0.008 OVERHEAD(\$/R*\$F) 0.000 ^a 0.007 0.002 0.001 TOTAL(\$/R*\$F) 0.009 0.023 0.014 0.012 TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*\$F) 0.012 STD DEV(\$/R*\$F) 0.004	LABOR(\$/R#SF)	0.002	0.007	0.004	0.003	
OVERHEAD(\$/R*\$F) 0.000 ^a 0.007 0.002 0.001 TOTAL(\$/R*\$F) 0.009 0.023 0.014 0.012 TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*\$F) 0.012 STD DEV(\$/R*\$F) 0.004	MATERIAL(\$/R*SF) 0.005	0.010	0.008	0.008	
TOTAL (\$/R*SF) 0.009 0.023 0.014 0.012 TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*SF) = 0.012 STD DEV(\$/R*SF) = 0.004	OVERHEAD(\$/R*SF	•) 0.000 a	0.007	0.002	0.001	
TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN($s/R*SF$) = 0.012 STD DEV($s/R*SF$) = 0.004	TOTAL ('\$/R*SF)	0.009	0.023	0.014	0.012	
	TOTAL COST MEAN(\$/R*SF) =	STATISTICS	WEIGHTED BY	R-VALUE * JJ \$/R#SF) =	8 SIZE 0.004	
THE ZERO OVERHEAD COST IS DUE TO ROUNDING	a THE ZERO OVERHEAD	D COST IS DUE	TO ROUNDING			

PORTLAND ME INSULATE ATTIC WITH CELLULOSE WORK DONE UNDER CONTRACT 10 JOBS REPORTED

SUMMARY STATISTICS					
	MIN	НАХ	MEAN	MEDIAN	
JOB SIZE(SF) 6	50.0	1650.0	1040.6	1050.0	
R-VALUE ADDED	7.3	30.3	15.1	14.2	
LABOR(\$/R*SF)	0.001	0.004	0.002	0.002	
MATERIAL (\$/R+SF)	0.006	0.007	0.006	0.006	
OVERHEAD(\$/R#SF)	0.001	0.023	0.011	0.011	
TOTAL (S/R*SF)	0.009	0.031	0.020	0.021	

TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*SF) = 0.018 STD DFV(\$/R*SF) = 0.006

PURTLAND ME INSULATE ATTIC WITH CELLULOSE WORK DONE IN-HOUSE 5 JOBS REPORTED

SUMMARY STATISTICS				
	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	660.0	1156.0	965.2	1000.0
R-VALUE ADDED	14.3	25.3	19.6	19.8
LABOR(\$/R*SF)	0.002	0.004	0.003	0.003
MATERIAL (\$/R+SF) 0.007	0.007	0.007	0.007
OVERHEAD (\$/R*SF) ^a 0.000	0.002	0.001	0.001
TOTAL(\$/R#SF)	0.010	0.012	0.011	0.012

TUTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*SF) = 0.011 STD DEV(\$/R*SF) = 0.001 a OVERHEAD AND TRAVEL COSTS WERE NOT REPORTED FOR ALL THESE HOLD

^aOVERHEAD AND TRAVEL COSTS WERE NOT REPORTED FOR ALL THESE HOUSES

ST LOUIS MO INSULATE ATTIC WITH CELLULOSE WORK DONE UNDER CONTRACT 13 JOBS REPORTED

SUMMARY STATISTICS					
	MIN	НАХ	MEAN	MEDIAN	
JOB SIZE(SF)	600.0	1000.0	976.6	1000.0	
R-VALUE ADDED	21.1	43.9	32.5	33.7	
LABOR(\$/R#SF)	0.000 ^a	0.019	0.009	0.009	
MATERIAL(\$/R*SF) 0.006	0.008	0.008	0.007	
OVERHEAD (\$/R*SF	0.003	0.012	0.007	0.007	
TOTAL (S/P*SF)	0.011	0.031	0.024	0.026	

TOTAL COST STATISTICS WEIGHTED BY R-VALUE # JOB SIZE MEAN(\$/R*SF) = 0.024 STD DEV(\$/R*SF) = 0.006

^aTHE ZERO LABOR COST IS DUE TO ROUNDING

TACOMA HA INSULATE ATTIC WITH ROCK WOOL WORK DONE UNDER CONTRACT 11 JOBS REPORTED

***************************************	***************************************
SUMMARY	STATISTICS
**********************************	***************************************

	MIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	540.0	1848.0	1014.9	980.0
R-VALUE ADDED	13.1	41.0	27.8	29.0
LABOR(\$/R#SF)	0.000 ^a	0.002	0.001	0.000
MATERIAL(\$/R*SF) 0.004	0.006	0.005	0.005
OVERHEAD(\$/R*SF) 0.005	0.018	0.007	0.005
TOTAL(\$/R*SF)	0.009	0.022	0.013	0.012

TOTAL COST STATISTICS WEIGHTED BY R-VALUE * JOB SIZE MEAN(\$/R*SF) = 0.012 STD DEV(\$/R*SF) = 0.002

^aTHE ZERO LABOR COST IS DUE TO ROUNDING

WASHINGTON DC INSULATE ATTIC WITH CELLULUSE WORK DONE IN-HOUSE 10 JOBS REPORTED

SUMMARY STATISTICS

	HIN	MAX	MEAN	MEDIAN
JOB SIZE(SF)	300.0	1400.0	327.2	842.0
R-VALUE ADDED	20.5	32.1	26.5	28.8
LAJOR(\$/R*SF)	0.003	0.006	0.005	0.005
MATERIAL (\$/R*SF) 0.006	0.020	0.008	0.006
UVERHEAD(\$/R*SF	0.001	0.005	0.003	0.003
TOTAL(\$/R#SF)	0.011	0.027	0.015	0.014

TOTAL COST STATISTICS WEIGHTED BY R-VALUE # JOB SIZE MEAN(\$/R*SF) = 0.015 STD DEV(\$/R*SF) = 0.005


4.3 WEATHERIZATION-RELATED REPAIR WORK

Table 4.1 presents cost data for the weatherization-related repair work described in subsection 3.3. The dollar amounts in the body of the table represent expenditures on each type of repair work for a particular city. Most amounts refer to work on a single house, except as explained in the footnote. The total column on the far right sums expenditures for each type of repair work across all cities. The total row at the bottom sums expenditures for each city across all types of repair work.

4.4 SUMMARY AND DISCUSSION OF WEATHERIZATION COST STATISTICS

Table 4.2 condenses the summary statistics presented in subsections 4.1 and 4.2 on the infiltration and conduction options by extracting the weighted mean of unit total cost from each table (i.e., option-site combination). As noted in subsection 4.2.2, however, the attic unit cost data are denominated on a per square foot per R-value added basis. In order to make these data comparable to the infiltration and non-attic conduction options, total cost per square foot measures are presented based on the mean R-value added across all sites, R-19. That is, the cost per square foot figures for attic insulation presented in table 4.2 are derived by extracting the weighted mean of total cost per "R" added per square foot from each option-site table and multiplying by 19.

			City			
ype of Repair Work	ATL	CHA	OAK	POR	TAC	TOTAL
epair or Replace Doors	162.02	434.53	1159.34	1052.82	607.74	3416.45
epair Structure	249.16					249.16
epair Roof	51.11	ţ	1907.00			1958.11
epair Window Frame					613.79	613.79
epair Window Sash		1167.26		38.64		1205.90
epair Gutters				294.29		294.29
epair Bulkhead Door				76.16		76.16
epair Eaves		72.72		159.73		232.45
epair Siding					1112.27	1112.27
TOTAL	462.29	1674.51	3066.34	1621.64	2333.80	9158.58

Expenditures (\$) for Weatherization-Related Repair Work, by City and Type of Repair Work

Table 4.1

Cost figures represent work done on a single house in every case except: Repair or Replace Doors in CHA (nine houses), in OAK (seven houses), in POR (four houses), and in TAC (three houses); Repair Window Sash in CHA (six houses); and Repair Siding in TAC (two houses). NOTE:

66

Table	4.2	Weight	ed Me	an Tot	al Cos	t of 1	Installed	Archit	ectural	Optic	ons, by	Lity,
	in I	Dollars	per L	ineal	Foot (\$/lf)	or Dollar	rs per	Square	Foot	(\$/sf) ^a	

							Ci	ty					
Option Description	Units	ALB	ATL	CHA	CSP	EAS	FAR	MSP	OAK	POR	STL	TAC	WAS
Infiltration Options													
Replace Broken Glass	(s/ef)	3.23		4.39	3,36	3.78			5,12	2.02b			
Reset Clazing	(\$/81)	3.23		0.27	0 78	0.18		•	5110	2 960			
Replace Thresholds	(\$/11)			4 60	1 80	0.10			2 27	2.00			
Seal Structural Gracks	(\$/11)			9.60	0.50				2.21				
Caulk Mindeus and Deems	(\$/11)			2.00	0.15	0.34				0.250			0.20
Weatherstyle Mindows	(\$/11)			0.19	0.10	0.34	0 4 3			0.23-			0.20
Weatherstrip Windows	(\$/11)	1 50	0.50		0.57		0.45		0.92	0 01 0		0.64	1.56
Weatherstrip Doors	(\$/11)	1.58	0.59		0.40		0.59		0.83	0.815		0.64	1.00
and Doors	(\$/1f)			0.51		1.16							
Weatherstrip Attic Hatch	(\$/lf)		0.60		0.44					1.24 ^b			
Conduction Options					c c								
Install Storm Windows	(\$/sf)	1.49			2.55						2.430	3.71	2.52
Install Triple Glazing	(\$/sf)		2.59		2.49	4.34	1.75						
Insulate Basement Walls wich Cellulose	(\$/sf)									0.70			
Insulate Basement Walls with Fiberglass Batts	(\$/sf)				1.95								
Insulate Basement Walls with Urea-Formaldehyde	(\$/sf)						0.62					0.42	
Install Foundation Vents	(\$/sf)			10.95									
Insulate Crawl Space with Styrofoam	(\$/sf)			2.21								1.19	
Insulate Floor Joists with Fiberglass Batts	(\$/sf)			0.26	0.51								0.48
Insulate Rim Joists with Fiberglass Batts	(\$/sf)							1.27					
Insulate Walls with Cellulose	(\$/sf)				0.64					0.21 ^d		0.36	0.34
Insulate Walls with Fiberglass	(\$/sf)					0.52							
Insulate Walls with Urea-Formaldehyde	(\$/sf)				0,61		0.53	0.92					0.71
Insulate Attic with Cellulose (R-value added=19) ^e	(\$/sf)			0.23 ^f	0.34	0.27	0.49	0.44	0.23	0.34 ^g	0.46		0.29
Insulate Attic with Fiber- glass (R-value added=19) ^e	(\$/sf)	0.13											
Insulate Attic with Rock Wool (R-value added=19) ^e	(\$/sf)		0.23									0.23	

^a Cost data were collected between the following dates: ALB 6/78-3/79; ATL 10/78-12/78; CHA 2/79-6/79; CSP 1/79-11/79; EAS 1/79-11/79; FAR 10/78-11/79; MSP 12/78-7/79; OAK 2/77-1/80; POR 2/78-5/79; STL 1/79-8/79; TAC 1/79-1/80; WAS 3/79-9/79.

b Overhead and travel costs were not reported for all these houses.

c Overhead and profit were not reported for all these houses.

d The measure of 0.21 \$/sf is for contracted wall insulation in Portland. A lower measure of 0.19 \$/sf was found for in-house wall insulation work.

^e The cost per square foot for adding R-19 attic insulation is derived by multiplying the cost per "R" added per square foot by 19.

f Cost includes weatherstripping attic hatch.

8 The measure of 0.34 \$/sf is for contracted attic insulation in Portland. A lower measure of 0.21 \$/sf was found for in-house attic insulation work. Table 4.3 presents the attic cost data in a slightly different manner. It gives the weighted mean of unit total cost based on actual R-values added in each city, rather than assuming R-19 was added. Thus, for each city, the cost per R added per square foot is multiplied by the mean R-value added in that city to come up with the cost per square foot for attic insulation.

On tables 4.2 and 4.3 one can compare the unit cost of architectural options across cities. In fact, there are 12 options that have reported costs from at least three demonstration sites. For many of these options such comparisons reveal a considerable degree of variation from city to city. Comparing the unit cost of replacing broken glass in table 4.2, for example, reveals that it varies by over two and one-half times between OAK and POR. Such significant variation implies that estimates of the cost of installing various architectural options may need to be based on estimating functions unique to each city in order to assure accuracy.

A number of factors may contribute to the variation in unit cost across cities. Regional differences in the costs of materials and labor constitute an obvious probable cause. Another likely source of variation is cost differences between contracted jobs and in-house jobs. Yet another is the presence of economies of scale, such that the size of a specific job becomes a relatively important factor in determining that job's unit cost.

Alternatively, it could be that differences across cities in the architectural designs of the demonstration dwellings cause the cost variation. For example, if it is more difficult to gain access to the attics of houses in one city than in another, such differences would be reflected in the corresponding costs of insulating the attic. (Note that the architectural design of a dwelling is distinct from its state of repair prior to weatherization. Differences in the state of repair would be reflected in the costs of weatherization-related repair work, presented in table 4.1).

A final possible source of variation in mean costs lies in the geographic locations of the dwellings within each demonstration site. Location is a source of variation because both travel distance and traffic congestion affect the travel component of option cost. For options installed by in-house labor, variations in cost due to differences in geographic distribution are reflected in the travel costs explicitly listed on the Dwelling Unit Cost Data Forms. For jobs done under contract, on the other hand, since travel cost is implicitly incorporated in total bid price, cost differences due to this source are not so readily apparent. Nevertheless, this implicit travel component is likely to vary from city to city.

The suggestions offered above as possible sources of intercity variation in the mean unit total cost of an architectural option do not constitute an exhaustive list. Furthermore, it is highly likely that the answer lies in some combination of sources rather than in a single source. Some of the possible sources of variation mentioned in this subsection warrant further study, and thus form the basis of several recommendations for further research elaborated in the concluding section of this report.

	Table 4.3.	Weighte in Doll	d Mean T ars per	otal Cost "R" added	of Insta per Squa	alled Att are Foot	ic Insula (Ş/R•sf)	tion Base and Dolla	d on Actu rs per Squ	al R-Valu uare Foot	ie Added : (\$/sf)a	by City,
							City					
Jnits	ALB	ATL	CHAb	CSP	EAS	FAR	MSP	OAK	POR	STL	TAC	WAS
\$/R•sf	6.007	0.012	0.012	0.018	6.014	0.026	0.023	0.012	0.018	0.024	0.012	0.015
R added	19.0	19.8	17.4	16.9	14.1	10.4	20.5	13.9	15.1	32.5	27.8	26.5
\$/sf	6.133	0.238	0.209	0.304	0.197	0.270	0.472	0.167	0.272 ^c	0.780	0.334	0.398
a Cellulo and TAC by mult	se was the , where roc iplying the	insulatin k wool wa cost per	g materi s added. R added	al added i The cost per squar	n all ci per sque e foot b	ities exc lare foot by the me	ept ALB w for addi an R-valu	here fibe ng the at e added.	rglass wa tic insul	s added, ation was	and ATL s derived	
b Costs i	nclude weat	herstripp	ing atti	c hatch.								

.

^C The measure of 0.272 \$/sf is for contracted attic insulation in Portland. A lower measure of 0.216 \$/sf was found for in-house attic insulation work.

69



5.0 RECOMMENDATIONS FOR FURTHER RESEARCH

This section describes further economic research that would be useful in support of the CSA Weatherization Demonstration Program. In order for this additional research to be possible, the collection of cost data on the four major groups of energy conservation options installed in the demonstration houses must first be completed. These four option groups are 1) conduction, 2) infiltration, 3) mechanical, and 4) hot water. The conduction and infiltration options comprise the architectural options discussed in this report. The mechanical option group includes those options that affect the operation of the building space heating system, and the hot water options are those directed toward improving the operating efficiency of the domestic hot water system. The collection of data on the total costs of installing these latter two types of options is currently underway.

Once all the field data have been collected as outlined above, the recommendations for energy conservation retrofits of low-income housing should be reassessed. The retrofit packages installed in the demonstration houses were selected on the basis of 1977-78 fuel prices, and energy savings and retrofit costs that were estimated before the fact. More recent fuel prices and data on energy savings and retrofit costs collected from the actual demonstration experience could be used to reassess the retrofit packages.

70

Recent fuel costs could be obtained by contacting all energy utilities serving the participating demonstration sites for the appropriate rate schedules. These schedules could be used to determine the marginal cost (including taxes and all surcharges) of a unit of fuel for each fuel type and site. These fuel cost data could then be used in a post-retrofit evaluation of the four major groups of energy conservation options installed in the demonstration houses. In conjunction with forthcoming estimates for each participating house of the annual purchased fuel savings attributable to each of the four option groups, the option and fuel cost data could be used to calculate for each house: (1) the present value cost of each option group based on the installed cost and expected replacement schedule of each option; and (2) the present value of the fuel savings attributable to each option group based on updated fuel prices and the latest DoE projections of fuel price increases. These present value measures could be used to assess whether the particular groups of options installed for each fuel type and demonstration site are actually cost effective in the sense of yielding a positive net return on the funds expended. The cost effectiveness of all the options combined could also be assessed for each participating house. These assessments of the cost effectiveness of retrofit packages would assist CSA, the Department of Energy, state and county energy offices, and other interested parties in deciding whether the originally recommended package of retrofit options can be expected to pay for itself over a reasonable time period.

The cost effectiveness of the attic insulation option could be more accurately measured with additional analysis. Because different amounts of attic insulation were added to each house within a demonstration site, the costs of this option had to be reported in terms of cost per square foot per R-value added. There is good reason to expect, however, that there is a significant fixed cost component being hidden in such a measure. For example, it is likely that the cost per square foot of adding R-22 is less than twice that of adding R-11. In other words, the average cost per R-value added is likely to be lower when more insulation is added to a given size attic. Regression analysis could be applied to the attic insulation cost data for each city in order to separate the fixed cost component corresponding to the labor time spent on gaining access and setting up equipment, from the variable labor and materials cost components corresponding to each increased unit of R-value added per square foot. In this way, the true marginal cost of increased insulation could be more accurately measured.

Another area in which further analysis would be useful deals with the question of possible economies (or diseconomies) of scale being present in the installation of architectural options. That is, the size of a particular job (e.g., square feet of wall area insulated) may be an important factor in determining the actual cost per square foot of the job. If this is the case, then the product of a flat (constant) unit cost times the job size will not provide the best estimate of the true job cost. Regression analysis can be useful here both to test whether economies (or diseconomies) do exist in the installation of these retrofit options, as well as to improve the accuracy of job cost estimates by taking job size into account. A fifth area involves the investigation of whether the cost of a specific option is significantly different for contracted jobs compared with in-house jobs. It may be that most of the differences in cost between these two categories are attributable either to other factors (such as regional cost differences) or to random variations. A number of statistical tests could be conducted to measure the extent of the true difference between contracted and in-house job costs.

One other area in which further study is warranted involves the updating of cost estimates. Most of the cost data collected and reported under this project refers to retrofits installed between October 1978 and December 1979. Because of the rather significant inflation that the U.S. economy is currently experiencing, the cost estimates for each retrofit need to be periodically updated, if they are expected to serve as a useful basis for future policy decisions. A specialized system of cost indexing should be developed to permit periodic revision of the cost estimates to take into account future changes in the costs of labor and materials. In formulating the index system, an attempt should be made to incorporate both time-related and location-related variations in cost.

REFERENCES

- 1. American Society of Heating, Refrigerating, and Air-Conditioning Engineers, Inc. ASHRAE Handbook of Fundamentals, New York, 1972.
- Brookhaven National Laboratory. An Assessment of Thermal Insulation Materials and Systems for Building Applications, Report No. BNL-50862, June 1978.
- Chapman, Robert E. et al. Optimizing Weatherization Investments in Low-Income Housing: Economic Guidelines and Forecasts, National Bureau of Standards Interagency Report 79-1948, Washington, D.C., February 1980.
- Crenshaw, Richard et al. CSA Weatherization Demonstration Project Plan, National Bureau of Standards Interagency Report 79-1706, Washington, D.C., March 1979.

NB5-114A (REV. 2-80)		· · ·							
U.S. DEPT. OF COMM.	1. PUBLICATION OR	2. Performing Organ. Report No. 3.	Publication Date						
BIBLIOGRAPHIC DATA	REPORT NO.								
SHEET (See instructions)	NBS1R 80-2167		November 1980						
WEATHERIZATION INVESTMENT COSTS FOR LOW-INCOME HOUSING									
5. AUTHOR(S)									
Stephen F. Weber,	Michael J. Boehm, and	Barbara C. Lippiatt							
6. PERFORMING ORGANIZA	TION (If joint or other than NBS	see instructions) 7.	Contract/Grant No.						
NATIONAL BUREAU OF 3 Department of comm Washington, d.c. 2023	STANDARDS ERCE 4	. 8.	Type of Report & Period Covered Final						
9. SPONSORING ORGANIZAT	TON NAME AND COMPLETE A	DDRESS (Street, City, Stote, ZIP)							
Community Services 1200 19th Street, Washington, D.C.	Administration N.W. 20506								
10. SUPPLEMENTARY NOTE	S								
Document describes a computer program; SF-185, FIPS Software Summary, is attached.									
11. ABSTRACT (A 200-word or less factual summary of most significant information. If document includes a significant bibliography or literature survey, mention it here)									
This report present of field data on the This project is par Demonstration Progra program involves the vation techniques f out the United State consist of a variet purpose of reducing methods used to col of installing these in the form of summ of the unit cost of The significant int suggests that unique sources of variation further research in selected sources of	s the results of a pro- s the results of a pro- e costs of retrofitting t of the Community Sec- am being carried out the e installation and even for over 200 single-far es. The energy consec- ty of architectural mode heat losses due either lect and synthesize the techniques are descri- ary statistics includ installing each arch ercity variation found to cost estimating pro- on in the mean unit co- aclude investigating the variation.	oject involving the colle ng low-income houses for rvices Administration Wea through the National Burge aluation of a broad range nily houses in 14 demonst rvation techniques discus difications to building e er to air infiltration on he field data on the major ibed. An analysis of the ing the weighted mean and itectural option in each d in the mean unit cost of cedures may be needed for sts are discussed. Recom- he effect on cost that ca	action and tabulation energy conservation. Atherization au of Standards. The of energy conser- tration sites through- ased in this report envelopes for the c conduction. The or cost components ese costs is presented d standard deviation demonstration site. of most techniques r each city. Possible mmendations for an be attributed to						
12. KEY WORDS (Six to twelv Building economics; economic analysis; unit costs; weather	e entries; alphabetical order; ca cost components; data energy conservation; ization.	pitalize only proper names; and sepa a analysis; data collect: insulation; low-income ho	rate key words by semicolons) ion; demonstration; ousing; statistics;						
13. AVAILABILITY			14. NO. OF PRINTED PAGES						
For Official Distributi	on. Do Not Release to NTIS	Port Printing Office West Law P							
20402.	dent of Documents, U.S. Governi	ment Printing Office, Washington, D.	C. 15. Price						
Order From National 1	Fechnical Information Service (N	TIS), Springfleld, VA. 22161							