NBSIR 84-2987



Outline of CCVT Calibration Procedure, EPRI-NBS Prototype System--Supplement to EPRI Report EL-690 (Field Calibration System for CCVTs, April 1978)

David L. Hillhouse

U.S. DEPARTMENT OF COMMERCE
National Bureau of Standards
National Engineering Laboratory
Center for Electronics and Electrical Engineering
Electrosystems Division
Gaithersburg, MD 20899

August 1984



U.S. DEPARTMENT OF COMMERCE

NATIONAL BUREAU OF STANDARDS

QC 100 .U56 84-2987 1984

c. 2



NBSIR 84-2987

OUTLINE OF CCVT CALIBRATION
PROCEDURE, EPRI-NBS PROTOTYPE
SYSTEM--SUPPLEMENT TO EPRI
REPORT EL-690 (FIELD CALIBRATION
SYSTEM FOR CCVTs, APRIL, 1978)

David L. Hillhouse

U.S. DEPARTMENT OF COMMERCE
National Bureau of Standards
National Engineering Laboratory
Center for Electronics and Electrical Engineering
Electrosystems Division
Gaithersburg, MD 20899

August 1984

U.S. DEPARTMENT OF COMMERCE, Malcolm Baldrige, Secretary NATIONAL BUREAU OF STANDARDS, Ernest Ambier, Director



TABLE OF CONTENTS

		Page
	tract	
۱.	INTRODUCTION	1
	1.1 Calibration Before Going to The Field	
2.	DETAILED CALIBRATION PROCEDURES	2
	2.1 Calibration Before Going to The Field	2 4 6
3.	PRECAUTIONS	6
4.	REFERENCES	6

LIST OF FIGURES

		Page
Figure 1.	Measurement 1 Voltage integrity, divider module	. 7
Figure 2.	Calibration of standard capacitor	. 8
Figure 3.	Measurement 3 Calibration of standard divider	. 9
Figure 4.	Measurement 4 On-line calibration of CCVT	.10
Figure 5.	Coaxial Choke Test Circuit	.11

OUTLINE OF CCVT CALIBRATION PROCEDURE, EPRI-NBS PROTOTYPE SYSTEM--SUPPLEMENT TO EPRI REPORT EL-690 (Field Calibration SYSTEM FOR CCVTs, April, 1978)

David L. Hillhouse

ABSTRACT

This report contains, in outline form, the step-by-step procedure for use of the EPRI-NBS Prototype Field Calibration System for Coupling Capacitor Voltage Transformers (CCVTs) in the calibration of CCVTs in the substation. It was prepared for the use of EPRI (Electric Power Research Institute) personnel at Waltz Mill, PA, where the system now resides. It is a supplement to the EPRI final report (EL-690, April, 1978) on the project in which the system was developed.

Keywords: calibration; CCVT; EPRI; high voltage; prototype; substation

INTRODUCTION

This report outlines the most important steps to be taken in the field calibration of CCVTs in the substation. It does not cover all the details of these procedures. Such details are more fully documented in the references given at the end of the report.

GENERAL NOTE: This report is a supplement to the final report [1] on the development and testing of this calibration system. Reference [1] should be studied carefully before attempting to follow the procedures outlined below.

The overall philosophy requires that the system must be calibrated at home before proceeding to the field; then recalibrated at the site. Following this, the test CCVTs are calibrated against the system, and the system calibration is repeated afterward for closure. Upon return home, the initial calibration of the system is repeated to gain assurance of overall stability.

1.1 Calibration Before Going to The Field

Calibration before going to the field consists of three steps, the first of which is optional, as follows:

Measurement 1 (OPTIONAL). Check of the voltage integrity of the transfer standard divider at 25% overvoltage, using the truck-mounted resonant power supply.

Measurement 2. Low-voltage calibration of the truck-mounted compressed gas standard capacitor.

Measurement 3. One-hundred-kilovolt calibration of the modular standard divider, using the truck-mounted resonant power supply.

Numbers in brackets refer to the literature references listed at the end of this report.

1.2 Field Calibration of Operating CCVTs

Field calibration of operating CCVTs consists of six steps, one of which is optional:

- Measurement 1. Same as Measurement 1 above.
- Measurement 2. Same as Measurement 2 above.
- Measurement 3. Same as Measurement 3 above.
- Measurement 4a. Check of the coaxial choke system in the signal cables.
- Measurement 4. On-line calibration of the substation CCVTs.

Measurements 2 and 3. Repeat for closure.

The procedure for recalibration of the system after return from the field is identical to that outlined in Section 1.1 for pre-calibration.

2. DETAILED CALIBRATION PROCEDURES

NOTE: FOR FURTHER DETAILS, SEE ESPECIALLY Sections 6-2, 7-5, and Appendix D of reference [1].

2.1 Calibration Before Going to the Field

- Measurement 1 (OPTIONAL). Check of the voltage integrity of the modular transfer standard divider.
 - Step (1) Connect the circuit as shown in figure 1, making sure to short out two of the three modules (500 kV configuration).
 - Step (2) Turn on the current comparator bridge and detector power supplies, adjust the detector for low gain. Introduce some noise by, e.g., inserting an ungrounded "antenna" into the detector input terminals, tune the detector for maximum 60 Hz output.
 - Step (3) Turn on the 100 kV resonant power supply, adjust input voltage to about 10% of full scale, resonate the circuit per the manufacturer's operating instructions, contained in his manual.
 - Step (4) Obtain a preliminary bridge balance (ratio of approximately 80:1) by alternately adjusting first the ratio and then the quadrature circuit for detector minimum. Increase detector gain as balance is approached.
 - Step (5) Once preliminary balance is obtained, increase voltage to 100 kV (120% of rated voltage per module).
 - Step (6) Rebalance the bridge, monitor for five minutes (time is arbitrary), record the results. Comparison with earlier data should show little shift over a period of months, and negligible five-minute drift.

- Step (7) Reduce the voltage to zero, shut off power, short a different pair of modules, repeat steps (3) through (6).
- Measurement 2. Low-voltage calibration of the truck-mounted 200 kV compressed gas standard capacitor.
 - Step (1) Connect the circuit as shown in figure 2.
 - Step (2) Turn on the bridge and detector power supplies, adjust detector for low gain. Introduce some noise, by, e.g., inserting an ungrounded "antenna" into the detector input terminals, tune the detector for maximum 60-Hz gain.
 - Step (3) Turn on the 250 V transformer power supply, adjust to full voltage.
 - Step (4) Obtain a preliminary bridge balance (ratio of approximately 10:1) by alternately adjusting first the ratio and then the quadrature circuit for minimum. Increase detector gain as balance is approached.
 - Step (5) Obtain final bridge balance, record the results. Typical values might be:

Ratio = 1.00191 Multiplier = 10 Phase Angle = 0.005 millimadians.

This represents the comparison of a 1000.00 pF reference standard capacitor with the nominally 100 pF compressed gas capacitor -- value above is $1000.00/(10 \times 1.00191) = 99.809$ pF.

- Step (6) Reduce voltage to zero, turn off the power, secure for safety [2].
- Measurement 3. One-hundred-kilovolt calibration of the modular transfer standard divider, using the truck-mounted resonant power supply.
 - Step (1) Connect the circuit as shown in figure 3 (500 kV configuration).
 - Step (2) Turn on the bridge and detector power supplies, adjust the detector for low gain. Introduce some noise, tune the detector for maximum 60-Hz output.
 - Step (3) Turn on the 100 kV resonant power supply, adjust the input voltage to about 10% of full scale, resonate the circuit.
 - Step (4) Obtain a preliminary bridge balance (ratio of approximately 250:1 for 500 kV configuration) by alternately adjusting first the ratio and then the quadrature circuit for detector minimum. Increase detector gain as balance is approached.
 - Step (5) When preliminary balance is obtained, increase voltage to 100 kV.
 - Step (6) Rebalance the bridge (there will have been a small shift due to divider voltage dependence), record the results. Typical values might be:

Ratio = 0.49775 Multiplier = 500 Phase angle = 2.60 milliradians.

As the mathematics in [1] will show, the standard divider (SD) ratio is obtained from a combination of the Measurement 2 and Measurement 3 values, as follows:

- SD Ratio = $(10 \times 1.00191)(500 \times 0.49775) = 2493.50$. SD Phase Angle = 2.60+0.005 = 2.65 milliradians.
- Step (7) Reduce the voltage to zero, turn off the power, secure for safety [2].

2.2 Field Calibration of Operating CCVTs

The first three measurements below are identical to those in Section 2.1.

- Measurement 1 (OPTIONAL). Check of the voltage integrity of the modular transfer standard divider.
- Measurement 2. Low-voltage calibration of the 200 kV truck-mounted compressed gas standard capacitor.
- Measurement 3. One-hundred-kilovolt calibration of the modular transfer standard divider, using the truck-mounted resonant power supply.

Measurement 4a. Check of the coaxial choke system (fig. 5)

NOTE: A discussion of the theory of Measurement 4a will be found in Appendix 6 of reference [3]. The choke test circuit is located on top of the bridge. It performs, by means of switches and a slightly different technique, the test shown in figure 18, Appendix A-6, reference [3]. The voltages of concern are V , between grounds G1 and G2, and V_{92} , between grounds G2 and G3, figure 16 of the same reference. These voltages must be cancelled in order to avoid significant error in Measurement 4.

- Step (1) Connect the circuit for CCVT calibration, as shown in figure 4, EXCEPT DO NOT MAKE the plugboard connections 1-9 and 2-7, as called for on page D-16 of reference [1], shown also as open circuits on figure 5 of this report.
- Step (2) With the center conductors of the standard divider (SD) and test piece (TP) signal cables shorted to shield at the divider and in the control house, respectively,
 - (a) Plug a DVM into the choke test circuit output.
 - (b) Select the SD choke with the standard divider position of the choke selector switch.
 - (c) With the function selector switch in the choke selector position, readthe "choke-in" voltage on the DVM (should be no more than a few millivolts if choke is working correctly).

- (d) With the function selector switch in the choke monitor position, read the "choke-out" voltage by the same means (may be 0.1 to 0.5 volts in a typical substation).
- (e) Select the TP choke with the test piece position of the choke selector switch, repeat the above procedure.
- (f) Place the function selector switch in position 4.

NOTE: The choke out position of the function selector switch can also be used to monitor the full line voltage (approximately 120 volts) when the system is in operation.

- Measurement 4. On-line calibration of the substation CCVTS.
 - Step (1) Connect the circuit as shown in figure 4, carefully following the safety procedures outlined in Sections 3 and 4 of reference [2].
 - Step (2) Turn on the bridge and detector power supplies, adjust the detector for low gain. Introduce some noise, tune the detector for maximum 60-Hz output.
 - Step (3) Instruct the control house to connect and identify the low side of a test piece (CCVT).
 - Step (4) Balance the bridge (ratio of approximately 1:1 for a 500 kV, three-module divider) by alternately adjusting first the ratio and then the quadrature circuit for detector minimum. Increase detector gain as balance is approached.
 - Step (5) Record the results. Typical values may be:

Ratio = 0.98989 Multiplier = 1.0 Phase Angle = 0.44 milliradians.

The CCVT ratio is obtained by combining the data from Measurements 2, 3, and 4. Using the values from Measurement 2, Step (5) and Measurement 3, Step (6):

CCVT Ratio = $(10 \times 1.00191)x$ (500×0.49775) $(1.0 \times 0.98989) = (10 \times 500 \times 1.0) \times (1.00191 \times 0.49775 \times 0.98989) = 2468.29$.

CCVT Phase Angle = 2.60+0.005+0.44 = 3.09 milliradians.

- Step (6) Switch control house connections to another CCVT, repeat Steps (3) through (5) above.
- Step (7) Disconnect from the high voltage bus, carefully following Section 5 of reference [2]. Repeat Measurements 4a and 4 for another phase.

Measurement 2 and 3. Repeat for closure.

At the end of each day, and at the end of the test, the divider is recalibrated, in order to correct for any drift in its values (primarily due to self-heating).

2.3 Recalibration after Return from the Field

Repeat the calibration outlined in Section 2.1 (Calibration Before Going to the Field).


3. PRECAUTIONS

Be sure to perform the ground voltage checks called for in for in Section 2.2, Measurement 4a, at least once for every change of phases.

Use the same standard divider cable for all measurements. This cable forms part of the divider low-side capacitance, so that it changes the value of a 2500:1 ratio (500 kV) by approximately 0.01% per meter of cable length.

4. REFERENCES

- [1] Hilhouse, D. L., Petersons, O., and Sze, W. C., A Prototype Field Calibration System for Coupling Capacitor Voltage Transformers (CCVTs), EPRI Final Report No. EL-690 (April 1978).
- [2] Hillhouse, D. L., Guide for Safe Operating Procedures...During the Field Calibration of CCVTs, NBSIR 81-2192, (Feb. 1981).
- [3] Hillhouse, D. L., Petersons, O., and Sze, W. C., A Simplified System for Calibration of CCVTs in the Substation, NBS Technical Note 1155, (May 1982).
- [4] Hillhouse, D. L., Petersons, O., and Sze, W. C., A Prototype System for On-Site Calibration of Coupling Capacitor Voltage Transformers (CCVTs), IEEE Transactions on Power Apparatus and Systems, Vol. PAS-98, (May/June 1979), 1026-1036.






Figure 3. Measurement 3 -- Calibration of Standard Divider.

Figure 4. Measurement 4 -- On-Line Calibration of CCVT,




Figure 5. Coaxigl Choke Test Circuit.

NBS-1144 (REV. 2-90)								
U.S. DEPT. OF COMM.	1. PUBLICATION OR REPORT NO.	2- Performing Organ. Report No.	3- Publication Date					
BIBLIOGRAPHIC DATA	REPORT NOL		August 1004					
SHEET (See instructions)	NBSIR 84-2987		August 1984					
4 TITLE AND SUBTITLE								
OUTLINE OF CCVT CALIBRATION PROCEDURE, EPRI-NBS PROTOTYPE SYSTEMSUPPLEMENT TO								
EPRI REPORT EL-690 (Field Calibration System for CCVTs, April 1978)								
_								
5. AUTHOR(S)								
David L. Hillhouse,	- Physicist							
		cominger state of	7.5					
LIN UNING UKGANIZA	MON-(If joint or other than NBS.	see insurctions)	7. Contract/ Grant No.					
NATIONAL BUREAU OF S								
DEPARTMENT OF COMME	ERCE		8. Type of Report & Period Covered					
WASHINGTON, D.C. 20234								
3. SPONSORING ORGANIZAT	TON NAME AND COMPLETE A	ODRESS (Street, City, State, ZIP))					
•								
10_ SUPPLEMENTARY NOTES	5							
TO THE TARE NOTE:								
	COMPLICATION	Soft-						
	computer program: SF-185, FIPS							
11_ ABSTRACT (A 200-word or bibliography or literature si	urvey, mention it here)	ignificant information. If docume	ent includes à significant					
a	, y	•						
This report contains, in outline form, the step-by-step procedure for use of the								
EPRI-NBS Prototype	Field Calibration Sys	tem for Coupling Capac	citor Voltage					
EPRI-NBS Prototype Transformers (CCVTs	Field Calibration Sysss) in the calibration	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sysss) in the calibration	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us	Field Calibration Sys s) in the calibration se of EPRI (Electric P	tem for Coupling Capac of CCVTs in the substa	citor Voltage ation. It was					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the	Field Calibration Syss) in the calibration se of EPRI (Electric Persystem now resides.	tem for Coupling Capac of CCVTs in the substa Power Research Institut	citor Voltage ation. It was te) personnel at Waltz					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides.	item for Coupling Capac of CCVTs in the substa lower Research Institut	citor Voltage ation. It was te) personnel at Waltz					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the	Field Calibration Syss) in the calibration se of EPRI (Electric Persystem now resides.	item for Coupling Capac of CCVTs in the substa lower Research Institut	citor Voltage ation. It was te) personnel at Waltz					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides.	item for Coupling Capac of CCVTs in the substa lower Research Institut	citor Voltage ation. It was te) personnel at Waltz					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the 12. KEY WORDS (Six to twelve calibration; CCVT;	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides.	item for Coupling Capac of CCVTs in the substa lower Research Institut	citor Voltage ation. It was te) personnel at Waltz					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides.	item for Coupling Capac of CCVTs in the substa lower Research Institut	eparate key words by semicolons)					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the 12. KEY WORDS (Six to twelve calibration; CCVT;	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides.	item for Coupling Capac of CCVTs in the substa lower Research Institut	eparate key words by semicolons)					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the 12. KEY WORDS (Six to twelve calibration; CCVT; 13. AVAILABILITY \(\text{Y} Unlimited \)	Field Calibration Syss) in the calibration se of EPRI (Electric Persystem now resides. entries: alphabetical order; cap. EPRI; high voltage; p	item for Coupling Capac of CCVTs in the substa lower Research Institut	eparate key words by semicolons) 14. NO. OF PRINTED PAGES					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the 12. KEY WORDS (Six to twelve calibration; CCVT; 13. AVAILABILITY \(\text{V} Unlimited \(\text{D} For Official Distribution} \)	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides. entries: alphabetical order: cap. EPRI; high voltage; p	of CCVTs in the substa lower Research Institut	eparate key words by semicolons) 14. NO. OF PRINTED PAGES 16					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the 12. KEY WORDS (Six to twelve calibration; CCVT; 13. AVAILABILITY \(\text{V} Unlimited \(\text{D} For Official Distribution} \)	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides. entries: alphabetical order: cap. EPRI; high voltage; p	item for Coupling Capac of CCVTs in the substa lower Research Institut	eparate key words by semicolons) 14. NO. OF PRINTED PAGES 16					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the 12. KEY WORDS (Six to twelve calibration; CCVT; 13. AVAILABILITY X Unlimited For Official Distribution Order From Superintend 20402.	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides. entries: alphabetical order: cap EPRI; high voltage; p	italize only proper names: and se rototype; substation	eparate key words by semicolons) 14. NO. OF PRINTED PAGES 16					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the 12. KEY WORDS (Six to twelve calibration; CCVT; 13. AVAILABILITY X Unlimited For Official Distribution Order From Superintend 20402.	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides. entries: alphabetical order: cap. EPRI; high voltage; p	italize only proper names: and se rototype; substation	eparate key words by semicolons) 14. NO. OF PRINTED PAGES 16					
EPRI-NBS Prototype Transformers (CCVTs prepared for the us Mill, PA, where the Mill, PA, where the calibration; CCVT; Unlimited For Official Distribution Order From Superintend 20402.	Field Calibration Syss) in the calibration se of EPRI (Electric-Pesystem now resides. entries: alphabetical order: cap EPRI; high voltage; p	italize only proper names: and se rototype; substation	eparate key words by semicolons) 14. NO. OF PRINTED PAGES 16 15. Price					



