

## NATIONAL BUREAU OF STANDARDS REPORT

3368

3.7

THE FIRE RESISTANCE OF PRESTRESSED CONCRETE BEAMS

by

J. V. Ryan

Report to

Bureau of Yards and Docks Department of the Navy



U. S. DEPARTMENT OF COMMERCE NATIONAL BUREAU OF STANDARDS U. S. DEPARTMENT OF COMMERCE

Sinclair Weeks, Secretary

NATIONAL BUREAU OF STANDARDS A. V. Astin, *Director* 



## THE NATIONAL BUREAU OF STANDARDS

The scope of activities of the National Bureau of Standards is suggested in the following listing of the divisions and sections engaged in technical work. In general, each section is engaged in specialized research, development, and engineering in the field indicated by its title. A brief description of the activities, and of the resultant reports and publications, appears on the inside of the back cover of this report.

Electricity. Resistance and Reactance Measurements. Electrical Instruments. Magnetic Measurements. Electrochemistry.

Optics and Metrology. Photometry and Colorimetry. Optical Instruments. Photographic Technology. Length. Engineering Metrology.

Heat and Power. Temperature Measurements. Thermodynamics. Cryogenic Physics. Engines and Lubrication. Engine Fuels. Cryogenic Engineering.

Atomic and Radiation Physics. Spectroscopy. Radiometry. Mass Spectrometry. Solid State Physics. Electron Physics. Atomic Physics. Neutron Measurements. Infrared Spectroscopy. Nuclear Physics. Radioactivity. X-Ray. Betatron. Nucleonic Instrumentation. Radiological Equipment. Atomic Energy Commission Radiation Instruments Branch.

Chemistry. Organic Coatings. Surface Chemistry. Organic Chemistry. Analytical Chemistry. Inorganic Chemistry. Electrodeposition. Gas Chemistry. Physical Chemistry. Thermochemistry. Spectrochemistry. Pure Substances.

Mechanics. Sound. Mechanical Instruments. Fluid Mechanics. Engineering Mechanics. Mass and Scale. Capacity, Density, and Fluid Meters. Combustion Control.

Organic and Fibrous Materials. Rubber. Textiles. Paper. Leather. Testing and Specifications. Polymer Structure. Organic Plastics. Dental Research.

Metallurgy. Thermal Metallurgy. Chemical Metallurgy. Mechanical Metallurgy. Corrosion.

Mineral Products. Porcelain and Pottery. Glass. Refractories. Enameled Metals. Concreting Materials. Constitution and Microstructure.

Building Technology. Structural Engineering. Fire Protection. Heating and Air Conditioning. Floor, Roof, and Wall Coverings. Codes and Specifications.

Applied Mathematics. Numerical Analysis. Computation. Statistical Engineering.

Electronics. Engineering Electronics. Electron Tubes. Electronic Computers. Electronic Instrumentation. Process Technology.

Radio Propagation. Upper Atmosphere Research. Ionospheric Research. Regular Propagation Services. Frequency Utilization Research. Tropospheric Propagation Research. High Frequency Standards. Microwave Standards.

•Office of Basic Instrumentation

• Office of Weights and Measures.

## NATIONAL BUREAU OF STANDARDS REPORT

## **NBS PROJECT**

NBS REPORT 3368

1002-30-4822 June 1, 1954

THE FIRE RESISTANCE OF PRESTRESSED CONCRETE BEAMS

by

J. V. Ryan

Τo

Bureau of Yards and Docks Department of the Navy Project Order No. 61705



# U. S. DEPARTMENT OF COMMERCE NATIONAL BUREAU OF STANDARDS

The publication, repri unless permission is of 25, D. C. Such permi cally prepared if that

Approved for public release by the Director of the National Institute of Standards and Technology (NIST) on October 9, 2015.

part, is prohibited dards, Washington rt has been specifiort for its own use.

The Fire Resistance of Prestressed Concrete Beams

by

## J. V. Ryan

## Abstract

Six fire-endurance tests of prestressed concrete beams were made to supplement the results from an extensive program in England which was designed to investigate the fire resistances of large beams by determining the fire resistance of geometrically similar scale models at various scales. Of the six beams tested here, five were at 4/5 scale and the sixth at 1/2 scale. Variables included beam section, concrete cover to the prestressed cable, and the use of lightweight insulating concrete as an outer shell. The test results reported provide the information on the behavior of prestressed concrete during fire exposure and tend to confirm the scale relationship previously observed with smaller specimens during fire tests in England.

### 1. INTRODUCTION

The use of prestressed concrete construction has become increasingly popular during recent years, largely because of the reduction in the amount of steel and concrete necessary to provide the required design strength and load capacity. This results in lower dead loads and conservation of building materials.

With the more frequent use of prestressed construction the fire resistance behavior of such constructions became important. A research program to study this behavior was therefore started at the British Fire Research Station, Elstree, in cooperation with the Building Research Station. A survey of prestressed concrete applications in large buildings led to the selection of a 20 ft span beam as the basic unit to be investigated. Because the size of the floor testing furnace would not permit tests of 20 ft long beams, the program was

carried out on geometrically similar small scale beams in the belief that a relationship between fire resistance and scale would be established by which the fire resistances of larger scale beams could be predicted. Tests were made on beams of three different design types at scales of 1/4, 3/8, and 1/2 of the 20 ft basic unit under various conditions of loading and restraint.

The results of the tests seemed to indicate a linear relationship between geometric scale and fire resistance for T-section beams with a single cable of prestressed wires, designated type A, and it appeared desirable to extend the range of information by obtaining data on such beams at larger scales. The National Bureau of Standards offered to perform tests on a series of beams of larger size because of its interest both in prestressed concrete construction and information on the value of tests of small models for determining what performance may be expected from large structures. The six tests described herein were undertaken in cooperation with the Bureau of Yards and Docks, U. S. Navy. The test specimens were built at the Building Research Station in England and shipped to this country by the Fire Research Station.

## 2. TEST SPECIMENS

Each of the six test specimens was different from all the others in some respect, but they had points of similarity. Three were type A beams (T-section, single cable) one of 1/2scale, for the purpose of correlation with the tests at the British Fire Research Station, one of 4/5 scale, and the third 4/5 scale with 1-in. protection of reinforced vermiculite concrete on bottom and sides of the beam and the underside of the top slab. A fourth beam was type D, 4/5 scale, similar to type A, but having a greater concrete cover to the cable. The fifth and sixth beams were type E, 4/5 scale, identical to type A except that type E had no top slab. The maximum compressive stresses in a fully loaded T-section beam (types A and D) occur at the slab's upper surface, which is not exposed to the fire. The E type beam was introduced in order that the zone of maximum compressive stresses, located at the top of the rectangular section, would be within the furnace and therefore experience more severe fire exposure. One of the type E beams had 1 in. of vermiculite concrete on bottom and sides.

-

, .

The beams were designated by National Bureau of Standards fire test numbers and by a three-part system of notation used by the British, which consisted of type letter, scale fraction, and thickness of vermiculite concrete protection in inches. For example, A:1/2:0 indicated an A type beam of 1/2scale with no (0-in.) vermiculite concrete protection. The test numbers and beam notations are given in table 1.

Each of the beams was of uniform cross section over the center half of the span, increased in depth by bottom haunches to near each end, increased in width immediately beyond the haunches, and were of constant depth and width at each end bearing. The haunches were incorporated in the design to allow the use of straight prestressed cable cavities and still provide the greater bottom cover near the ends that would be found in beams in which a curved cable and cavity were used.

The ends of the prestressed cable and their anchorages, which extended beyond the ends of the beam proper, were encased in concrete. The dimensions of the various test specimens are given in figure 1. The prestressed cable in the 1/2 scale beam consisted of 32 steel wires of 0.103 in. diameter (12 ga British Standard Gage) while the cables in the 4/5 scale beams each consisted of 24 steel wires of 0.2 in. diameter. The wires were of cold drawn steel having tensile strengths as shown in table 3. The vermiculite concrete protection had been cast in 1-in. thick slabs with 1 1/2-in. ' hexagonal mesh 0.040 in. diam (No. 19 B.S. Ga) wire fabric at the mid-thickness, cut to the desired sizes and shapes, and placed to line the molds of the beams to be so protected. The gravel aggregate concrete for the beam proper was then cast into the lined mold, forming a direct bond with the vermiculite concrete slabs. The pattern of protective slabs, and the joints between, is shown in figure 2.

The concrete aggregate for the beams, including the top slabs of the T-sections, was a river gravel from the Thames valley. The mix proportions and water cement ratio were selected to give a compressive strength of 6000 lb/in.<sup>2</sup> at 28 days, when tested in the form of 6-in. cubes. (The strengths of 6- by 12-in. cylinders may be estimated by multiplying these values by 0.85, giving about 5100 lb/in.<sup>2</sup>). For the A:1/2:0 beam the proportions by weightwere approximately 1 part of rapid hardening portland cement, 1 3/4 parts of sand (3/16 in. max size), 2 5/8 parts of gravel (3/16 to 3/8-in. size). For the 4/5 scale specimens, the proportions by weight were 1 part of rapid hardening portland cement, 1 1/2 parts of sand (3/16 in. max), part of gravel (3/16 to 3/8 in. size), and 2 parts of coarser gravel (3/8 to 3/4 in. size). The water-cement ratio by weight was 0.48 for all specimens. A

•

petrographic survey of a sample of gravel recovered from one beam after test indicated the composition to be 95 to 98 percent chert (or flint). This gravel is one of the most common concrete aggregates in use in Britain; the particular gravel selected was a fair representative of its class.

The rectangular portions of the T-beams were cast first, with castellations along the top. The rectangular element was stressed seven or eight days after casting, when the cube strength of the concrete was at least 4500 lb/in.<sup>2</sup>, the initial stress in the cable being 145,600 lb/in.<sup>2</sup> (65 long tons/in.<sup>2</sup>). A grout of rapid hardening portland cement and water, in the ratio of 0.4/l by weight, was injected into the cable duct when tensioning was completed. The slabs for the A and D type beams were then cast on the castellated upper faces of the beams. During the period between completion of manufacture and shipment from England the specimens were stored in the open. During the 2 1/2 to 3/1/2 month period between arrival at the National Bureau of Standards and testing, they were stored indoors at approximately 70° F and 50 percent relative humidity.

## 3. TEST METHOD AND EQUIPMENT

The beams were subjected to tests under the provisions of British Standard 476, Fire Tests of Building Materials and Structures, with additional data taken to provide the basis for comparison with ASTM E119-50, Standard Methods of Fire Tests of Building Construction and Materials. The former requires that a beam continue to support the test load (representing the assumed dead load plus 1 1/2 times the design load) while exposed to furnace fires controlled to produce temperatures as close as possible to: 1000° F (538° C) at 5 min, 1300° F (704° C) at 10 min, 1550° F (843° C) at 30 min, 1700° F (927° C) at 1 hr, 1850° F (1010° C) at 2 hr, 2050° F (1121° C) at 4 hr, and 2200° F (1204° C) at 6 hr. The furnace temperatures were measured by 12 chromel-alumel thermocouples of 18 ga wire encased in ceramic insulators but with the junctions and about 1 in. of the wires bare. Six other thermocouples were located in the concrete and six on the wires of the prestressed cable. The former were 19 ga chromel-alumel while the latter were steel-constantan, employing an individual wire of the cable as half of each thermocouple. For those beams (tests 334 and 336) with vermiculite concrete protection, other thermocouples of 19 ga chromelalumel wire were located at the inner face of the vermiculite concrete. In addition, 12 thermocouples in wrought iron pipes (per ASTM E119-50) were distributed throughout the furnace to

•

provide comparative data. However, the temperatures measured by the bare thermocouples were used as the indication of proper furnace control in each test. The locations of the various thermocouples in the beams are indicated in figure 3.

Each beam was placed in the floor test furnace, in spe-cial supports prepared to receive it. The beam was located mid-way between the furnace sides with the underside of the top slab level with the undersides of the other concrete slabs used to fill out the remainder of the furnace opening. A gap of about 1 in. was left between these slabs and the test specimen, which gap was filled with mineral wool insulation. Separate slabs were cast to be placed on the type E beams. I slabs were made about 5-in. deep except at the center and These quarter points where glass fiber inserts, 2- by 5- by 32 in. kept the top slabs from being rigid and continuous. Full length reinforcing bars tied the slab sections and inserts together without rigidity. This was done to provide a flexible method of loading the beam and closing the furnace opening. The beams were baded at four points, the 1/8, 3/8, 5/8 and 7/8 points of span, by means of the mechanism shown in figure 4. The loads applied to the various beams, as well as other data, are given in table 1. The computed stresses in the concrete, before and after loading, were as given in table 2. The beams were tested under conditions described as loaded and unrestrained against longitudinal expansion.

#### 4. RESULTS

The results of the tests are given as logs of test observations, plots of the temperatures recorded, and representative photographs.

## 4.1 Test 331-A:1/2:0 beam

During the first 1 hr 10 min the beam showed no heat effects other than reddening of the edges and some deflection; at 1 hr 25 min, cracks across the beam were observed near center span and the deflections were increasing rapidly; 1 hr 29 min, crack across soffit, deflection nearly 4 in., load removed; 1 hr 37 min, gas off.

The temperatures indicated by the steel cable thermocouples changed rather erratically during the test. However, the furnace temperature control was fairly good, and the temperatures at the various locations in the beam rose in smooth curves, as shown in figure 5.

Romonira Bomonira	NCILGI AS		Reloaded cold, failed under ori-	ginal ap <mark>-</mark> plied load			Loaded to failure	68,910 lb 1ive load			action area
Fire Ex-	severity	percent	7.76		103.3	101.6	99.5		0.47	7.66	am type; f1 1 inches. atures to
e Temp ailure	Max	Чo	716		1072	1652	793	רקג ר		019	to bea rete in temper
Cabl at f	Av	ч	610		1069	r- 788	698	L77		717	refers conc rurnace
Type of			Deflec- tions		Beam & cable broke	Cable ex posed	none	20 0 11	broke	broke	Letter ermiculit average f
 Duratior of	: test	hr:min	1:29		3:40	2:36	6:02	ןן ע ר		4:3%	y B.R.S.: ness of v curve of
: Load	•••••	1b	24,400		58,200	59,600	59,600	000 90	<b>, , , , , , , , , ,</b>	20,200	oduced b to thick
. Age at	test	៨ឧ	238		223	256	262	240		107	n intr umber of are
B.R.S. Markino	9		B <b>P</b> 28		BP 34	B <b>P</b> 29	B <b>P</b> 30	д С с с с с С с		br 33	notatic final n s ratio
Symbol for	beam 1/		A:1/2:0		D:4/5:0	A:4/5:0	A:4/5:1	円・// / J ・ ()		T: <td>ystem of o scale, efined a:</td>	ystem of o scale, efined a:
NBS Test	0 N		331		332	333	334	Ц vv		055	D t S

Table 1. Summary of Results

1.

Table 2. Applied loads for the different beams and estimated stresses in the concrete

	··· ·			1				
	:: 1b/in. <sup>2</sup>	applied	At soffit of beam		-580	-580	- 600	- 580
	ge of test	load is a	.At top .of rec- .tangular slab		330	220	1490	2340
	te at a	er test	Under- side of slab		330	320	390	1
a contraction of the second	the concre	: Aft	At top of slab		1220	1200	980	1
6	esses in t	plied	At soffit of beam		1630	1590	760	1700
	essive stre	load is ap	.At top of rec- A tangular slab		. 10	- 80	120	20
	ed compr	ore test	Under- side of slab		10	20	140	ł
	Estimate	Bef	At top of slab		60	06	06	i t
		Applied	load	lЪ	24,1400	59,600	58,200	26,200
	•• •	• ••	Scale		1/2	4/5	4/5	4/5
	E	of 10	tior.		A	A	A	E

The day after the test, the beam had recovered some of the deflection and a reloading test was made. The beam failed under a load of 10.4 long tons, almost the same as the test load. Following the reloading test, when the specimen was broken up, it was found that all of the wires in the prestressed cable were unbroken but the steel-constantan junctions were rusty, possibly accounting for the observed variations in cable temperatures. The conditions of the beam after the fire test and after the reloading test are shown in figures 6 and 7.

## 4.2 Test 332-D:4/5:0

During the first hour the beam showed no heat effects other than reddening, some deflection and emission of steam; at 1 hr 10 min, two small pop-outs and four short cracks in beam; 1 hr 13 min, crack 1 to 3-in. from bottom of beam runs full length, about 1/8-in. wide; 1 hr 30 min, cracks wider; 1 hr 43 min, considerable concrete fell from bottom and one side of south haunch, about 2-in. deep; 1 hr 54 min, cracks along beam up to 2-in. wide, fall of concrete from north haunch; 1 hr 56 min, concrete down from 3 to 4 ft of south haunch and beam, 2- to 3-in. deep; 3 hr 31 min, considerable concrete fell from west face of beam near center of span; 3 hr 38 min, concrete fell from full width of beam, north half, 3-in. deep, pressure in loading system unsteady; 3 hr 40 min, beam broke and collapsed; 3 hr 41 min, gas off.

The furnace control was fairly good, the average temperature having been near or slightly above the Standard curve throughout the test. The temperatures at the various locations in the beam rose to about 212° F (100°C) and leveled off for periods ranging from 10 min to 1 hr 10 min before continuing upward, apparently indicating time required to eliminate moisture. The cable temperatures behaved in a similar manner but remained near 212° F about 1 3/4 hr. The temperature curves are shown in figure 8.

After the test, the beam and slab were found to have broken in the middle, and the bottom concrete had broken off to expose the prestressed wires from haunch to haunch. The breaks in the broken wires were not all in one location but were divided into two locations, as shown in figure 9. All the wires were broken.

At 12 min, water was dripping from the beam at center span; 15 min, four or five puddles of water, each 3 to 10 in. across, on top of slab near each quarter point; 20 min, two transverse hairline cracks in top slab near each quarter point, water or steam therefrom bubbling into covering puddle; 34 min, water from beneath steel plates on top slab at two loading points; 53 min, short longitudinal crack 1 in. from bottom of east side of south haunch; 1 hr 23 min, eight transverse cracks in top slab ranged from hairline to 1/16-in. wide; 1 hr 32 min, 1 ft long crack 1 in. from bottom of east face near center span; 2 hrs, cracks in beam 1/8- to 1/4-in. wide; 2 hr 4 min, momentary drop of oil pressure in loading system; 2 hr 9 min, concrete fell from bottom of beam along north half, including most of haunch, in depth of 2- to 3-in. over full width, temporary large drop in oil pressure; 2 hr 27 min, some wires of prestressed cable exposed, apparently since 2 hr 9 min, concrete fallen from bottom edges in south half; 2 hr 36 min, load failure as beam settled down quickly; 2 hr 38 min, gas off.

The furnace control was good, the average temperature having been near that specified in the Standard Time-Temperature Curve throughout the test. The temperatures indicated by the six thermocouples in the concrete rose smoothly during the first 2 hr but those by two jumped quickly thereafter. The temperatures in the prestressed cable behaved in a similar manner, as shown in figure 10.

On the day following the test the beam had recovered partially from the maximum deflection and the beam and slab were cracked in several locations. They were cracked through or broken at center span. Concrete had fallen from the bottom to expose the lower side of the grouted cable duct over the north half including most of the haunch, and to expose much of the cable in the south, again including most of the haunch. Fifteen of the 24 wires in the cable were broken. Their locations are shown in figure 11. The condition of the beam is shown in figure 12.

4.4 Test 334-A:4/5:1

At 11 min there appeared to be a 4-in. diam pop-out in the vermiculite concrete; 47 min, a piece of vermiculite concrete, 4-in. long by 1/2-in. wide. hanging down near south end; 1 hr 49 min, full thickness of vermiculite concrete fell from bottom of beam at south end for 2 ft; 1 hr 59 min to 2 hr 1 min, repeated loud popping as concrete spalled

.

violently along 1 to 2 ft of beam and haunch in north, dislodging the vermiculite concrete; 2 hr 30 min, a few moist spots on top of slab, each 10 to 12-in. diam; 4 hr, loud thump and repeated popping as slab spalls away all but top 1 1/2 in. of depth along 2 ft of east edge north of center; 5 hr 39 min, loud metallic sound; 6 hr 2 min, test stopped, gas off.

The furnace control was good, the average temperatures being a little low only near the end of the test, and the temperatures in the beam and cable rose gradually and smoothly throughout the test, as shown in figure 13. Thermocouple  $P_1$  became inoperative at about 4 1/4 hr and  $P_4$  had been found to be inoperative in a pre-test check.

Upon being unloaded and cooling over the weekend, the beam recovered about one-third of the total deflection. The vermiculite concrete slabs were thoroughly cracked and the joints between had opened. The beam had spalled at each end and the slab in the north half on the east side, as shown in figure 14. The spalling had involved, or been caused by, splitting of the aggregate rather than loss of bond between aggregate and cement. This is shown in figure 15. The beam was subjected to a reloading test and failed under a load of about 65,180 lb (29.1 long tons), exclusive of the weight of the beam and slab. The beam and slab broke at the worst of the spall in the slab, about 2 ft north of center, exposing the cable from that location to the north end of the exposed length, as shown in figure 16. After the reloading test it was found that none of the prestressed wires was broken.

## 4.5 Test 335-E:4/5:0

During the first hour, the beam showed no fire effects other than reddening and some deflection; 1 hr 19 min, two full length cracks on east side of the beam, each about 1/8-in. wide, one 1 in. and the other 2 1/2 in. from bottom; 1 hr 24 min, at least 1 in. of concrete fell from bottom of beam, full width along central 8 ft; 1 hr 43 min, more concrete fell from north end; 1 hr 46 min, more concrete fell from south; 1 hr 55 min, pressure in loading system fell; 1 hr 55 1/2 min, beam collapsed; 1 hr 56 min, gas off.

The furnace control was fairly good, the average temperature being a little low during most of the test. The temperatures in the concrete and cable rose smoothly at first but jumped after 1 1/2 hr as shown in figure 17, probably due to cracking. Three of the thermocouples in the concrete became inoperative before the end of the test.

The beam had broken at three places, roughly the center and the quarter points. The cable was exposed over the central 14 to 15 ft but only two wires were broken, as indicated in figure 11. The concrete of the beam was much more "burned out" than in previous tests, and could be crumbled in the hand except that from the ends which had been in the protected supports.

## 4.6 Test 336-E:4/5:1

No fire effects other than reddening and deflection were observed until 51 min, when the joints between vermiculite concrete slabs appeared to have opened about 1/4 in.; 1 hr 28 min, joints slightly wider, possibly 1/2 in.; 1 hr 50 1/2 min to 1 hr 55 min, repeated loud popping and spalling of beam in north until vermiculite concrete slabs and some of beam down from bottom of north haunch and adjoining 1 ft of central section; 3 hr 30 min, no change since 2 hr except some loosened vermiculite concrete fell; 4 hr 29 min, loud thump, temporary drop in oil pressure; 4 hr 39 1/2 min, beam "sat down" in slow collapse; 4 hr 41 min, gas off.

The furnace control was good, the avenage temperature having been very near that specified by the Standard Time-Temperature Curve throughout the test. The temperatures in the concrete and cable rose smoothly and gradually, except that indicated by thermocouple P1 which jumped at about 4 hr, as shown in figure 18.

After test, the beam was found to have broken at the center of the span and a considerable amount of concrete was off the north half, exposing the cable. Twelve of the 24 wires in the cable were broken, the breaks having been about 4 ft north of where the beam broke. A large piece of concrete had sheared off the top, as shown in figure 19. The spalled areas showed shearing of the aggregate, as in the test of the A:4/5:1 beam.

#### 5. DISCUSSION

## 5.1 Size of Beam

The fire endurance of the A:1/2:0 beam (test 331) observed in this series of tests was about 91 percent of that of a similar beam in the previous British tests, the latter beam having been aged about one month longer, and was about 93 percent of that of a duplicate beam made and tested in England at the same time as the beam in test 331. This agreement was considered to be close enough to permit comparisons between the results obtained in this series and

those from the British Fire Research Station. The slight differences between the fire endurances may have resulted from differences in temperature and humidity conditions during aging.

The results obtained for the A: $\frac{1}{5}$ :0 beam (test 333) were about 10 percent lower than those anticipated from an extension of the linear relationship tentatively based on the results from England. As the beams tested by the Fire Research Station were of 1/4, 3/8 and 1/2 scales and those tested at the National Bureau of Standards of 1/2 and  $\frac{4}{5}$ scales (A:1/2:0 and A: $\frac{4}{5}$ :0), predictions of the fire endurance of a full scale beam involve an extrapolation equal to 36 percent of the total range of available test data. If it is assumed that the fire endurance is proportional to a linear dimension of the geometrically similar beams, the predicted value for a full-scale beam A:1:0 would depend somewhat upon the data used in making the extrapolation. Considering the data for the beams A:1/4:0, A:3/8:0 and A:1/2:0 originally tested by the Fire Research Station in England, the predicted value is about 3 hr  $\frac{4}{2}$  min; using only the data for the beams A:1/2:0 tested in Washington, it is 3 hr 20 min; and by giving equal weight to all available data, it is about 3 hr 24 min.

## 5.2 Concrete Cover to Cable

On the A and E type beams, the thickness of concrete on each side of the cable cavity was slightly less than that below, the difference having been 1/8 in. on the 1/2 scale and about 1/10 in. on the 4/5 scale. However, on the 4/5 scale D type beam, the concrete thickness was about 1/10 in. greater on the sides than the bottom. This leaves some question as to which thickness to consider; the bottom in all cases, the side, or whichever is least on each specimen. The orientation of the cable in the beam requires consideration of how extensive a "face" it presents to the heat penetrating the concrete. Since both sides of each beam were exposed, the sum of the two sides of the cable made a greater "face" than the bottom in all cases. However, the bottom concrete was subject to exposure from three sides and often showed evidence of greater heat damage than the sides, as evidenced by cracks, crumbling, and spalling. Therefore, the thickness of concrete below the cable appears to have been more significant than that on each side, so long as they were as nearly equal as in these test beams. The results obtained in the three tests of unprotected T-section beams (tests 331, 332, 333), when plotted as fire resistance vs thickness of concrete below the cable, gave points approximating a straight line. Interpolation on this line for the 4-in. thickness expected on a full scale type A beam gives 3 hr 20 min as the

predicted fire resistance for such a beam. Extrapolation along a line based on the results of the two A type beams, alone, would predict a resistance more nearly 3 3/4 hr. However, the lower value of 3 hr 20 min, having been determined by consideration of one more data point and by interpolation rather than extrapolation, should be more nearly correct.

The cracking and crumbling of the concrete mentioned above would become increasingly important at the larger scales. It would appear desirable and might prove necessary to incorporate some reinforcement in the concrete, such as a cage or basket of wire mesh located about 1 in. beneath the concrete surface. Such reinforcement should prevent loss of concrete.

## 5.3 Insulation

The 1-in. thick reinforced vermiculite concrete insulation used in two tests proved very effective in extending the period of fire resistance. The unprotected A:4/5:0 beam had failed at 2 hr 36 min whereas the insulated A: $\frac{1}{5}$ :1 beam withstood the fire exposure during the maximum period defined in BS476, 6 hours, without failure and, after cooling, re-tained strength to support a load up to 13,000 lb greater than that applied during the fire test. The ratio of fire resistance periods for the protected beam compared to the unprotected was 2.32/1. However, since the A:4/5:1 beam had not failed at the end of the test, this ratio would have been higher if the beam could have been tested to failure. Very similar results were obtained in the tests of the E:4/5:0 and E:4/5:1 beams (tests 335 and 336), respectively. In this case, however, both beams broke. The fire resistance of the former was 1 hr 56 min and of the latter was 4 hr 40 min. The ratio of fire resistance for the E:4/5:1 to that for the E:4/5:0 was 2.42/1 of the same order as that for the A beams. It is believed that about 1 1/4-in. thick vermiculite concrete would be required on full scale beams in order to give the same ratio between the fire resistances of protected and unprotected beams.

The only violent spalling observed in this series of tests occurred in the two tests of beams with insulation of l-in. reinforced vermiculite concrete. Each of these beams spalled explosively along the haunches and ends of the central section. Spalling near one end occurred in two of the four British tests of A-type beams with 1 in. of vermiculite concrete insulation but did not occur in any other tests, either with greater thicknesses of the same type of insulation or with no insulation. The spalling might have

been caused by stresses resulting from excessive local heating through cracks along the joints between adjacent vermiculite-concrete slabs at the transition from central section to haunch. It is also possible that the vermiculite concrete may have retarded the escape of excess moisture from the beams during curing. Previous observations during fire tests of dense concrete having high moisture content have indicated greater spalling than that observed during tests of more thoroughly dried specimens. Neither of the foregoing possible explanations is considered completely satisfactory; they are suggested, however, as possibilities.

## 5.4 Shape of Section

The difference between A and D type beams was largely one of thickness of concrete around the cable, as discussed in section 5.2. That between the A and E beams, however, was in the top slab's contact with the beam. Since the cover to the prestressed cable was the same in each type, this factor should not enter into any difference in fire resistance. The intimate contact between beam and slab in the A type was such that the top slab would dissipate heat from the concrete and assist in supporting the load. This assisting effect was of greatest importance late in the fire exposure as the concrete at the bottom of the beam lost strength. Loss of strength to a given depth in the concrete should require about the same time in each type but would represent a larger fraction of the total load bearing section in the type E beam than in the type A, thereby leading to the earlier failure of the former.

## 5.5 Cable Temperature

Of the six thermocouples in the prestressed cable, four were located at the center of the span. Although the temperatures of the prestressed wires measured during the tests may not have been the maxima over the full spans of the wires due to the small number of thermocouples and their concentration, the wire temperatures at which failure should be expected can be predicted from the results of a study made in England. The English data on the strength-temperature relationship for prestressed wire used in their beams indicates a 50 percent loss of strength at about 750° F (about 400° C). Similar data 1/ on steel for conventionally reinforced concrete

Mechanical Properties of Metals and Alloys, National Bureau of Standards Circular C447, Dec. 1,1943, pp.252-254.

.

•

shows a 50 percent loss of strength at 1000 to 1060°F (about 540 to 570°C). Thus if beams of the two types of construction are fabricated using a factor of safety of two in their designs and equal concrete cover, it would be expected that failure would occur in the prestressed beam at an earlier time during fire tests of the two beams.

The average and median temperatures of the prestressed wires measured at the time of failure in each test are given in table 3 as degrees F above the predicted 750° F.

Table	3.	Temperat	tur	es at	Fail	ure,
		degrees	F	above	750°	F

Beam	Average	<u>Median</u>
A:1/2:0	-140	-142
A:4/5:0	+ 38	-124
D:4/5:0	+319	+322
E:4/5:0	+ 11	-277
A:4/5:1	-52*	- 95*
E:4/5:1	-239	-248

\* Temperature at end of 6 hr exposure without failure.

The fact that these temperatures were lower than expected in most cases indicates that the wires in the prestressed cables were heated to failure at locations somewhat removed from the central location of the thermocouples. Examination of the beams after the tests showed that most of the breaks and drawnout sections in the wires were at least 1 ft from the thermocouple junctions.

## 5.6 Deflections

The curves of deflections versus time in figure 20 show large early deflections followed by a steady state period for the unprotected beams, but a slow more or less uniform increase of deflection for the insulated beams. This effect is believed to be one of differential thermal expansion. As the concrete at the beam soffit, and the bottom of the slab of an A or D beam, is heated rapidly at the start of the fire exposure it expands while the concrete in the interior of the beam and the top of the slab remains cool and does not expand. In these beams of high strength concrete, a bowing toward the hot surface resulted. For the  $E:\frac{4}{5}:0$ 

beam, the effect was of reduced magnitude since the separate top slab would not offer much restraint against the expansion of the upper surface of the beam. The vermiculite-concrete insulation prevented the rapid heating of the beam soffit, thereby diminishing the tendency for large deflections after the initial fire exposure.

### 6. SUMMARY

These tests provide data which, coupled with the data from tests at the British Fire Research Station, provide the basis for a linear relationship between fire resistance and scale of geometrically similar A type beams by which the fire resistance of full scale A beams may be predicted. This relationship may be expressed as:

$$R_{\rm H} = 218 \, {\rm S} - 14$$

where  $R_F$  is fire resistance in minutes and S is scale. For an A:1:0 beam (S = 1), this formula gives a predicted  $R_F$  of 3 hr 2µ min. In view of the range of data, S should not be taken greater than unity. The D and E type beams were tested only at 4/5 scale so no relationship may be proposed.

The thickness of the concrete cover over the reinforcing cable is one of the several variables which affect the fire resistances of prestressed beams. The results of these tests indicate it may be one of the most important. The D:4/5:0 beam had 4.4 in. cover and a fire resistance of 3 hr 40 min, the A:4/5:0 beam with 3.0 in. cover had a fire resistance of 2 hr 36 min, and the A:1/2:0 beam with 2 in. cover had a fire resistance of 1 hr 29 min. An A:1:0 beam, with 4-in. cover would be between the first two and would be expected to have a fire resistance of 3 hr 20 min on the basis of cover thickness. With the thick covers of 3 in. and more it would appear advisable to include some light reinforcement such as wire mesh not more than 1 in. from the concrete surface to prevent the loss of concrete during fire exposure.

The use of vermiculite concrete well bonded to the structural concrete, as when used as a form liner for the latter, will greatly increase the fire resistance which may be expected from a given size beam. The use of 1 in. of vermiculite concrete on 4/5 scale A and E beams gave 2 1/3 to 2 1/2 times the fire resistance of the unprotected beams and might be expected to give at least 2 times the fire resistance when used on A:1 and E:1 beams. Although beams so protected showed a tendency to spall violently, which was not shown by the other beams, this tendency is more than offset by the increased fire resistance.

.

.

	Age Tensile	test of wires	da lb/in. <sup>2</sup>	238 284,500	223 255,400	256 250,900	262 255,400	262 24,8,600	267 255,400
	e strength of s at test age	: Slab	b/in. <sup>2</sup>		7980	9020	9310	1	8
	: Compressiv : 6-in. cube	Beam	11		8630	9240	9350	7410	8790
	strength of at 28 days	Slab	b/in. <sup>2</sup>	5980	0979	0†69	0102	- 1	1
	Compressive 6-in.cubes	Beam		6810	6390	7070	2000	6070	7210
	: Symbol			A:1/2:0	D:4/5:0	A:4/5:0	A:4/5:1	E:4/5:0	E:4/5:1

Table 4. Physical Data for Construction Materials.

Table 5. Results of Cold Loading Tests on Beams.

The following results were obtained in tests of beams similar to those subjected to fire tests. The data were obtained in England

•• ••							
in cable	lb/in. <sup>2</sup>	284,500	253,100	257,600	253,100	255,400	
•• ••							
Slab	n. <sup>2</sup>	0016	5980	6100	1	1	
•• ••	īb∕i						
Beam		9100	0699	7280	7630	6510	
••••		0	0	0	0	0	
Failur		48,20	112,70	115,40	51,50	47,00	
ack		0		0	0	0	
rst cr		27,600	65,900	62,300	31,600	29,800	
E H				6			
test	ರೆಡ	108	07	39	210	48	
beam		A:1/2	A:4/5	D:4/5	E:4/5	E:4/5	
	beam : test: First crack ; Failure : Beam ; Slab ; in cable	beam : test: First crack : Failure : Beam : Slab : in cable : da da da lb/in. <sup>2</sup> lb/in. <sup>2</sup>	<pre>beam : test: First crack : Failure : Beam : Slab : in cable da A:1/2 108 27,600 48,200 9100 9100 284,500</pre>	beam : test: First crack : Failure : Beam : Slab : in cable   da in cable : in cable : in cable : in cable   A:1/2 108 27,600 48,200 9100 9100 284,500   A:4/5 40 65,900 112,700 6690 5980 253,100	beam : test: First crack Failure : Beam : Slab : in cable   da id ib/in. <sup>2</sup> ib/in. <sup>2</sup> ib/in. <sup>2</sup> A:1/2 108 27,600 48,200 9100 284,500   A:1/5 40 65,900 112,700 6690 5980 253,100   D:4/5 39 62,300 115,400 7280 6100 257,600	beam test first crack Failure Eam is lab is lab in cable in cable da da $1b/in.^2$ $1b/$	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$

18.

\* Includes weight of beam

.

•









## FIG.I DIMENSIONS OF TEST BEAMS

TYPES A&D	TYPE E
SECTIONS THROU OF SPA	IGH CENTER

8

			-	IN INCHES	-	
	түре	-	Α	A	D	E
5	SCALE	Ξ-	2	**5	**5	⁴⁄5
	L	-	126	201.6	201.6	201.6
	F	-	7	11.2	11.2	11.2
	G	-	6	9.6	9.6	9.6
	Η	-	20	32	32	32
	J	-	60	96	96	96
	5	-	20	32	32	_
	A	-	3	4.8	4.8	-
	В	-	5	8	12	8
	С	-	10	16	16	16
	D	-	9	14.4	15.4	14.4
	E	-	11	17.6	17.6	17.6
	R	-	3	4.5	5.5	4.5
	X	_	1.25	2.16	2.95	2.16
	Y		2	2.95	2.16	2.95

DIMENSIONS OF TEST\_SPECIMENS

+G· . F



-G÷



L

SIDE ELEVATION





TYPES A&E % BEAMS

- CONCRETE - CI TO C6 AT CENTER OF BEAM

CABLE-WI TO W4 AT CENTER OF BEAM W5 & W6 4 FT. FROM CENTER OF BEAM

☆ INSULATION - PI TO P4 FOR TYPE"A" PI TO P3 FOR TYPE"E" ALL AT CENTER OF BEAM

4



TYPE A 2 BEAM

-CONCRETE - CI TO C6 AT CENTER OF BEAM

• CABLE -WI TO W4 AT CENTER OF BEAM W5 & W6 2 لم FT. FROM CENTER OF BEAM



-CONCRETE-CI TO C6 AT CENTER OF BEAM

© CABLE -WI TO W4 AT CENTER OF BEAM W58 W6 4 FT. FROM CENTER OF BEAM

#### FIG.3 THERMOCOUPLE LOCATIONS IN BEAMS





FIG.4 LOADING APPARATUS IN PLACE BEFORE TEST



FIG.5 TEMPERATURES OBSERVED DURING TEST 331





FIG.6 A:1/2:0 BEAM AFTER FIRE TEST 331



FIG. 7 A:1/2:0 BEAM AFTER FIRE TEST 331 AND RELOADING TEST





FIG.8 TEMPERATURES OBSERVED DURING TEST 332. TEST STOPPED BEFORE ALL 3 HR,40MIN. TEMPERATURE OBSERVATIONS COMPLETED



FIG.9, D:4/5:0 BEAM AFTER FIRE TEST 332, SHOWING BREAKS IN SLAB, BEAM, AND CABLE, THE LATTER GROUPED IN TWO LOCATIONS.





TEST 331 - 1/2 SCALE TYPE A - NONE BROKEN TEST 332 - 4/5 SCALE TYPE D - ALL BROKEN TEST 334 - 4/5 SCALE TYPE A WITH VERMICULITE CONCRETE-NONE BROKEN

X-BROKEN 333 /5 SCALE TYPE A	O- UNBROKEN 335 4/5 SCALE TYPE E
0000	хооо
хооо	0000
X	0000
X X X X	0000
хохх	0000
ххох	0 0 0 X

4

336 4/5 SCALE TYPE E WITH VERMICULITE CONCRETE X 0 0 0 X X 0 X





FIG. 12 A: 4/5:0 BEAM AFTER FIRE TEST 333



FIG. 13 TEMPERATURES OBSERVED DURING FIRE TEST 334





FIG. 14 A: 4/5:1 BEAM AFTER FIRE TEST 334



FIG. 15 REPRESENTATIVE SPALLED AREA (SLAB) FROM TEST OF  $A_1 \frac{4}{5}$  I BEAM



FIG. 16 NORTH HALF OF A: 4/5:1 BEAM AFTER FIRE TEST 334 AND RELOADING TEST



## FIG. 17 TEMPERATURES OBSERVED DURING TEST 335



FIG. 18 TEMPERATURES OBSERVED DURING TEST 336



FIG. 19 E:4/5:1 BEAM FROM ABOVE AFTER FIRE TEST 336 SHOWING SHEAR FAILURE AT TOP







×

#### THE NATIONAL BUREAU OF STANDARDS

#### **Functions and Activities**

The functions of the National Bureau of Standards are set forth in the Act of Congress, March 3, 1901, as amended by Congress in Public Law 619, 1950. These include the development and maintenance of the national standards of measurement and the provision of means and methods for making measurements consistent with these standards; the determination of physical constants and properties of materials; the development of methods and instruments for testing materials, devices, and structures; advisory services to Government Agencies on scientific and technical problems; invention and development of devices to serve special needs of the Government; and the development of standard practices, codes, and specifications. The work includes basic and applied research, development, engineering, instrumentation, testing, evaluation, calibration services, and various consultation and information services. A major portion of the Bureau's work is performed for other Government Agencies, particularly the Department of Defense and the Atomic Energy Commission. The scope of activities is suggested by the listing of divisions and sections on the inside of the front cover.

#### **Reports and Publications**

The results of the Bureau's work take the form of either actual equipment and devices or published papers and reports. Reports are issued to the sponsoring agency of a particular project or program. Published papers appear either in the Bureau's own series of publications or in the journals of professional and scientific societies. The Bureau itself publishes three monthly periodicals, available from the Government Printing Office: The Journal of Research, which presents complete papers reporting technical investigations; the Technical News Bulletin, which presents summary and preliminary reports on work in progress; and Basic Radio Propagation Predictions, which provides data for determining the best frequencies to use for radio communications throughout the world. There are also five series of nonperiodical publications: The Applied Mathematics Series, Circulars, Handbooks, Building Materials and Structures Reports, and Miscellaneous Publications.

Information on the Bureau's publications can be found in NBS Circular 460, Publications of the National Bureau of Standards (\$1.00). Information on calibration services and fees can be found in NBS Circular 483, Testing by the National Bureau of Standards (25 cents). Both are available from the Government Printing Office. Inquiries regarding the Bureau's reports and publications should be addressed to the Office of Scientific Publications, National Bureau of Standards, Washington 25, D. C.

